

## MOTOR VEHICLES AND ROAD TRAFFIC ACT

### CHAPTER 48:50

**Act  
42 of 1934**

Amended by

2 of 1936	12 of 1961	†8 of 1978	9 of 1990	48/2014
10 of 1937	11 of 1963	17 of 1978	4 of 1992	*2 of 2015
37 of 1938	2/1963	19 of 1978	6 of 1992	1 of 2016
28 of 1944	21/1963	20 of 1978	6 of 1993	7 of 2016
34 of 1944	32 of 1964	†21 of 1978	3 of 1994	18/2016
24 of 1945	11 of 1965	28 of 1978	226/1994	47/2016
13 of 1946	27/1966	14 of 1979	5 of 1995	61/2016
40 of 1946	36 of 1967	47 of 1980	8 of 1996	*9 of 2017
2 of 1948	2/1968	185/1980	9 of 1997	14 of 2017
33 of 1948	6/1968	2 of 1982	*25 of 1997	*15 of 2017
10 of 1949	15 of 1968	8 of 1982	35 of 1998	117/2017
37 of 1949	3 of 1969	146/1982	21 of 2000	4 of 2020
30 of 1951	146/1969	3/1983	22 of 2000	*10 of 2020
32 of 1951	2/1973	20 of 1983	2 of 2002	*15 of 2020
2 of 1952	11/1974	157/1983	*19 of 2007	*20 of 2020
30 of 1952	13/1974	4/1985	30 of 2007	*26 of 2020
47 of 1952	27/1974	23/1985	1 of 2009	*30 of 2020
20 of 1953	6 of 1974	198/1985	8 of 2009	*16 of 2021
47 of 1956	5 of 1975	1 of 1986	5 of 2010	19/2022
35 of 1957	6/1975	3/1986	13 of 2010	109/2022
197/1957	31 of 1976	17 of 1986	2 of 2013	*6 of 2023
115/1958	6 of 1977	*11 of 1988	5 of 2013	245/2024
11 of 1959	44 of 1977	37 of 1989	12 of 2014	

(\*See Notes on pages 4 and 5)

(†This Act was validated by Act No. 21 of 1978)

**Current Authorised Pages**

<i>Pages</i>	<i>Authorised</i>
<i>(inclusive)</i>	<i>by L.R.O.</i>
1-490	..

**Index of Subsidiary Legislation**

	<i>Page</i>
Motor Vehicles and Road Traffic Regulations (G 1.6.44) ... ..	158
Safety Helmets Notification (GN 137/1978) ... ..	294
Special Speed Limits Order (GN 210/1979) ... ..	295
Speed Limits (Built-Up Areas) Order (GN 209/1979) ... ..	297
Special Speed Limits (Bridges) Order (GN 46/1957) ... ..	304
Road Traffic (Prohibited Parking) Order (GN 206/1979) ... ..	305
Miscellaneous Roads (Unilateral Parking) Order (GN 207/1979) ... ..	314
Miscellaneous Roads (Unilateral Alternate Parking) Order (GN 208/1979) ... ..	321
Private Motor Cars (Parking Places) Order (GN 214/1979) ... ..	337
Public Stands (Taxis) Parking Order (GN 212/1979) ... ..	341
Public Stands (Motor Omnibuses) Parking Order (GN 213/1979) ... ..	350
Goods Vehicles Stands Parking Order (GN 215/1979) ... ..	353
Parking on Dual Carriage-ways Order (GN 216/1979) ... ..	354
Queen's Park Savannah Parking Order (GN 73/1966) ... ..	355
Independence Square (Parking of Vehicles) Order (GN 220/1979) ... ..	356
South Quay (Parking of Vehicles) Order (GN 219/1979) ... ..	357
Broadway (Parking of Vehicles) Order (GN 218/1979) ... ..	359
One-Way Traffic Order (GN 211/1979) ... ..	360
Eastern Main Road Traffic Order (GN 58/1976) ... ..	372
Beetham Highway Order (GN 60/1976) ... ..	373
Restriction of Parking (Public Buildings) Order (GN 56/1963) ... ..	374
Public Stand (Maxi-Taxi) Parking Order (LN 141/1981) ... ..	375
Traffic Restriction (Queen's Park Savannah Reticulation) Order (LN 147/1981) ... ..	377
Traffic Restriction (San Fernando) Order (LN 152/1981) ... ..	382
Notice of Exemption from Requirement to hold a Driver's Permit issued in a Foreign Country (LN 242/1986) ... ..	385
Traffic Control Regulations (LN 90/1993) ... ..	389
Motor Vehicles (Seat Belt Assemblies) Regulations (LN 210/1994) ... ..	400
Traffic Signs and Pedestrian Crossings Order (LN 1/1993) ... ..	405
Traffic Control Taxi Stand Location Order (LN 113/1988) ... ..	425
Port-of-Spain Transit Centre (Taxi Stand) Order (LN 226/1997) ... ..	431
Port-of-Spain Transit Centre (Public Service Vehicle Station) Regulations (LN 227/1997) ... ..	437
Priority Bus Route (Traffic Control) Order (LN 99/1988) ... ..	449
Priority Bus Route (Special Roads Toll) Regulations (LN 75/1988) ... ..	452

**Index of Subsidiary Legislation—Continued**

	<i>Page</i>
Motor Vehicles and Road Traffic (Approval of Device for Quantitative Measuring of the Proportion of Alcohol in a Person’s Breath) Order (LN 266/2009)	454
Motor Vehicles and Road Traffic (Approval of Device for Obtaining an Indication of Alcohol in a Person’s Breath) Order (LN 267/2009) ...	455
Motor Vehicles and Road Traffic (Mobile Devices) Regulations (LN 281/2010)	457
Motor Vehicles and Road Traffic (Speed Measuring Device) Order (LN 60/2016)	460
Motor Vehicles and Road Traffic (Speed Measuring Device) Order (LN 142/2017)	460
Motor Vehicles and Road Traffic (Fixed Penalty Payment Methods and Payee) Order (LN 101/2020) ... ..	461
Motor Vehicles and Road Traffic (Windscreen and Window Tint) Regulations (LN 281/2020) ... ..	464
Motor Vehicles and Road Traffic (Persons with Disability Parking Permit) Regulations (LN 66/2024) ... ..	482

**Note on Legal Notice No. 197/1999**

A. (1) Regulation 3(k) of the Motor Vehicles and Road Traffic (Amendment) Regulations, 1999 (LN 197/1999) inserted the following Part, *viz.*, “PART II—Authorised Examiners and Premises” .

(2) The Motor Vehicles and Road Traffic Regulations already contained a Part II and the new Part II *viz.*, “PART II—Authorised Examiners and Premises”, inserted by LN 197/1999 was renumbered as “Part VA”.

B. Legal Notice No. 197/1999 was validated by Act No. 9 of 2001.

**Note on Delegation of Functions Orders**

See LN 114/2019 and LN 4/2024.

**Note on Omissions**

The following Subsidiary Legislation have been omitted:

- (a) The Motor Vehicles and Road Traffic (Exemption from payment of Registration Fee) Order, 1991 [LN 35/1991 (*made under section 16(2) of the Act*)].
- (b) The Remittance of Transfer Tax on Motor Vehicles (BWIA International Airways Limited) Order, 1995 (LN 65/1995) (*made under section 19E of the Act*).
- (c) Traffic Control Orders (*made under section 65 of the Act*).

- (d) Traffic Control (Experimental Scheme) Regulations (*made under section 67 of the Act*).
- (e) Traffic Restrictions (Temporary Provisions) Orders (*made under section 68 of the Act*).
- (f) Motor Vehicles and Road Traffic (Extension of Time) Orders (*made under section 19 of the Act*).
- (g) Motor Vehicles and Road Traffic (Extension of Time for the Validity of Certain Documents) Orders (*made under section 61B of the Act*).
- (h) Motor Vehicles and Road Traffic (Extension of Period for Payment of Fifty Per Cent of Fixed Penalty) Orders (*made under section 50(4) of the Act*).

***For references to the above Subsidiary Legislation—See the Current Edition of the Consolidated Index of Acts and Subsidiary Legislation of Trinidad and Tobago.***

#### **Note on Application**

(1) Section 10 of the Motor Omnibus Concessions (Acquisition of Undertakings) Act, 1964 (Act No. 32 of 1964) provided that nothing contained in section 100 of this Act or any Regulations made thereunder which relates to the granting or operation of concessions shall apply to motor omnibuses operated by Government under that Act (i.e., Act No. 32 of 1964).

(2) The United States Defence Area (Agreement) Ordinance, 1961 (Ord. No. 12 of 1961) (*See in particular sections 7, 8, 9, 11 and 17*) grants certain exemptions from the provisions of this Act.

#### **Note on Metrication**

In this Chapter the laws have been metricised. [*See paragraph 12 of the Second Schedule to the Law Revision Act (Chap. 3:03) and LN 185/1980*].

#### **Note on Act No. 11 of 1988**

*See section 27 of Act No. 11 of 1988 for validation of charges for certain vehicle licences.*

#### **Note on Act No. 25 of 1997**

*See section 45 of Act No. 25 of 1997 for validation of acts and things purported to be done between 1st October 1996 and 16th September 1997.*

#### **Note on Act No. 19 of 2007**

By Act No. 19 of 2007 sections 70A, 70B, 70C, 70D, 70E, 70F, 70G and 70H took effect from 16th November 2009 (*See LN 237/2009*).

#### **Note on Regulation 28**

Section 66 of the Emergency Ambulance Services and Emergency Medical Personnel Act, Chap. 29:02 amended regulation 28 of this Act by inserting subregulations 28(2), (3) and (4).

**Note on Act No. 2 of 2015**

Amendments made to the Fourth Schedule by Act No. 2 of 2015 took effect on 1st January 2015.

**Note on Act No. 9 of 2017**

(1) The Motor Vehicle and Road Traffic (Amendment) Act, No. 9 of 2017 took effect on 26th May 2020 by LN 100/2020.

(2) The Motor Vehicles (Enforcement and Administration) Act, Chap. 48:52 was repealed by Act No. 9 of 2017.

**Note on Act No. 15 of 2017**

Amendments made to the Fourth Schedule by Act No. 15 of 2017 took effect on 1st January 2018.

**Note on Act No. 10 of 2020**

Amendments made to this Act by Act No. 10 of 2020 took effect on 11th May 2020 by LN 92/2020. Act No. 10 of 2020 amended Act No. 9 of 2017 by inserting Section 50 which deals with the discharge of liability in relation to fixed penalties made under the repealed Motor Vehicles (Enforcement and Administration) Act, Chap. 48:52.

**Note on Act No. 15 of 2020**

Sections 7, 10–16, 18–23, 25 and 26 of Act No. 15 of 2020 took effect on 23rd June 2020 by LN 136/2020.

**Note on Act No. 20 of 2020**

Amendments made to this Act by Act No. 20 of 2020 took effect on 21st July 2020 by LN 275/2020.

**Note on Act No. 26 of 2020**

Amendments made to this Act by Act No. 26 of 2020 took effect on 22nd December 2020 by LN 410/2020.

**Note on Act No. 30 of 2020**

Amendments made to this Act by Act No. 30 of 2020 took effect on 1st January 2021.

**Note on Act No. 16 of 2021**

Amendments made to this Act by Act No. 16 of 2021 took effect on 1st January 2022.

**Note on Act No. 6 of 2023**

Amendments made to this Act by Act No. 6 of 2023 took effect on 20th June 2023 by LN 174/2023.

**CHAPTER 48:50**

**MOTOR VEHICLES AND ROAD TRAFFIC ACT**

ARRANGEMENT OF SECTIONS

SECTION

1. Short title.

**PART I  
GENERAL**

2. Interpretation.
- 2A. Non-application of section 64 of Interpretation Act. Ch. 3:01.
3. Trinidad Transport Board.
4. Appointment of Transport Commissioner, Assistant Transport Commissioner, etc.
- 4A. Minister to approve forms, certificates and procedures for registration of vehicles.
5. Transport Officers to have powers, etc., of members of the Police Service.
6. Precept of appointment.
7. Equipment.
8. *(Repealed by Act No. 25 of 1997).*
9. Penalty for assaulting or obstructing Transport Officer.
10. Power to stop and inspect vehicles.
- 10A. Appointment and functions of a Traffic Warden.

**PART II  
REGISTRATION OF MOTOR VEHICLES**

11. Motor vehicle registers.
12. Registration of motor vehicles.
13. Examination of motor vehicles.
14. Motor vehicles tax.
15. Cancellation of registration.
16. Exemptions from need for registration.  
Exemption from payment of registration fee.
17. Restriction on registration of taxis.
- 17A. Restriction on registration of motor vehicles.
18. Registration on change of use.
19. Transfer of registration.
- 19A. Tax payable on transfer of motor vehicle.
- 19B. Payment of transfer tax.

SECTION

- 19C. Evidence of sale or date of transfer.
- 19D. Age of motor vehicle.
- 19E. Refund of transfer tax.
- 19F. Exemption.
- 19G. *(Repealed by Act No. 9 of 1997).*
- 20. Interpretation.

**PART IIA**  
**TRAFFIC VIOLATIONS**

- 20A. Conditions of permit and registration.
- 20B. Commission of a traffic violation.
- 20C. Standard of proof.

**PART III**  
**LICENSING OF MOTOR VEHICLES**

- 21. Using vehicle without prescribed registration, an offence.
- 22. Licensing Authority may permit goods vehicles to be used for the conveyance of persons.
- 22A. Police and Prison Service vehicles exempted from payment of fees.
- 23. Restrictions on licensing of certain motor vehicles and trailers.
- 24. *(Repealed by Act No. 9 of 1997).*
- 25. Conditions to be satisfied before licence issued.
- 26. Licensing Authority may designate premises.
- 27. Cancellation or refusal of registration.
- 28. Amendment of Register and Certificate of Registration.
- 29. )
- to } *(Repealed by Act No. 9 of 1997).*
- 33. }
- 34. Dealers' general licence.
- 35. Uses of dealers' general licence.
- 36. Register of dealers' general licences.
- 37. Cancellation of dealers' general licence.
- 38. Dealers' general licence not transferable.
- 39. Dealer to accompany vehicle when used.
- 40. Record of vehicles used under authority of dealers' general licence.  
Record of hire of rented cars.
- 40A. *(Repealed by Act No. 37 of 1989).*
- 41. International certificates and temporary licences for motor vehicles.
- 41A. Special permit for private school bus.

ARRANGEMENT OF SECTIONS—*Continued*

SECTION

PART IV

**DRIVING PERMITS**

- 42. Driving without a permit, an offence.
- 43. Motorcycles and safety helmets.
- 43A. Private motor cars and certain other vehicles to be fitted with seat belts.
- 43B. Certain motor vehicles to be equipped with seat belts.
- 43C. Wearing of seat belts compulsory.
- 43D. Driving while a child is in the vehicle.
- 44. Issue of driving permits.  
Fees.
- 45. Driving instructors.
- 46. Offences of driving instructor.
- 47. Driving tests.
- 48. Physical fitness.
- 49. Applications for driving permits.
- 50. Classes of vehicles.
- 51. Restrictions on driving permits for certain vehicles.
- 52. Age.
- 53. Driving test fees.
- 54. Colour classification of driving permits and provisional permits.
- 55. International driving permits.
- 56. Production of driving permit or provisional permit.
- 56A. Exemption in case of valid driving permit held elsewhere.
- 57. Register of driving permits.
- 58. Period of driving permit.
- 59. Expiration of provisional permit.
- 60. Re-issue of lost or defaced driving permit.
- 61. Restrictions on the issue of new driving permit after expiration of former one.
- 61A. Expired driving permit.
- 61B. Continuation of validity.

PART V

**DRIVING AND OTHER OFFENCES  
AND GENERAL CONDITIONS RELATING  
TO THE USE OF ROADS**

- 62. Speed limits.
- 62A. Prohibition on devices designed to detect speed measuring devices.
- 63. Motor racing and speed trials.

**SECTION**

- 64. Traffic signs.
- 65. Parking of vehicles and one-way roads.
- 66. Drivers to comply with traffic directions.
- 66A. Failure to comply with a traffic light.
- 67. Experimental traffic schemes.
- 68. Temporary prohibition or restriction of traffic on roads.
- 69. Restrictions on parking in certain streets.
- 70. Driving when under influence of liquor.  
Disqualification from driving upon conviction.
- 70A. Driving or being in charge of a vehicle while blood alcohol levels exceed prescribed limit.
- 70B. Breath test.
- 70C. Breath analysis.
- 70D. Laboratory test.
- 70E. Refusal to consent to taking of or providing specimen.
- 70F. Ancillary provisions as to evidence in proceedings for an offence under section 70A or 70B.
- 70G. Interpretation of sections 70A to 70F.
- 70H. Regulations.
- 71. Causing death by dangerous driving.
- 71A. Dangerous driving.
- 71B. Interpretation.
- 72. Careless driving.
- 73. Warning to be given of intended prosecution.
- 74. Taking vehicle without consent of owner.
- 75. Interfering with motor vehicle.
- 76. Restrictions on persons being towed on bicycles.
- 77. Restriction on cyclists riding abreast or holding on to other moving vehicles.
- 78. Distribution of advertisements from vehicles prohibited.
- 79. Duty to stop, give aid, and report in case of accident.

**PART VA**

**RED-LIGHT CAMERA SYSTEM**

- 79A. Definitions.
- 79B. Installation of red-light camera.
- 79C. Unlawful interference.
- 79D. Owner deemed responsible.

ARRANGEMENT OF SECTIONS—*Continued*

SECTION

- 79E. Photographic image or video recording captured by red-light camera system.
- 79F. Preparation of citation notice.
- 79G. Form of citation notice.
- 79H. Service of citation notice.
- 79I. Payment of fixed penalty.
- 79J. Filing of notice of contest.
- 79K. Proceedings for traffic violation under section 66A.
- 79L. Transmission of documents to Court.
- 79M. Certificate of Inspection Officer.
- 79N. Certificate of Commissioner of Police.
- 79O. Evidence of condition of red-light camera.
- 79P. No Complainant in proceedings.
- 79Q. Magistrate to proceed *ex parte* where owner is absent.
- 79R. Non-payment of fixed penalty and failure to file notice to contest.
- 79S. Notice to owner of possible sanctions.
- 79T. Imposition of sanctions by Licensing Authority.

PART VI

**FIXED PENALTY ENFORCEMENT  
AND ADMINISTRATION**

- 80. Definitions.
- 81. Constable may issue fixed penalty notice.
- 82. Contents of fixed penalty notice.
- 83. Payment of fixed penalty.
- 84. Amount of fixed penalty.
- 84A. Referral to a child traffic counselling programme.
- 84B. Attendance at a child traffic counselling programme.
- 85. Notice to contest to be filed.
- 86. Transmission of documents to Court.
- 87. Listing of proceedings in respect of fixed penalty notice.
- 87A. Temporary suspension of permit pending determination of charge.
- 88. Appearance of parties in proceedings where notice to contest was filed.
- 88A. Non-payment of fixed penalty and failure to file notice to contest.

- 88B. Notice to driver or owner of possible sanctions.
- 88C. Imposition of sanctions by Licensing Authority.
- 88D. Minister may by Order prescribe fixed penalty traffic violations.

**PART VIA**

**LEGAL PROCEEDINGS, DEMERIT POINTS,  
SUSPENSION AND CANCELLATION OF  
DRIVING PERMITS**

- 88E. Power to convict for reckless or dangerous driving on trial for manslaughter.
- 88F. Power to proceed on charge for careless driving on hearing of charge under section 70 or 71A.
- 88G. Power of Court to require a suspended permit be produced.
- 88H. Right of appeal.
- 88I. Production of offender's Record of Conviction.
- 88J. Establishment of Demerit Points Register.
- 88K. Demerit points.
- 88L. Simultaneous traffic violations.
- 88M. Accumulation of demerit points and disqualification.
- 88N. Reissue of driving permit after disqualification.
- 88O. Demerit points to be expunged after two years.
- 88P. Double demerit points.
- 88Q. Fraudulent application for driving permit.

**PART VII**

**GENERAL**

- 89. Fees and duties.
- 89A. *(Repealed by Act No. 9 of 1997).*
- 90. Fraudulent imitation, etc., of documents.
- 91. Offences and general penalty.
- 92. Liability at Common Law.
- 93. Refusing to give name or address or giving false name or address.
- 94. Giving false information.
- 95. Duplicate licences, permits and certificates.
- 96. Liability of driver and person in charge of vehicle for offences.
- 97. Power to require motor vehicles licensed according to M.G.W. to be weighed.
- 98. Recovery of damage to road or bridge.

ARRANGEMENT OF SECTIONS—*Continued*

**SECTION**

- 99. Certificate as to damage to be admissible in evidence.
- 100. Regulations.
- 101. *(Repealed by Act No. 25 of 1997).*
- 102. Regulation of conduct of drivers and conductors.
- 103. Regulation of conduct of passengers.
- 104. Control of number of passengers.
- 105. Control of bus terminals and coach stations.
- 106. Offences in connection with Regulations.
- 106A. Rules and Practice Direction for traffic matters.
- 107. Parking in grounds, etc., of public officers restricted.
- 108. Powers of police where vehicles parked in contravention of Act or left on road.
- 109. Charges payable before delivery of vehicle; and sale of vehicles in custody.
- 110. In the event of a conflict of laws, the provisions of this Act to prevail.  
Where similar powers are granted under this and any other law the Board shall decide as to the exercise of those powers.
- 111. Highway Code.

**FIRST SCHEDULE.**

**SECOND SCHEDULE.**

**THIRD SCHEDULE.**

**FOURTH SCHEDULE.**

**FIFTH SCHEDULE.**

**SIXTH SCHEDULE.**

**SEVENTH SCHEDULE.**

**EIGHTH SCHEDULE.**

**NINTH SCHEDULE.**

---

**CHAPTER 48:50**

**MOTOR VEHICLES AND ROAD TRAFFIC ACT**

**An Act relating to Motor Vehicles and Road Traffic.**

[1ST JANUARY 1935]

1950 Ed.  
Ch. 16, No. 3.  
42 of 1934.  
Commencement.

1. This Act may be cited as the Motor Vehicles and Road Traffic Act. Short title.

**PART I  
GENERAL**

2. In this Act—
- “agricultural tractor” means a tractor approved by the Licensing Authority exclusively for agricultural purposes; Interpretation.  
[20 of 1953  
47 of 1956  
35 of 1957  
11 of 1963  
36 of 1967  
3 of 1969  
8 of 1978  
14 of 1979  
8 of 1982  
11 of 1988  
9 of 1997  
25 of 1997  
21 of 2000  
5 of 2010  
2 of 2013  
1 of 2016  
9 of 2017].
- “agricultural trailer” means a trailer approved by the Licensing Authority exclusively for agricultural purposes;
- “approved form” means the form approved under section 4A of the Act;
- “Assistant Transport Commissioner”, “Automotive Licensing Officer”, “Motor Vehicles Officer” and “Motor Vehicles Supervisor” mean, respectively, any persons carrying out the provisions of this Act relating to the licensing, registration and examination of vehicles;
- “Board” means the Trinidad Transport Board;
- “Borough of Arima” means the Borough of Arima as defined in the First Schedule to the Municipal Corporations Act; Ch. 25:04.
- “certificate” means the certificate approved under section 4A of the Act;
- “citizen of Trinidad and Tobago” has the meaning assigned in section 2 of the Immigration Act; Ch. 18:01.
- “City of Port-of-Spain” means the City of Port-of-Spain as defined in the First Schedule to the Municipal Corporations Act;
- “City of San Fernando” means the City of San Fernando as defined in the First Schedule to the Municipal Corporations Act;

“driver” includes any person actually driving a motor vehicle at any given time and any person in charge thereof for the purpose of driving whenever the same is stationary on any road;

“driving permit” means a permit issued in accordance with Part IV kept in the form specified in section 54;

“emergency vehicle” means—

- (a) a vehicle being used by a member of the Police Service, Prison Service or Defence Force; or
- (b) an ambulance being operated,

in an emergency situation while sounding its siren or other warning instrument approved by the Licensing Authority;

“freight passenger vehicle” means a motor vehicle constructed for the purpose of carrying both passengers and goods and which is approved by the Licensing Authority as suitable for that purpose;

“goods vehicle” means a motor vehicle other than an agricultural tractor or industrial tractor which is so constructed or adapted as to show its primary purpose is the carriage or haulage of goods, merchandise or other loads, and includes—

- (a) a motor vehicle constructed or adapted for the carriage both of persons and of goods and which is registered for use as a goods vehicle;
- (b) a motor vehicle which is registered for use as a goods vehicle and which was so registered before 1st January 1963;

“hiring car” or “taxi” means a public service vehicle having seating accommodation for not more than eight passengers and which is of a type approved by the Licensing Authority as suitable for the ordinary purposes of a taxi;

“indivisible load” means a load which cannot without undue expense or risk of damage be divided into two or more loads for the purpose of conveyance on a road;

“industrial tractor” means a tractor approved by the Licensing Authority exclusively for industrial purposes;

“Licensing Authority” means the authority appointed in accordance with the provisions of section 4 for the registration and control of motor vehicles;

“maximum gross weight” or “M.G.W.” in reference to a goods vehicle, means the tare together with the load including the weight of the driver and loaders, and in reference to a motor omnibus means the tare together with the weight of the driver, conductor and number of passengers for which the vehicle is registered; and for the purposes of this definition the weight of a driver, loader, conductor or passenger shall be taken as 60 kilogrammes;

“maxi-taxi” means a public service vehicle with seating accommodation for not less than nine nor more than twenty-five passengers;

“motorcycle” means a motor vehicle with less than four wheels and the weight of which unladen does not exceed 365 kilogrammes;

“motor omnibus” means a public service vehicle other than one registered as a “hiring car”, “private school bus” or “maxi-taxi”, and includes a light motor omnibus having seating accommodation for not more than ten passengers, an ordinary motor omnibus having seating accommodation for more than ten passengers and a freight passenger vehicle;

“motor vehicle” means any mechanically propelled vehicle intended or adapted for use on roads and includes a trolley vehicle, but does not include vehicles constructed exclusively for use on rails or other specially prepared tracks;

“motor vehicles tax” means the tax imposed under section 14 of this Act;

“Motor Vehicles Inspector” means any person carrying out the provisions of this Act relating to the inspection and making of reports on the condition of vehicles and includes the person for the time being performing the duties of Automotive Licensing Officer in the Ward of Tobago;

Ch. 25:04. “Municipal Corporation” means a municipal or regional corporation established under the Municipal Corporations Act;

“overtaking” includes passing or attempting to pass any other vehicle proceeding in the same direction;

“owner” —

- (a) in the case of a motor vehicle that is not registered, includes the person in actual charge or possession of the vehicle in Trinidad and Tobago;
- (b) in the case of a vehicle that is registered, means the person in whose name the vehicle is registered:

Provided that, in the case of a motor vehicle which is the subject of a hire-purchase agreement, it means the person in possession of the vehicle under that agreement; and whenever the registered owner of a motor vehicle is absent from Trinidad and Tobago, the person in actual charge or possession of the vehicle in Trinidad and Tobago shall be deemed to be the owner thereof;

“parking” means causing or permitting a vehicle, whether occupied or not, to stand on a road, except —

- (a) while the vehicle is being loaded or unloaded; or
- (b) while passengers are entering or leaving the vehicle; or
- (c) in compliance with the directions of a constable or of a traffic sign or with the requirements of traffic regulations; or
- (d) while temporarily stopped by reason of traffic conditions; or
- (e) while stopped owing to mechanical breakdown or lack of fuel,

and “park” and other cognate expressions shall be construed accordingly;

“payee” means a person or entity appointed in accordance with section 88D;

“pole trailer” means a trailer so designed that an indivisible load placed thereon will be supported at its front end by the body or chassis of the towing vehicle and at its rear end by the body or chassis of the trailer;

“private motor car” means a motor vehicle approved by the Authority for private use exclusively with seating accommodation for not more than eight persons;

“private school bus” means a public service vehicle having seating capacity for not less than nine nor more than twenty-five passengers, used for transporting school children and is a type approved by the Licensing Authority;

“public service vehicle” means a motor vehicle used for carrying passengers for hire or reward, whether at separate and distinct fares for their respective places or not;

“rented car” means a motor vehicle, other than a motorcycle, of a type approved by the Licensing Authority and having seating accommodation for not more than eight persons including the driver, which is privately hired from the owner and which is not to be used as a public service vehicle;

“road” means any street, road or open space to which the public are granted access and any bridge over which a road passes, and includes any privately owned street, road or open space to which the public are granted access either generally or conditionally;

“semi-trailer” means any trailer which is so designed that when operated the forward part of its body or chassis rests upon the body or chassis of the towing vehicle;

“tare” means the actual weight of a motor vehicle when unladen but inclusive of the body, accumulators, loose tools, spare wheels and other usual equipment and a full supply of water and fuel used for the purposes of propulsion;

“tonne” means the metric tonne of 1 000 kilogrammes;

“tractor” means any motor vehicle constructed for the purpose of hauling trailers whether or not it is itself capable of carrying passengers or goods but does not include a goods vehicle so constructed except when such goods vehicle is hauling a trailer;

“traffic” includes bicycles, tricycles, motor vehicles, tramcars, vehicles of every description, pedestrians, and all animals being ridden, driven or led;

“traffic light signal” means an electronic or automated device installed for the purpose of controlling vehicular traffic and showing red, amber and green light signals;

“traffic sign” includes any signal (whether an electric automatic signal or otherwise), warning signpost, direction post, sign, line, direction arrow, word, mark or other device erected, placed or otherwise marked on or near a road for the guidance or direction of traffic;

“traffic violation” shall be construed in accordance with section 20B;

“Traffic Warden” means a person appointed in accordance with the provisions of section 10A;

“trailer” means any vehicle which has no independent motor power of its own and which is attached to a tractor or other motor vehicle, but does not include a side-car attached to a motorcycle;

“Transport Commissioner” means the person mentioned in section 4(1);

“Transport Officer” includes the Transport Commissioner, the Assistant Transport Commissioners, Motor Vehicles Inspectors, Automotive Licensing Officers, Motor Vehicles Officers and Motor Vehicles Supervisors;

“vehicle” includes tramcars, carriages, wagons, carts, motor vehicles, bicycles, tricycles, vans, hand carts, sledges, trucks, barrows and all other machines for the portage of goods or persons.

Non-application  
of section 64 of  
Interpretation  
Act.  
Ch. 3:01.  
[9 of 2017].

**2A.** Section 64 of the Interpretation Act does not apply to a traffic violation.

Trinidad  
Transport Board.  
[2 of 1952  
11 of 1965  
6 of 1974  
9 of 1997].

**3.** (1) There shall be established a body to be called the Trinidad Transport Board (hereinafter referred to as the Board) consisting of the Chief Technical Officer (Works) as Chairman, the Commissioner of Police or such other First Division Police Officer as may be nominated in writing for the purpose by the Commissioner of Police, the Licensing Authority, the Chairman of

the Road Safety Association of Trinidad and Tobago, a member of the Trinidad and Tobago Automobile Association and seven other members to be appointed by the President after consultation with such representatives or bodies, representatives of the following interests, as the President may think fit, that is to say, local government, commerce, industry, agriculture and labour. The President may appoint any person to act in the place of the Chairman or any other member of the Board in the case of his absence or inability to act as such Chairman or other member. The Board may act by any five of their members and may so act notwithstanding any vacancy in the number of members constituting the Board. The Board shall have the power to regulate their procedure.

(2) The Board shall act in an advisory capacity and shall advise the President on all matters appertaining to road traffic and in particular as to the following matters:

- (a) licence duties in respect of motor and other vehicles;
- (b) Customs and Excise duties in respect of transport vehicles and fuel therefor;
- (c) the needs of areas as a whole in relation to traffic (including the provision of adequate suitable and efficient services and the elimination of unnecessary or unremunerative services) and the co-ordination of all forms of passenger and goods transport, including transport by rail and sea;
- (d) the regulation and control of traffic;
- (e) the construction and maintenance of roads and the cost thereof; and
- (f) any other matter affecting traffic or transport that the President may refer to the Board.

(3) The Board shall hear and determine any appeal submitted by any aggrieved person against any order or decision of the Licensing Authority or of an Automotive Licensing Officer, and the Board's decision thereon shall be final and conclusive.

(4) The Board shall perform such other duties as are assigned to them by this Act and the Regulations made hereunder or by any Order of the President.

Appointment of Transport Commissioner, Assistant Transport Commissioner, etc. [3 of 1969, 9 of 1997, 25 of 1997].

**4.** (1) The Transport Commissioner is the Licensing Authority and shall be charged with responsibility for the registration and inspection of all motor vehicles and issue of driving permits and such other matters as are assigned to him by this Act or any Regulations made thereunder.

(2) Notwithstanding anything to the contrary in this Act, any reference to an Assistant Transport Commissioner, Automotive Licensing Officer, Motor Vehicles Inspector, Motor Vehicles Officer and Motor Vehicles Supervisor is a reference to a Transport Officer and the functions or powers specified in relation to such Officer shall be performed by a Transport Officer.

(3) Transport Officers shall be under the direction of the Transport Commissioner who may assign such officers as may be necessary to such localities and to perform such duties as he directs for the purposes of the Act.

Minister to approve forms, certificates and procedures for registration of vehicles. [25 of 1997].

**4A.** The Minister shall approve in writing, forms, certificates and procedures required by the Licensing Authority for the registration of all motor vehicles and trailers.

Transport Officers to have powers, etc., of members of the Police Service. [3 of 1969].

**5.** (1) In the exercise of powers and duties conferred on him by this Act and any Regulations made thereunder, every Transport Officer shall have the powers, authorities and privileges and shall be entitled to all the immunities given by any law from time to time in force to any member of the Police Service.

(2) Where any Transport Officer makes a complaint against any person, any other Transport Officer may appear before the Magistrate who is trying or inquiring into the matter of the said complaint, and shall have the same privilege as to addressing the said Magistrate and as to examining the witnesses adduced in the said matter as the Transport Officer who made the complaint would have had.

Precept of appointment. [3 of 1969].

**6.** (1) On the appointment of any person to be a Transport Officer, the Transport Commissioner shall deliver or cause to be delivered to him a precept authorising him to act as such.

(2) The precept shall be in the following form:

REPUBLIC OF TRINIDAD AND TOBAGO

**THE MOTOR VEHICLES AND ROAD TRAFFIC  
ACT (CHAP. 48:50)**

To .....

of .....

I, ....., Transport Commissioner do  
under and by virtue of the power and authority vested in me by the Motor  
Vehicles and Road Traffic Act hereby issue to you this precept authorising  
you to perform the duties of .....

.....

.....  
*Transport Commissioner*

7. Every Transport Officer shall be provided with a manual describing his powers and duties, a badge and such uniform and other equipment as may be approved by the Minister. Such badge shall be evidence of the office of a Transport Officer and shall in all cases be displayed by every such officer when exercising the duties of his office. The cost of these articles of clothing and equipment shall be defrayed from such funds as may be provided for the purpose by Parliament. Equipment.  
[3 of 1969].

**8. (*Repealed by Act No. 25 of 1997*).**

9. Any person who assaults, obstructs or resists any Transport Officer in the execution of his duty, or aids or incites any other person to assault, obstruct or resist any Transport Officer in the execution of his duty, is liable on summary conviction to a fine of three hundred dollars or to imprisonment for six months. Penalty for  
assaulting or  
obstructing  
Transport  
Officer.  
[3 of 1969].

10. (1) Every driver of a motor vehicle shall, on the request of a Transport Officer in uniform, if such officer shall put up his hand as a signal for that purpose, cause a motor vehicle to stop and remain stationary as long as may be reasonably necessary for the Transport Officer to satisfy himself of the vehicle's roadworthiness and the driver's general compliance with the Act. Power to stop  
and inspect  
vehicles.  
[3 of 1969  
25 of 1997].

(2) Any driver of a motor vehicle who contravenes subsection (1) is liable on summary conviction to a fine of three hundred dollars or to imprisonment for six months.

Appointment  
and functions  
of a Traffic  
Warden.  
[21 of 2000  
9 of 2017].

**10A.** (1) The Police Commissioner may—

- (a) with the approval of the Minister responsible for the Police; and
- (b) subject to—
  - (i) such conditions as the Minister directs; and
  - (ii) criteria as may be established by Order by the Minister responsible for transport after consultation with the Licensing Authority,

appoint by instrument in writing, any member of an organisation or any person as a Traffic Warden for the purpose of assisting the Police in connection with the control and regulation of road traffic and with the enforcement of the law.

(2) A Traffic Warden shall, while in the execution of his duty, wear such uniform as the Police Commissioner, with the approval of the Minister responsible for the Police, directs.

(3) Any driver who—

- (a) fails to comply with the directions given by a Traffic Warden while on duty;
- (b) obstructs a Traffic Warden in the execution of his duty, or aids or incites any other person not to comply with the directions of a Traffic Warden or to obstruct a Traffic Warden in the execution of his duty,

commits an offence and is liable on summary conviction to a fine of ten thousand dollars and imprisonment for six months.

## PART II

### REGISTRATION OF MOTOR VEHICLES

Motor vehicle  
registers.  
[25 of 1997].

**11.** (1) The Licensing Authority shall cause registers of motor vehicles to be kept in the manner he directs.

(2) The Licensing Authority shall supply to any person applying for a copy of the entries relating to any specified vehicle a

copy of these entries on payment of a prescribed fee, provided that he shows that he has a reasonable cause for requiring such a copy.

**12.** (1) No person shall, in any place, use or keep for use or, being the owner, permit any other person to use or keep for use any motor vehicle—

Registration of  
motor vehicles.  
[35 of 1957  
44 of 1977  
9 of 1997  
25 of 1997  
5 of 2013].

- (a) not being a vehicle exempted from registration under this Act, unless it is registered under this Act according to the procedures required by the Licensing Authority or;
- (b) being an agricultural tractor, agricultural trailer or industrial tractor, for any purpose unless the Licensing Authority has granted its approval, in the prescribed manner, of the use of the vehicles for that purpose.

(2) No person shall be liable to a penalty for a breach of this section if he proves that he has taken all reasonable steps to comply with its requirements, and, when the vehicle is in use on a road, that it is on its way for the purpose of being registered.

(3) The Transport Officer to whom application is made shall, upon being satisfied that the provisions of this Act and the Motor Vehicles Insurance (Third-party Risks) Act and Regulations respectively made thereunder, have been complied with, forthwith enter particulars of the vehicle in the register, and shall assign to the vehicle a registered letter or letters and number, which shall become the identification mark of such vehicle.

Ch. 48:51.

(3A) The Licensing Authority shall—

- (a) on the application by a diplomat or diplomatic organisation for the registration of a motor vehicle in his or its name; and
- (b) upon being satisfied that the provisions of this Act and the Motor Vehicles Insurance (Third-party Risks) Act and Regulations made thereunder, have been complied with,

Ch. 48:51.

register the motor vehicle as a diplomatic motor vehicle and forthwith enter particulars of the vehicle in the register and shall

assign to the vehicle special identification marks to be carried on the registration plates of the vehicle.

(4) A certified copy of the entry in the register shall be given to the owner of the vehicle, and such certificate of registration shall be regarded as *prima facie* evidence that the vehicle to which it refers has been registered.

(5) If a motor vehicle does not bear on it an identification mark as required by the Licensing Authority, this fact shall be regarded as *prima facie* evidence that the vehicle has not been registered, and any constable may detain such a vehicle until enquiries have been made.

(6) The onus of proving that a vehicle has been registered rests upon the owner of the vehicle.

(7) The owner of a motor vehicle shall notify the Licensing Authority of all circumstances or events which affect the accuracy of the entries in the register, at the same time forwarding his certificate of registration for amendment. A Transport Officer may call upon any owner of a motor vehicle at any time to furnish all information for the verification of the entries in the register relating to such vehicle.

(8) Whenever the registered owner of a motor vehicle is about to absent himself from Trinidad and Tobago leaving his registered vehicle in Trinidad and Tobago, he shall notify the Licensing Authority in writing of the name and address of the person in whose charge or possession the vehicle will be left.

(9) No person shall be registered as the owner of a motor vehicle unless he is at least seventeen years of age.

(10) In this section—

“diplomat” means a diplomatic agent, consular officer or an official of an international organisation or agency who is certified in writing by the Minister with responsibility for foreign affairs as being entitled to enjoy privileges and immunities under the Privileges and Immunities (Diplomatic, Consular and International Organisation) Act;

“diplomatic organisation” means a diplomatic mission, consular post or a regional or international organisation or agency that is certified in writing by the Minister with responsibility for foreign affairs as being entitled to enjoy privileges and immunities under the Privileges and Immunities (Diplomatic, Consular and International Organisation) Act.

**13.** (1) Before registering any motor vehicle the Transport Officer shall verify all the particulars in the approved form and may inspect any motor vehicle in accordance with the direction of the Transport Commissioner for the purpose of ensuring that it conforms with the requirements of the Act and the purpose for which it is sought to be registered.

Examination of motor vehicles. [3 of 1969, 44 of 1977, 25 of 1997].

(2) Before registering any goods vehicle, freight passenger vehicle, motor omnibus or trailer, the Transport Officer shall ascertain the maximum gross weight or the maximum number of passengers which the vehicle may be authorised to carry, and such maximum gross weight or maximum number of passengers shall be entered in the register and in the certificate of registration.

(3) If any owner of a motor vehicle or trailer is aggrieved at the outcome of any inspection required under subsection (1) he may appeal to the Licensing Authority who may review the outcome of that inspection and direct that the requirements of the Transport Officer are either unreasonable or that such requirements shall be enforced.

**14.** (1) There shall be payable to the Comptroller of Customs and Excise in respect of the classes of motor vehicles specified in the Fourth Schedule, a motor vehicles tax computed in accordance with the provisions of that Schedule.

Motor vehicles tax. [35 of 1957, 28 of 1978, 9 of 1997, 30 of 2007, 7 of 2016]. Fourth Schedule.

(2) Motor vehicles tax shall be payable by the importer to the Comptroller of Customs and Excise upon the vehicle being entered for use within Trinidad and Tobago and before the registration of the motor vehicle.

(2A) For the purposes of collecting and enforcing the payment of the motor vehicles tax, the Customs Act relating to the importation of goods shall apply in the same manner as if it were a duty of Customs.

Ch. 78:01.

(2B) Where, on or before the coming into operation of the Finance (No. 2) Act, 2007, a motor vehicle has been entered for use within Trinidad and Tobago but no motor vehicles tax has been paid on such vehicle, the provisions of this Act shall apply in relation to the collection of such tax as if the Finance (No. 2) Act, 2007 had not been enacted.

(3) The President may remit or refund in whole or in part any motor vehicles tax whenever he shall deem it expedient to do so.

(4) If any motor vehicle in respect of which motor vehicles tax is payable is registered contrary to the provisions of this section, such registration shall be void and of no effect and the motor vehicle shall be deemed not to have been registered.

Fourth  
Schedule.

(5) The President may by Order amend the Fourth Schedule.

(6) An Order made by the President under subsection (5) shall have effect from the date of publication, but—

(a) shall, as soon as may be, but within sixty-one days, from the date of such publication, be laid in each House of Parliament; or

(b) if either House of Parliament, within forty days from the date the Order is laid under paragraph (a), resolves that the Order be annulled, the Order is void as from the date of the resolution, but without prejudice to the validity of anything done under the Order or to the making of the Order.

(7) If an Order is not laid in Parliament within the period of sixty-one days referred to in subsection (6)(a), the Order shall on the termination of that period expire and be of no further effect.

(8) So much of motor vehicles tax as shall have been paid under an Order made under this section as may be in excess of the said tax payable immediately after such Order has been dealt with by Parliament under subsection (6) or has expired under subsection (7) shall be repaid to any person who has paid the same.

**15.** (1) The registration of a motor vehicle shall remain valid so long as the vehicle is kept in use and shall only be cancelled where the Licensing Authority is satisfied that—

Cancellation of registration.  
[25 of 1997  
5 of 2013  
9 of 2017].

- (a) the vehicle has been destroyed;
- (b) the vehicle has been rendered permanently unserviceable;
- (c) the vehicle has been permanently removed from Trinidad and Tobago;
- (d) section 23(1) has been contravened;
- (e) a transaction in respect of the vehicle was effected under a misrepresentation of the information required for the purposes of the transaction;
- (f) the owner of a motor vehicle registered under section 12(3A) is no longer entitled to enjoy privileges and immunities under the Privileges and Immunities (Diplomatic, Consular and International Organisation) Act; or
- (g) an application is made to transfer a motor vehicle registered under section 12(3A) to a person who is not entitled to enjoy privileges and immunities under the Privileges and Immunities (Diplomatic, Consular and International Organisation) Act.

Ch. 17:01.

(1A) Where the registration of a motor vehicle is cancelled under paragraph (f) or (g), the Licensing Authority may register that motor vehicle under section 12(3).

(2) The owner of a motor vehicle which has been destroyed, rendered permanently unserviceable or has been permanently removed from Trinidad and Tobago shall notify the Licensing Authority, in writing, within one month of such event and an owner who fails to notify the Authority is liable to a fine of three thousand dollars.

(3) ***(Repealed by Act No. 9 of 2017).***

(4) Where the Licensing Authority cancels a registration under subsection (1), the Authority shall notify the owner in writing.

(5) Where the owner of a motor vehicle is aggrieved by the decision of the Licensing Authority to cancel his registration, he may appeal to the Board.

Exemptions from need for registration. [12 of 1961 11 of 1965 44 of 1977 25 of 1997 5 of 2010].

**16.** (1) The following classes of motor vehicles shall be exempted from the need for registration:

- (a) new motor vehicles in the possession of manufacturers or dealers in motor vehicles, but subject to such provisions as to dealers' general licences as may appear hereinafter;
- (b) private motor cars and motor cycles brought into Trinidad and Tobago by visitors for their own use for a period not exceeding three months subject to such conditions as may be prescribed;
- (c) any motor vehicle the property of or used by the President for his official or personal duties.

Exemption from payment of registration fee.

(2) No fee on registration shall be charged in respect of the following:

- (a) any motor vehicle which is the property of the Government or any Municipal Corporation; or the Corporation established under the Public Transport Service Act;
- (b) any motor vehicle specially exempted by an Order of the President on account of its being owned by a public body or of its being used for any charitable, philanthropic or other public purpose:

Ch. 48:02.

Provided that the exemption hereby granted from payment of the registration fee in respect of a vehicle shall cease whenever the condition justifying such exemption ceases to apply to that vehicle.

(2A) Notwithstanding the requirements of subsection (1) and any other written law, the Minister may by Order prescribe the identification mark to be carried on any registered motor vehicle or trailer owned or used by the State.

Restriction on registration of taxis. [11 of 1963].

**17.** (1) Notwithstanding the provisions of section 12, during any period when there is in force an Order under this section, no motor vehicle shall be registered for use as a taxi except in accordance with such Order.

(2) The Minister may by Order prohibit or restrict, subject to such conditions, if any, as may be specified in the Order, the registration of motor vehicles for use as taxis.

(3) In this section, “Minister” means the Minister responsible for road transport.

**17A.** (1) Where a motor vehicle is assembled in Trinidad and Tobago and the Customs duty payable on such a vehicle as assembled has not been paid, the Licensing Authority shall not register the vehicle for use, unless the fee specified in the First Schedule in relation to such a vehicle is paid and the vehicle shall be exempt from motor vehicles tax.

Restriction on registration of motor vehicles. [8 of 1996 2 of 2002]. First Schedule.

(2) The President may remit or refund the whole or any part of the fee referred to in this section where he considers it expedient to do so.

(3) Notwithstanding subsection (1), with effect from 1st May 2003, no locally assembled motor vehicle using new or used foreign parts shall be registered for use under this Act.

**18.** (1) Where the owner of a motor vehicle which is registered for use for a particular purpose intends to use that vehicle for some other purpose he shall, before using the vehicle for that other purpose, apply to the Licensing Authority for registration of the vehicle for use for that other purpose; and the application shall, subject to subsection (2), be dealt with as if the vehicle had not previously been registered, but—

Registration on change of use. [11 of 1963 9 of 1990].

- (a) the fee payable for such registration shall be the fee prescribed for an amendment of the Register;
- (b) except as provided by subsection (2), motor vehicles tax shall not be payable before such registration.

(2) Motor vehicles tax shall be payable in accordance with section 14 before the registration of a motor vehicle for a purpose other than that for which it was registered where the vehicle was first registered after 31st December 1962.

(3) Where the tax paid in respect of the current registration is more than that payable for the class of vehicle in respect of which the new registration will apply, no tax is payable.

Transfer of  
registration.  
[30 of 1951  
3 of 1994  
25 of 1997  
9 of 2017  
4 of 2020  
20 of 2020  
26 of 2020].

**19. (1)** On the change of possession of a motor vehicle otherwise than by death—

- (a) the motor vehicle shall not be used for more than seven days after such change of possession unless the new owner is registered as the owner thereof;
- (b) the registered owner and the new owner shall, within seven days after such change of possession, make application in writing signed by both of them to the Licensing Authority giving the name and address of the new owner and the date of change of possession and such application shall be accompanied by the certificate of registration and the prescribed fee. The Transport Officer shall thereupon by endorsement of the certificate of registration and entry in the register substitute the name of the new owner for that of the registered owner and shall date and initial the substitution and from such date the new owner shall for all purposes be deemed to be the registered owner of the motor vehicle described in the relevant entry in the register and in such certificate of registration;
- (c) the registered owner and the person seeking registration as the registered owner shall both be present before the Licensing Authority together with the used motor vehicle that is the subject of the transfer at the time that transfer of registration occurs;
- (d) where a person referred to in paragraph (c) is a company, a letter of authorisation signed by a director of the company authorising a representative to act on behalf of the company shall be produced to the Licensing Authority;
- (e) where a person referred to in paragraph (c) is unable to be present due to illness or disability, the Licensing Authority or an officer appointed by him, upon payment of a fee of one hundred dollars to be paid by or on behalf of the ill or disabled person, shall be required to visit the

person and the vehicle for the purpose of effecting the transfer of registration;

- (f) where a person referred to in paragraph (c) is out of the country, the Licensing Authority may effect the transfer of registration if the other person produces a sworn affidavit to the effect that that other person is out of the country.

(2) In the case of the death of the registered owner the legal personal representative of the deceased in Trinidad and Tobago shall be deemed to be the owner for the purposes of such transfer, and in the absence of any legal personal representative in Trinidad and Tobago the person into whose possession the motor vehicle shall lawfully come shall, for the purposes of such transfer, be deemed to be the registered owner: Provided that such personal representative or other person as aforesaid shall notify the Licensing Authority of the death of the registered owner within one month of the happening of such event.

(3) At the discretion of the Transport Officer a new certificate of registration may be issued instead of endorsing the original certificate.

(4) If the Licensing Authority is satisfied that there has been a change of possession of a motor vehicle but that the registered owner has failed to make the application referred to in subsection (1)(b) or to surrender the certificate of registration, the Licensing Authority may, without prejudice to any proceedings which may be taken against the registered owner for such failure, transfer the registration of the motor vehicle in the same manner as if the provisions of the said subsection (1)(b) had been complied with.

(5) Where a registration of transfer of a used motor vehicle has not been made within seven days after the change of possession of that vehicle in accordance with subsection (1)(a), the registered owner shall be liable to pay to the Licensing Authority a penalty of two hundred dollars.

(6) Where a registration of transfer referred to in subsection (5) has not been made within fourteen days after the change of possession of that vehicle, the registered owner is liable to a fine of five thousand dollars.

(7) Notwithstanding any provision to the contrary contained in this Act and subject to subsection (8), any transfer of registration required to be completed on or before 31st December 2020 may be completed on or before 31st March 2021.

\*(8) The Minister may, by Order, extend any of the dates specified in subsection (7).

Tax payable on transfer of motor vehicle. [3 of 1994 5 of 2010]. Fifth Schedule.

**19A.** (1) There shall be charged, levied and collected in respect of every used motor vehicle in respect of which there is to be a transfer of registration on the change of possession a tax (hereinafter called “transfer tax”) as specified in the Fifth Schedule.

Ch. 75:01.

(2) The Tax Authority shall be the Board of Inland Revenue which, in respect of the collection and recovery of transfer tax, has all the powers that it has in relation to income tax under the Income Tax Act.

(3) Subject to negative resolution of Parliament, the Minister with responsibility for finance may by Regulations amend, suspend or revoke the provisions of the Fifth Schedule.

Payment of transfer tax. [3 of 1994].

**19B.** (1) The transfer tax shall be paid to the Licensing Authority by the person seeking registration as the registered owner (hereinafter referred to as “the transferee”) at the time of the registration of the change of possession of the motor vehicle.

Ch. 75:06.

(2) A transferee shall not be registered as the new owner in respect of the transfer of a used motor vehicle unless the transfer tax is paid.

(3) Subject to subsection (4), the transfer tax shall not be payable by used car dealers registered under the Value Added Tax Act.

(4) In order to be eligible for an exemption from the payment of the transfer tax, a used car dealer shall register with the Licensing Authority as an exempt person and shall—

(a) produce a Value Added Tax Certificate to the Licensing Authority; and

(b) satisfy the Licensing Authority that—

(i) he is a bona fide dealer in used motor vehicles; and

\*See Note on omissions at page 4.

- (ii) he has sold five or more used motor vehicles in the period of twelve months preceding the time of the aforementioned registration.

(5) A person shall not be considered a bona fide dealer in used motor vehicles unless he is engaged in the business of buying used motor vehicles for resale.

(6) Where a person purchases a used motor vehicle from a person registered under the Value Added Tax Act, he shall be exempt from the payment of the transfer tax where he produces to the Licensing Authority a tax invoice under that Act in respect of the purchase.

**19C.** (1) Where a transfer of registration on the change of possession of a used motor vehicle is as a result of the sale of that vehicle, the purchaser shall produce to the Licensing Authority at the time of registration of the change of possession of the vehicle a receipt evidencing such sale.

Evidence of sale or date of transfer.  
[3 of 1994].

(2) Where there is a transfer of registration on the change of possession of a used vehicle without the payment of consideration, there shall be produced to the satisfaction of the Licensing Authority at the time of registration of the change of possession of the vehicle evidence of the date of transfer of ownership of the vehicle.

**19D.** For the purposes of the transfer tax, the age of the motor vehicle shall be determined from the date of first registration of that vehicle.

Age of motor vehicle.  
[3 of 1994].

**19E.** The President may remit or refund in whole or in part any transfer tax whenever he deems it expedient to do so.

Refund of transfer tax.  
[3 of 1994].

**19F.** Unconditional gifts of motor vehicles to an organisation approved by the President under section 6(1)(g) of the Corporation Tax Act are exempt from the transfer tax.

Exemption.  
[3 of 1994].  
Ch. 75:02.

**19G.** *(Repealed by Act No. 9 of 1997).*

**20.** In this Part the expression “motor vehicle” includes trailer.

Interpretation.  
[44 of 1977].

PART IIA

TRAFFIC VIOLATIONS

Conditions of permit and registration. [9 of 2017].

**20A.** (1) It is hereby declared that compliance with this Act and other written laws relating to the use of a vehicle on a road by the holder of a driving permit is a condition of the driving permit.

(2) It is hereby declared that compliance with this Act and other written laws relating to the use of a motor vehicle on a road is a condition of the registration of the motor vehicle under this Act and that, subject to the provisions of this Act and those written laws, the owner of the motor vehicle is responsible for any breach of this Act or those written laws which involves the use of his motor vehicle and which is imputable to him as the owner.

Commission of a traffic violation. [9 of 2017].

**20B.** The breach of a condition specified in the Seventh Schedule by the holder of a driving permit or owner of a vehicle constitutes a traffic violation and the holder of the driving permit or the owner of the motor vehicle shall be liable to be dealt with in accordance with this Act.

Standard of proof. [9 of 2017].

**20C.** In proceedings for a traffic violation under this Act, the standard of proof shall be on a balance of probabilities.

PART III

LICENSING OF MOTOR VEHICLES

*[This Heading was deleted by section 5(h) of Act No. 9 of 1997]*

Using vehicle without prescribed registration, an offence. [11 of 1963, 14 of 1979, 3 of 1994, 9 of 1997, 5 of 2010, 9 of 2017].

**21.** (1) Save as is otherwise provided in this Act, if—

- (a) *(Deleted by Act No. 9 of 1997)*;
- (b) any motor vehicle or trailer is used upon any road for a purpose which is not authorised by the registration issued in respect thereof or is altered in a manner which may conflict with the purpose or use for which it is registered, without permission from the Licensing Authority or is in contravention of any provisions of this Act; or
- (c) any goods vehicle, public service vehicle, rented car or trailer is used upon a road being loaded so

as to exceed the maximum gross weight or the number of passengers, respectively, covered by the registration,

the owner or the driver or other person in charge of the motor vehicle, as the case may be, who contravenes—

- (i) *(Deleted by Act No. 9 of 1997)*;
- (ii) paragraph (b) or (c), is liable to a fine of eight thousand dollars.

(2) *(Repealed by Act No. 9 of 2017)*.

(3) } *(Repealed by Act No. 9 of 1997)*.

(4) }

(5) *(Repealed by Act No. 9 of 2017)*.

(6) }

to } *(Repealed by Act No. 9 of 1997)*.

(8) }

22. (1) Notwithstanding anything contained in section 21 the Licensing Authority may, in his discretion and on payment of the appropriate fee (if any) specified in the First Schedule, grant permission to enable a goods vehicle, agricultural trailer or trailer to be used for the conveyance, either generally or on particular journeys, of such number and classes of passengers, without hire or reward, and of such number of other persons employed for the purpose of loading or unloading the goods, merchandise or other loads carried on the goods vehicle, agricultural trailer or trailer as he may think fit, subject to such conditions as he may impose.

Licensing Authority may permit goods vehicles to be used for the conveyance of persons. [9 of 1997]. First Schedule.

(2) Whenever permission is granted under the authority of subsection (1), a permit under the hand of the Licensing Authority in a form to be determined by him and containing the conditions subject to which such permission has been granted shall be issued to the registered owner of the goods vehicle, agricultural trailer or trailer, as the case may be.

(3) No such permit for the conveyance of passengers shall be valid for a longer period than six months from the date

of issue thereof and no such permit for the conveyance of persons employed to load and unload goods, merchandise or other loads shall be valid for a longer period than the unexpired portion of the calendar year in which the permit was issued.

(4) The Licensing Authority may waive the payment of any fee in the case of any agricultural trailer used for agricultural purposes or of any vehicle registered as a goods vehicle but not primarily constructed for the carriage or haulage of goods, merchandise or other loads.

(5) The Licensing Authority may cancel or suspend any permit issued under this section if in his opinion any of the conditions attached to the issue of such permit have not been complied with by the registered owner.

First Schedule.

(6) The Licensing Authority may issue a duplicate permit on payment of the appropriate fee specified in the First Schedule in place of any permit proved to his satisfaction to have been lost, defaced, mutilated or rendered illegible.

Police and  
Prison Service  
vehicles  
exempted from  
payment of  
fees.  
[17 of 1986  
9 of 1997].

**22A.** (1) Notwithstanding anything contained in sections 21 and 22, the Licensing Authority without charging a fee, may, in such form as he may determine, grant permission to the Police or Prison Service for vehicles belonging to those Services and registered as goods vehicles, to convey their personnel and persons in custody of the Police and Prison authorities.

(2) Notwithstanding the provisions of this Act station wagons or estate cars however registered may be used for the purpose of carrying passengers.

(3) Section 22(1) shall not apply to—

- (a) Police and Prison Service vehicles;
- (b) station wagons and estate cars however registered.

Restrictions on  
licensing of  
certain motor  
vehicles and  
trailers.  
[31 of 1976  
17 of 1978  
9 of 1997  
5 of 2010  
9 of 2017  
15 of 2020].

**23.** (1) Save as provided in this section—

- (a) no motor vehicle exceeding the maximum gross weight of fifteen tonnes;
- (b) no trailer exceeding the maximum gross weight of eight tonnes;

- (c) no motor vehicle or trailer all the wheels of which are not fitted with pneumatic tyres;
- (d) **(Deleted by Act No. 15 of 2020);**
- (e) no motor vehicle painted in the colour or combination of colours used by the Trinidad and Tobago Regiment, the Coast Guard, the Police Service or the Prison Service other than a motor vehicle of the Trinidad and Tobago Regiment, the Coast Guard, the Police Service, or the Prison Service respectively, and no motor vehicle, other than, a motor car, painted in the colour or combination of colours used by the Fire Service,

shall be used upon any road.

(1A) The Licensing Authority shall cancel the registration of any vehicle or trailer referred to in subsection (1) where, in relation to that vehicle or trailer, subsection (1) is contravened.

(1B) Notwithstanding subsection (1A), a person who contravenes subsection (1)(d), is liable to a fine of five thousand dollars.

(2) The Licensing Authority may, on the recommendation of the Board and with the approval of the Chief Technical Officer (Works), by Notification published in the *Gazette* authorise the use on roads, subject to such restrictions and conditions as may be specified in the Notification, of special types of motor vehicles or trailers which are constructed for special purposes or do not comply with this section or Regulations made under section 100; but nothing contained in this subsection shall be deemed to prohibit any authority responsible for the maintenance of any road or other person from recovering any extraordinary expense incurred in respect of any such road by reason of such use.

(3) The Chief Technical Officer (Works) may grant a special permit to the owner of a tractor, goods vehicle or trailer for conveying an indivisible load of heavy machinery or other articles in excess of the maximum gross weight of fifteen tonnes in the case of a motor vehicle and of eight tonnes in the case of a

trailer, subject to such conditions as may be specified in the permit and on payment of a special fee calculated at the rate of eight cents per kilometre or part thereof to be travelled for each tonne or part thereof of the gross weight to be transported in excess of the maximum gross weight for which such tractor, goods vehicle or trailer is registered.

(4) The Chief Technical Officer (Works) may grant a special permit to the owner of any machine used for industrial purposes to enable such machine to be moved from one place to another, subject to such conditions as may be specified in the permit, and on payment of a special fee calculated at the rate of four cents per kilometre or part thereof to be travelled for each tonne or part thereof of the gross weight to be transported; but the Chief Technical Officer (Works) may reduce by not more than fifty per cent the special fee payable under this subsection when the permit is granted in respect of a machine which is fitted entirely with pneumatic tyres.

(5) Notwithstanding the issue of a permit under subsection (3) or (4), no fee shall be payable in respect of road rollers, nor in respect of motor vehicles using only roads which are not maintained at the public expense, nor in any case in which the distance travelled along a public road does not exceed eight hundred metres.

(6) Any person to whom a permit has been granted under this section who fails to observe any of the conditions specified in such permit is liable to a fine of four hundred dollars, and, in addition, he shall be liable for any damages occasioned by his neglect or failure to observe any of such conditions.

**24. (Repealed by Act No. 9 of 1997).**

**25. (1) (Repealed by Act No. 9 of 1997).**

(2) The decision of the Licensing Authority as regards the class or type to which any vehicle conforms or under which it should be registered, shall be conclusive.

**26. (1)** For the purpose of the inspection of motor vehicles or trailers for roadworthiness, the Licensing Authority may

Conditions to be satisfied before licence issued. [9 of 1997].

Licensing Authority may designate premises. [25 of 1997].

designate premises not being under the control of the Authority where such vehicles may be examined by persons not in the employ of the Authority and further the Authority may authorise such persons to issue the approved certificate.

(2) A designation may be subject to such conditions as may be determined by the Licensing Authority.

(3) A current list of designated premises shall be published in the *Gazette* and at least one daily circulating newspaper.

27. (1) Where a Transport Officer certifies in writing that the motor vehicle or trailer is so constructed or is in such a condition as to constitute a health, safety or environmental hazard to any person travelling in the vehicle or to other members of the public or is injurious to the roads or contravenes the Act, the Licensing Authority may cancel a motor vehicle registration or trailer registration or refuse to renew such registration.

Cancellation or refusal of registration. [25 of 1997].

(2) An owner of a motor vehicle or trailer in respect of which the registration is cancelled or for which the issue or renewal of the registration is refused may appeal to the Transport Board.

28. On transfer of ownership of a motor vehicle or trailer, the Transport Officer shall, on payment of the prescribed fee, duly amend the register and the certificate of registration.

Amendment of Register and Certificate of Registration. [25 of 1997].

29. )  
to } *(Repealed by Act No. 9 of 1997).*  
33. )

34. A Transport Officer may issue to a dealer in, manufacturer or repairer of, motor vehicles or trailers, who makes application in the approved form, a dealers' general licence which, subject to the provisions of sections 35 to 40 and to any other conditions for the purposes of the Act, shall authorise the use of any number of motor vehicles or trailers the property of the dealer.

Dealers' general licence. [25 of 1997].

Uses of dealers' general licence. [25 of 1997].

**35.** A dealers' general licence in the approved form shall authorise the use of any motor vehicle or trailer, the property of the dealer, which is being tested by the dealer, or is being tested or used for the purpose of effecting a sale. It shall not authorise the carriage of passengers or goods for fee or reward, or any passenger not engaged in testing the vehicle or inspecting the vehicle with a view to purchase.

Register of dealers' general licences. [25 of 1997].

**36.** Motor vehicles and trailers used under the authority of a dealers' general licence shall not be registered in the manner provided by section 12 but the Transport Officer shall keep a separate register in the approved form of all such licences issued by him.

Cancellation of dealers' general licence. [25 of 1997].

**37.** (1) A Transport Officer may at any time cancel a dealers' general licence for a breach of any of the provisions of this Act or of any Regulations made thereunder.

(2) The Transport Officer shall give notice of such cancellation to the person to whom such licence was issued, and may at his discretion repay to him so much of the annual fee paid as is proportionate to the unexpired portion of the year in respect of which the fee was paid.

(3) Any person whose licence has been cancelled in accordance with this section or to whom a dealers' general licence has been refused may appeal to the Licensing Authority against the decision of the Transport Officer, and the Licensing Authority may order that the cancellation shall be confirmed or that the licence be restored to the holder.

Dealers' general licence not transferable. [25 of 1997].

**38.** No dealers' general licence shall be used for any purpose not provided for in this Act nor shall it be transferred or assigned to any other person without the authority of the Transport Officer.

Dealer to accompany vehicle when used.

**39.** No motor vehicle or trailer shall be used on any road under the authority of a dealers' general licence unless the holder of the licence, or a person duly authorised by him in writing, accompanies such vehicle.

**40.** (1) The holder of a dealers' general licence shall keep in the approved form, a record of every occasion on which a motor vehicle or trailer is used under the authority of such licence. He shall produce such record for inspection when requested by any First Division Police Officer or by any police officer authorised in writing by any First Division Police Officer.

Record of vehicles used under authority of dealers' general licence. [36 of 1967 25 of 1997].

(2) The owner of a rented car or a rented motorcycle shall keep in the prescribed form a record of every occasion on which a rented car or a rented motorcycle is hired out. He shall produce such record for inspection when requested by any First Division Police Officer or Transport Officer or any police officer authorised in writing by any First Division Police Officer, or by any Transport Officer.

Record of hire of rented cars.

**40A. (Repealed by Act No. 37 of 1989).**

**41.** (1) The owner of any motor vehicle in respect of which an international certificate for a motor vehicle has been issued elsewhere than in Trinidad and Tobago, in accordance with the provisions of any International Convention relating to the international circulation of motor vehicles which has been applied to Trinidad and Tobago, shall, whilst such certificate remains valid and subject to such conditions as the Licensing Authority determines, be exempted from any requirement to register such motor vehicle.

International certificates and temporary licences for motor vehicles. [9 of 1997 25 of 1997].

(2) Where a motor vehicle is brought into Trinidad and Tobago for the purpose of being used by the owner during a visit, and the owner of such motor vehicle does not hold an international certificate as aforesaid, the Licensing Authority may issue a temporary licence to use the motor vehicle without registration or payment of any fee for not more than three months and subject to such conditions as the Licensing Authority determines.

(3) No motor vehicle in respect of which an international certificate or temporary licence has been issued shall be used in Trinidad and Tobago for hire or trade purposes unless the owner has complied with the provisions of the Motor Vehicles Insurance (Third-party Risks) Act.

Ch. 48:51.

(4) Where a person in Trinidad and Tobago desires to use a motor vehicle in any other country which has adhered to any International Convention as aforesaid, he shall apply to the Licensing Authority for an international certificate in respect of the motor vehicle.

(5) The Licensing Authority shall have power, subject to such conditions as may from time to time be prescribed, to issue international certificates for motor vehicles in accordance with any International Convention as aforesaid. Before the certificate is issued, the applicant must satisfy the Licensing Authority that the motor vehicle complies with the requirements of the said Convention, and for such purpose the Licensing Authority may require an examining Inspector to examine the motor vehicle and report thereon.

(6) The Licensing Authority shall keep a record of all international certificates for motor vehicles and temporary licences issued by him, and of all motor vehicles being used in Trinidad and Tobago under the authority of international certificates issued in other countries.

Special permit  
for private  
school bus.  
[5 of 2010].

**41A.** The Licensing Authority may issue a special permit to the owner of a private school bus, used to transport school children during a school term, subject to such conditions as may be specified in the permit and on payment of the prescribed fee.

#### PART IV

#### DRIVING PERMITS

Driving without  
a permit an  
offence.  
[12 of 1961  
19 of 1978  
\*14 of 1979  
25 of 1997  
2 of 2015  
9 of 2017].

**42.** (1) Save as in this section provided, no person shall drive a motor vehicle on a road unless he is the holder of a valid driving permit for a motor vehicle of that class, and no person shall employ any person to drive a motor vehicle on a road unless the person so employed is the holder of a valid driving permit for a motor vehicle of that class, and if any person acts in contravention of this provision, he shall be liable to a fine of seven hundred and fifty dollars or imprisonment for one year: Provided that if the driver of the vehicle has never been the holder of a valid driving permit or has been

\*See page 155 of this Act for transitional provisions relating to permits.

previously refused a valid driving permit or is disqualified from holding or obtaining a valid driving permit, he may be arrested forthwith without a warrant and he shall be liable to a fine of fifteen hundred dollars.

(2) Notwithstanding subsection (1), for the purpose of learning to drive a motor vehicle of any class, a person (in this section referred to as “a learner”) who is not the holder of a valid driving permit for a vehicle of that class may nonetheless drive a vehicle of such a class on a road, so long as he is the holder of a provisional permit issued for that class of motor vehicle by the Transport Officer.

(3) A learner who fails to comply with any condition attaching to or any restriction specified in his provisional permit is liable to the penalty prescribed in subsection (1) as if he were not the holder of a provisional permit and the provisional permit shall be cancelled.

(4) When granting a provisional permit for the purpose mentioned in subsection (2), the Transport Officer may impose such conditions and restrictions as he may deem necessary for the safety of the public and shall, without prejudice to the generality of the foregoing words, specify—

- (a) that the learner shall drive upon such roads and at such times as may be mentioned in the permit;
- (b) that the learner shall not use a taxi, or a motor omnibus carrying passengers, for the purpose of learning to drive; and
- (c) that when learning to drive a motor vehicle (other than a motorcycle) the learner shall have sitting next to him, for the purpose of instructing him, a person who is the holder of a valid driving permit for the class of vehicle that the learner is learning to drive and has been the holder of such a permit for the requisite period as specified in section 45:

Provided that a learner may appeal to the Board against the refusal of a Transport Officer to grant him a learner’s permit or against any condition or restriction imposed by the Transport Officer and, on such appeal being made, the Board may make such order as they think just, and such order shall be final and conclusive.

(5) A provisional permit shall not be issued in respect of a motor vehicle in Class 4, 5, 6 or 7 unless the learner already holds a driving permit in respect of a motor vehicle in the next lower Class and has held such a permit for a period of not less than twelve months.

(6) A learner and the person accompanying him for the purpose of instruction, shall each be liable for any traffic violation or for any offence committed against any of the provisions of this Act during the course of such instruction.

(7) It shall be lawful for any person subject to the orders of the Military Authority to drive a motor vehicle owned or hired by the Military Authority whilst such vehicle is being used for military purposes so long as he is the holder of an identification card in a form approved by the Licensing Authority and signed by the Commander of the Trinidad and Tobago Defence Force or by a military officer authorised by him in that behalf, provided that such person is not disqualified by law from holding a driving permit under this Act and is on duty and is driving a vehicle of the class specified in the identification card.

Motorcycles  
and safety  
helmets.  
[20 of 1978  
5 of 2010].

**43.** (1) Notwithstanding section 42, from 1st September 1978 no person may drive or be carried on a motorcycle on any road unless he wears a safety helmet capable of affording the head of the wearer protection from injury in the event of an accident.

(2) A person who contravenes subsection (1) is liable on summary conviction to a fine of two thousand dollars or imprisonment for six months.

(3) The types of helmet which are capable of affording the head of the wearer protection from injury in the event of an accident shall be prescribed by the Minister, by reference to design, construction or other quality, by Notification.

Private motor  
cars and certain  
other vehicles  
to be fitted with  
seat belts.  
[17 of 1986  
226/1994  
25 of 1997  
5 of 2010].

**\*43A.** (1) Every—  
(a) private motor car;  
(b) public service vehicle;

\*Date of commencement of section 43A and 43B—1st January 1995 (LN 226/1994).

- (c) goods vehicle; and
- (d) rented car,

not exceeding a maximum tare weight of 3 000 kilogrammes, subject to such exemptions as may be prescribed, brought into, or assembled in Trinidad and Tobago shall, before such motor vehicle is registered, be fitted with a seat belt for the driver and for every passenger who may occupy a front seat of such vehicle and such seat belt shall form an integral and not an optional part of the vehicle.

(2) The seat belt referred to in subsection (1), shall be so designed as to provide restraint for both upper and lower parts of the trunk of the wearer and shall be of the type prescribed—

- (a) by reference to design, construction or other quality;
- (b) by reference to different classes of vehicles, different descriptions of persons and different circumstances, save that in a motor vehicle authorised to carry two passengers in the front the seat belt affixed to the middle front seat need not provide restraint for the upper part of the trunk of the wearer.

(3) The Licensing Authority shall, before the registration of any motor vehicle referred to in subsection (1), satisfy himself that the provisions of that subsection and of any Regulation made in pursuance of subsection (2) have been complied with and may refuse to register any motor vehicle which in his opinion fails to satisfy all or any of those requirements.

(4) The Minister may make Regulations for the purposes of subsection (2).

**\*43B.** (1) Every person who is the registered owner of any motor vehicle referred to in subsection (1) of section 43A shall have such motor vehicle fitted with seat belts of the type referred to in subsection (2) of section 43A.

Certain motor vehicles to be equipped with seat belts. [17 of 1986 226/1994 5 of 2010 9 of 2017].

(2) The registered owner of a motor vehicle referred to in subsection (1) who contravenes the provisions of that

\*Date of commencement of section 43A and 43B—1st January 1995 (LN 226/1994).

subsection is liable to a fine of four thousand dollars for the first traffic violation and to a fine of eight thousand dollars for any subsequent traffic violation.

Wearing of seat belts compulsory. [17 of 1986 226/1994 5 of 2010].

**\*43C.** (1) The driver and every passenger seventeen years of age or more occupying a front seat in any motor vehicle referred to in subsection (1) of section 43A shall wear a seat belt while the motor vehicle is in motion.

(1A) The driver of a motor vehicle referred to in section 43A(1) shall not without reasonable excuse drive a vehicle while there is in the front seat of the vehicle a person who is not wearing a seat belt.

(2) Any person who contravenes the provisions of subsection (1) or subsection (1A) is guilty of an offence and liable on summary conviction to a fine of two thousand dollars.

(3) A person shall not be convicted under this section if he proves that at the material time he or the passenger, as the case may be, held a valid certificate signed by a legally qualified medical practitioner to the effect that it is inadvisable on medical grounds for him or the passenger to wear a seat belt and the certificate shall be valid for a period of not more than two years from the date of issue.

(4) The Minister may make Regulations exempting persons from the provisions of subsection (1).

Driving while a child is in the vehicle. [226/1994 5 of 2010 9 of 2017].

**\*43D.** (1) The driver of a motor vehicle referred to in section 43A(1) shall—

- (a) not, without reasonable excuse, drive his vehicle while there is in the front seat of the vehicle a child of five years of age and under; and
- (b) ensure that a child—
  - (i) under six months of age, be restrained in a properly fastened and adjusted, rearward facing child restraint;

\*Date of commencement of sections 43C and 43D—1st January 1995 (LN 226/1994).

- (ii) over six months and under four years of age, be restrained in a properly fastened and adjusted, rearward facing child restraint or a forward facing child restraint that has an in-built harness; and
- (iii) over four years and under five years of age, be restrained in a properly fastened and adjusted, forward facing child restraint that has an in-built harness or an approved booster seat that is properly positioned and fastened.

(2) The Minister may by Order prescribe the type of child restraint and booster seat referred to in subsection (1).

(3) Subsection (1)(b) shall not apply to the driver of a public service vehicle.

(4) The driver of a motor vehicle who contravenes this section is liable to a fine of two thousand dollars.

(5) The driver of a motor vehicle shall not be liable under this section—

- (a) if he proves that the child held a valid certificate signed by a medical practitioner to the effect that it is inadvisable on medical grounds for the child to be placed in a child restraint or booster seat and the certificate shall be valid for a period of not more than two years from the date of issue; or
- (b) where there is only one row of seats in the vehicle.

**44.** (1) Driving permits shall be issued by a Transport Officer to applicants in accordance with this Part.

Issue of driving permits.  
[25 of 1997].

(2) Subject to sections 61A(4) and 89(1A), on the issue of a driving permit there shall be payable such fee as may from time to time be prescribed.

Fees.  
[1 of 2016].

**45.** (1) A person who instructs a learner to drive a motor vehicle in Class 2, 3, 4 or 7 shall be the holder of a valid driving permit for that class of vehicle for a period of not less than three years.

Driving instructors.  
[14 of 1979  
25 of 1997].

(2) A person who instructs a learner to drive a motor vehicle in Class 5 or 6 shall be the holder of a valid driving permit for that class of vehicle for a period of not less than five years.

(3) A person who instructs a learner shall have with him at all times while in a vehicle instructing the learner, his valid driving permit in respect of the class of vehicle in which he is giving instruction.

Offences of driving instructor. [14 of 1979 25 of 1997 9 of 2017].

- 46.** (1) A person who instructs a learner and who—
- (a) is not the holder of a valid driving permit for the class of motor vehicle in which he is giving instruction; or
  - (b) is not the holder of a permit referred to in paragraph (a) for the period specified in section 45; or
  - (c) is giving instruction to a learner who is driving a motor vehicle on a road and the learner is not the holder of a provisional permit for that class of vehicle,

is liable to a fine of five thousand dollars.

(2) ***(Repealed by Act No. 9 of 2017).***

Driving tests. [25 of 1997].

**47.** (1) A Transport Officer in his discretion may require an applicant for a valid driving permit to produce a certificate of having passed a driving test signed by such association as may be approved of by the Licensing Authority.

(2) Driving tests may be conducted by such examiners as the Licensing Authority shall from time to time approve or appoint for the purpose.

(3) The nature of the driving test shall be at the discretion of the Transport Officer or of such examiner as aforesaid but shall include a test of the applicant's knowledge of the rules of the road, road signals and road signs; but where the applicant desires permission to drive an agricultural tractor only such test shall be restricted to the driving of an agricultural tractor and to questions affecting such driving and shall not include questions affecting the driving of motor vehicles generally.

(4) If the applicant requires permission to drive a particular class of vehicle only or if the applicant is being tested under the provisions of section 48(2), then the examiner shall issue a certificate on which any appropriate restrictions are clearly set forth, after satisfying himself by means of such tests as he may deem suitable that the applicant is qualified to drive a vehicle of such particular class or of such particular construction. In such cases, the Transport Officer shall clearly set forth the restrictions on the permit itself.

**48.** (1) The Transport Officer shall not issue a driving permit to any person unless he has personally satisfied himself that the vision, hearing and bodily and mental fitness of the applicant are such as to warrant the issue of a driving permit and that the applicant is of good character.

Physical  
fitness.  
[20 of 1978  
14 of 1979  
25 of 1997  
9 of 2017].

(2) If a permit is refused under subsection (1) other than on the grounds as to character, the applicant may claim to be subjected to a test as to his fitness or ability to drive a motor vehicle, or a motor vehicle of a particular class or description, or a motor vehicle of a particular form of construction, and if he passes such test and is not otherwise disqualified the permit shall not be refused by reason of the provisions of subsection (1).

(3) An applicant for the issue or renewal of a driving permit to drive a motor vehicle other than a motorcycle or a private motor car or an applicant for the issue or renewal of a driving permit who has attained the age of sixty-five years shall submit together with his application a medical certificate that his vision, hearing and bodily and mental fitness are such as to warrant the issue of a driving permit of the kind to which the application relates.

(4) Where the holder of a driving permit or provisional permit suffers the loss of use of an eye or limb, his permit is revoked and shall be returned to the Licensing Authority within three months of his suffering the disability.

(5) A person referred to in subsection (1) who notwithstanding his disability wishes to drive may claim to be subjected to a test as to his fitness to drive as is contemplated by subsection (1).

(6) A person who passes a test under this section shall be issued a driving permit or provisional permit, as the case may be, subject to such terms and conditions as the Transport Officer may impose, and a permit so issued may be for a period of one year.

(7) Where a person who is the holder of a driving permit or provisional permit is advised by a registered medical practitioner that he is unfit to drive by reason of some physical or mental incapacity, his permit is revoked and shall be returned forthwith to the Licensing Authority.

(8) Where the person referred to in subsection (7) wishes to resume driving upon the cesser of his incapacity, he may, having regard to the duration of his incapacity, be required by the Transport Officer to be subjected to a driving test.

(9) A person who fails to comply with the requirements of this section relating to the return of his driving permit is liable to a fine of two hundred dollars and to a further fine of five dollars for each day that the traffic violation continues.

Applications  
for driving  
permits.  
[25 of 1997].

**49.** Applications for driving permits shall be made to the Transport Officer on the approved form and shall be signed by the applicant.

Classes of  
vehicles.  
[14 of 1979  
8 of 1982  
6 of 1992  
25 of 1997].

**50.** For the purposes of this Part, there shall be the following classes of motor vehicles:

- Class 1 Motorcycles
- Class 2 Wheel tractors
- Class 3 Light motor vehicles (including private motor cars, taxis with a tare weight not exceeding 2 270 kilogrammes, maxi-taxis whatever their tare weight and light goods vehicles not exceeding a maximum gross weight of 2 950 kilogrammes)
- Class 4 Heavy motor vehicles (including motor vehicles whose maximum gross weight exceeds 2 950 kilogrammes but does not exceed 15 240 kilogrammes)

- Class 5 Extra heavy motor vehicles (including motor vehicles whose maximum gross weight exceeds 15 000 kilogrammes)
- Class 6 Motor omnibuses
- Class 7 Motor vehicles not specified in Classes 1 to 6.

**51.** (1) Subject to subsection (2), no driving permit shall be issued or endorsed as valid for a public service vehicle or for a goods vehicle exceeding the maximum gross weight of 2 540 kilogrammes to an applicant who is under the age of twenty-one years nor for any such goods vehicle or for a public service vehicle unless the applicant has driven a motor vehicle other than a motorcycle regularly during the preceding twelve months.

Restrictions on driving permits for certain vehicles.

(2) The driving permit of an applicant who has previously held a driving permit endorsed as valid for a goods vehicle or public service vehicle may, in the discretion of the Licensing Authority and subject to such conditions or tests as he may think fit to impose, be endorsed as valid for a goods vehicle or public service vehicle, as the case may be, notwithstanding that the applicant has not driven a motor vehicle other than a motorcycle regularly during the preceding twelve months.

**52.** Save as provided in section 51 any person not being under the age of seventeen years and not being otherwise disqualified shall be qualified to obtain a driving permit.

Age.

**53.** Every person undergoing a driving test under section 47 shall pay in respect of such test and certificate of competency such fee as may from time to time be prescribed. The fee for examination shall be paid irrespective of what the result of the test may be. If the examiner is a Government Officer, the fee for examination shall be credited to the public revenue, and if the examiner is not a Government Officer, the fee shall be appropriated to the examiner. The fee for the certificate of competency shall be appropriated to the association.

Driving test fees.

Colour classification of driving permits and provisional permits. [8 of 1978, 14 of 1979, 25 of 1997].

**54.** Driving permits and provisional permits shall be in the approved form. Driving permits shall be classified by a colour indication to correspond with the class of vehicle in respect of which they are issued, as follows:

- Class 1 Brown
- Class 2 White
- Class 3 Red
- Class 4 Yellow
- Class 5 Orange
- Class 6 Blue
- Class 7 Pink.

Provisional permits shall be colour classified, Green.

International driving permits. [25 of 1997].

**55.** (1) The holder of an international driving permit issued elsewhere than in Trinidad and Tobago, in accordance with the provisions of any International Convention relating to the international circulation of motor vehicles which shall have been applied to Trinidad and Tobago, shall, whilst such permit remains valid, be exempted from any requirement to hold a driving permit under this Act to drive in Trinidad and Tobago; but he shall only be entitled to drive in Trinidad and Tobago a motor vehicle of the class for which he holds an authorisation to drive in the country in which his international driving permit was issued.

(2) Where a person in Trinidad and Tobago desires to drive a motor vehicle in any other country which shall have adhered to any International Convention as aforesaid, he shall apply to the Licensing Authority for an international driving permit. The applicant must comply with the requirements of the said Convention and shall, in addition to such other particulars as may be required by the Licensing Authority, satisfy the latter that he holds a valid driving permit issued in Trinidad and Tobago and that he is ordinarily resident in Trinidad and Tobago. The Licensing Authority shall have power to issue international driving permits in accordance with any International Convention as aforesaid and on payment of the prescribed fee. Such permits shall, unless suspended by a Court, remain in effect for twelve months from the date of issue.

(3) The Licensing Authority shall keep a register of all holders in Trinidad and Tobago of valid international driving permits issued elsewhere than in Trinidad and Tobago, and of all holders of international driving permits issued by him.

**56.** (1) A person who drives or is in charge of a motor vehicle on any road or a learner who is in a motor vehicle on any road receiving instruction shall have on his person or in the motor vehicle for production as required by subsection (2) his driving permit or provisional permit as the case may be.

Production of driving permit or provisional permit.  
[8 of 1978  
21 of 1978  
14 of 1979  
25 of 1997  
9 of 2017].

(2) A Transport Officer in uniform or a police officer in uniform may require any person referred to in subsection (1) to produce his driving permit or provisional permit for examination, in order to ascertain the name and address of the holder of the permit, the date of issue and the Transport Officer by whom it was issued.

(3) A person who fails to comply with the requirements of this section is liable to a fine of five hundred dollars.

**56A.** (1) Notwithstanding section 42(1) the holder of a valid driving permit issued in any country referred to in subsection (2) shall, whilst such permit remains valid, be exempted for a period of three months from the date of his arrival in Trinidad and Tobago from any requirement to hold a driving permit issued under this Act to drive in Trinidad and Tobago; but he shall only be entitled to drive in Trinidad and Tobago a motor vehicle of the class for which he is authorised to drive by the permit of which he is the holder.

Exemption in case of valid driving permit held elsewhere.  
[17 of 1986  
9 of 2017].

(2) The Minister may by Notice published in the *Gazette* specify the countries to which subsection (1) applies.

(3) The holder of a valid driving permit referred to in subsection (1) who drives or is in charge of a motor vehicle on any road shall have such driving permit on his person or in the motor vehicle together with any travel document on which is certified his date of arrival in Trinidad and Tobago for production as required by subsection (4).

(4) A Transport Officer in uniform or a police officer may require the person referred to in subsection (3) to produce his driving permit together with the travel document on which is certified his date of arrival in Trinidad and Tobago for examination in order to ascertain the validity of the permit and his entitlement to drive in Trinidad and Tobago.

(5) A person who fails to comply with the requirements of this section is liable to a fine of five hundred dollars.

(6) In this section “valid driving permit” includes a valid driving licence or a valid certificate of competence to drive a motor vehicle issued in any country specified by the Minister under subsection (2).

Register of  
driving permits.

**57.** The Licensing Authority shall keep a register of all driving permits issued showing the name and address of the holder, the date of issue, the class of vehicle authorised and a record of any convictions by a competent Court.

Period of  
driving permit.  
[8 of 1978  
19 of 1978  
5 of 2010  
2 of 2013].

**58.** (1) Unless previously suspended, cancelled or revoked by the competent authority, a driving permit shall expire upon the expiration of—

- (a) five years from the date of issue, where on such date the holder of the permit has not yet attained the age of sixty-one years;
- (aa) five years or ten years from the date of renewal, where on such date the holder of the permit has not yet attained the age of fifty-six years;
- (ab) five years from the date of renewal, where on such date the holder of the permit has attained the age of fifty-six years but has not yet attained the age of sixty-one years;
- (b) four years from the date of issue or renewal, where on such date the holder of the permit has attained the age of sixty-one years but has not yet attained the age of sixty-two years;

- (c) three years from the date of issue or renewal, where on such date the holder of the permit has attained the age of sixty-two years but has not yet attained the age of sixty-three years;
- (d) two years from the date of issue or renewal, where on such date the holder of the permit has attained the age of sixty-three years but has not yet attained the age of sixty-four years;
- (e) one year from the date of issue or renewal where on such date the holder of the permit has attained the age of sixty-four years but has not yet attained the age of sixty-five years; or
- (f) two years from the date of issue or renewal, where on such date the holder of the permit has attained the age of sixty-five years and over.

(2) Notwithstanding subsection (1), a driving permit which is valid until 31st December 1977 is deemed to have been extended to such date in 1978 as is the anniversary date of the first issue of that permit; and if that permit was renewed in 1978 before 10th April, that renewal is deemed to be effective until the date in 1979 which is the anniversary date of the first issue of the permit.

**59.** Unless previously suspended, cancelled or revoked by competent authority, a provisional permit shall expire at the end of one year from the date of issue.

Expiration of provisional permit. [14 of 1979].

**60.** If a driving permit is lost, defaced, mutilated or rendered illegible, the Licensing Authority shall issue a new permit on payment of the prescribed fee without further driving test.

Re-issue of lost or defaced driving permit.

**61.** (1) On or after the expiration of a driving permit by effluxion of time and on application by the holder thereof for the issue of a new driving permit, the Transport Officer shall, subject to section 48 and of this section, issue a new permit to the applicant.

Restrictions on the issue of new driving permit after expiration of former one. [25 of 1997 9 of 2017].

(2) The Licensing Authority may refuse to issue a driving permit to an applicant who has, within the three years

preceding the application, been convicted of manslaughter arising out of the use of any motor vehicle or of any offence under section 70 or section 71 or of repeated offences or traffic violations under any one or more of the other sections of this Act or of the Regulations made under this Act.

(3) Any applicant aggrieved by any act, order or refusal of the Licensing Authority or of a Transport Officer may appeal to the Trinidad Transport Board whose decision shall be final.

Expired driving  
permit.  
[5 of 2010  
1 of 2016].

**61A.** (1) Subject to subsections (3) and (4), an applicant for the issue of a new driving permit who is the holder of a permit which expired, shall pay to the Licensing Authority prior to the issue of the new permit the sum of—

- (a) three hundred and fifty dollars, where the period from the date of expiration to the date of submission of the application is six months or less;
- (b) eight hundred and seventy-five dollars, where the period from the date of expiration to the date of submission of the application is more than six months but does not exceed three years; or
- (c) one thousand, seven hundred and fifty dollars, where the period from the date of expiration to the date of submission of the application is more than three years but does not exceed five years.

(2) An applicant who was absent from Trinidad and Tobago during the period specified in subsection (1)(b) or (c), shall pay to the Licensing Authority the sum of three hundred and fifty dollars.

(3) An applicant for the issue of a new driving permit who is the holder of a permit which expired for a period which exceeds five years, shall, whether such period is spent in or out of Trinidad and Tobago, be required to produce a certificate of having passed a driving test in accordance with section 47 and shall pay to the Licensing Authority the sum of three hundred and fifty dollars prior to the issue of the new permit.

(4) A citizen of Trinidad and Tobago who is sixty years of age or over is exempt from the payment of fees for the issue of a new driving permit under this section.

**61B.** (1) Notwithstanding any provision to the contrary contained in this Act and subject to subsection (2), any driving permit, taxi driver licence, badge, certificate or other document issued by the Licensing Authority which expires on or before 31st December 2020 shall be deemed to be valid until 31st March 2021.

Continuation of  
validity.  
[4 of 2020  
20 of 2020  
26 of 2020].

\*(2) The Minister may, by Order, extend any of the dates specified in subsection (1).

#### PART V

#### DRIVING AND OTHER OFFENCES AND GENERAL CONDITIONS RELATING TO THE USE OF ROADS

**62.** (1) Subject as hereinafter provided, it shall not be lawful for any person to drive a motor vehicle of any class or description on any road—

Speed limits.  
[47 of 1956  
17 of 1986  
25 of 1997  
5 of 2010  
12 of 2014  
2 of 2015  
9 of 2017  
14 of 2017].  
Second  
Schedule.

- (a) outside a built-up area at a speed greater than the speed specified in the Second Schedule as the maximum speed in relation to a vehicle of that class or description;
- (b) within a built-up area at a speed greater than the speed specified in the Second Schedule as the maximum speed in relation to a vehicle of that class or description;
- (c) whether outside or within a built-up area, in respect of which a special speed limit is imposed, at a speed exceeding the special speed limit imposed in relation to a vehicle of that class or description.

(2) The Minister may by Order impose a special speed limit with respect to any road, whether outside or within a built-up area, or any part of such road, in relation to motor vehicles generally or in relation to any class or description of motor vehicle.

(3) The Chief Technical Officer (Works) may by Order impose a special speed limit with respect to any bridge over

\*See Note on omission at page 4.

which a road passes, whether outside or within a built-up area, in relation to motor vehicles generally or in relation to any class or description of motor vehicle.

- (4) It shall be the duty of the Licensing Authority—
- (a) to erect or cause to be erected and to maintain or cause to be maintained traffic signs in such positions as may be requisite for the purpose of securing that adequate guidance is given to drivers of motor vehicles as to the places where a length of road begins, and ceases, to be a road in respect of which a special speed limit is imposed and as to the special speed limit so imposed;
  - (b) to alter or remove traffic signs as may be requisite in pursuance of any Order made under subsection (2) or (3).

(5) Any person who drives a motor vehicle on any road in contravention of the provisions of subsection (1) is liable to a fine of six thousand dollars and to be disqualified from holding or obtaining a driving permit for such period as the Court shall think fit.

It shall be a good defence for any person charged with having contravened subsection (1)(c) to prove that at the time of the alleged contravention there was a failure to comply with subsection (4) by reason of which he did not know that the length of road over which the contravention is alleged to have taken place was a length of road in respect of which the special speed limit had been imposed, and that he did not otherwise know of the imposition of the special speed limit in respect of such length of road.

(6) A constable may use a speed measuring device for the purposes of measuring the speed at which a person is driving a motor vehicle.

(6A) The Minister shall, by Order, approve the speed measuring devices which may be used for the purposes of subsection (6).

(6B) Before using a speed measuring device on any day, a constable shall satisfy himself that the device is—

- (a) in a satisfactory condition; and

(b) properly calibrated so that it indicates speed readings within a limit of error not greater or less than two kilometres per hour of the true speeds, after which the constable shall enter into the device his name, regimental number and the speed limit of the area where the speed check is to be conducted.

(6C) A constable shall, after complying with subsection (6B), record in a log book for that purpose, an entry stating that he has complied with subsection (6B).

(6D) A constable who determines with the use of a speed measuring device that a motor vehicle has exceeded the speed limit, shall cause the motor vehicle to be stopped.

(6E) Where a motor vehicle is stopped pursuant to subsection (6D), a constable shall—

- (a) inform the driver of the motor vehicle that he has—
  - (i) exceeded the speed limit as determined with the use of a speed measuring device; and
  - (ii) failed to comply with subsection (1);
- (b) deliver to the driver of the motor vehicle a printout from the speed measuring device which—
  - (i) purports to be evidence of the speed at which the driver was driving the motor vehicle;
  - (ii) includes a photograph of the vehicle identifying the registration plate;
  - (iii) bears an endorsement by the constable who operated the device, stating the date and time of the traffic violation, the place where the traffic violation occurred and that the constable is qualified to operate the device; and
  - (iv) bears the signature of the constable who operated the device.

(6F) In proceedings for a traffic violation under this section in which evidence is given of a measurement of speed

obtained by the use of a speed measuring device, a certificate purporting to be signed by a constable certifying that—

- (a) he is certified by the Commissioner of Police as being qualified to operate a speed measuring device;
- (b) the speed measuring device used by him to measure the speed at which a person was driving the motor vehicle was approved by the Minister under subsection (6A);
- (c) the measurement was made on the date and completed at the time stated in the certificate;
- (d) the speed measured by the device and expressed in kilometres per hour was the speed at which the person was driving the motor vehicle on the date and time stated in the certificate; and
- (e) the constable satisfied himself before using the device, that the device was in a satisfactory condition and properly calibrated in accordance with subsection (6B),

is admissible and is *prima facie* evidence of the particulars certified in and by the certificate.

(6G) In proceedings a traffic violation under this section—

- (a) evidence may be given of the speed at which a person was driving the motor vehicle as determined with the use of a speed measuring device operated by a constable who is certified by the Commissioner of Police as being qualified to operate the device; and
- (b) the speed so determined shall be deemed to be the speed at which he was driving the motor vehicle, unless he proves otherwise.

(6H) In proceedings for a traffic violation under this section, a certificate purporting to be signed by the Commissioner of Police that a constable named therein is qualified to operate a speed measuring device is admissible and is *prima facie* evidence of the particulars certified in and by the certificate.

(6I) In proceedings for a traffic violation under this section, evidence of the condition of a speed measuring device shall not be required unless evidence that the instrument was not in a satisfactory condition has been adduced.

(6J) In proceedings for a traffic violation under this section, a document purporting to be evidence of the speed at which a person was driving a motor vehicle shall not be admissible as evidence, unless a copy of it has been delivered to the person who was driving the motor vehicle.

(7) Subject to negative resolution of Parliament, the Minister may by Order amend the Second Schedule.

Second  
Schedule.

(8) In this section and section 62A—

“built-up area” means the City of Port-of-Spain, the City of San Fernando, the Borough of Arima, and any other area or road or portion thereof declared by Order of the Board to be a built-up area for the purposes of this section;

“constable” means—

(a) a police officer as defined in section 3 of the Police Service Act; or

Ch. 15:01.

(b) a member of the Special Reserve Police established under the Special Reserve Police Act;

Ch. 15:03.

“speed measuring device” means a device designed to measure the speed at which a person is driving a motor vehicle;

“special speed limit” means, in relation to the driving of any motor vehicle or a motor vehicle of any specified class or description on a road, a speed limit specifying a speed less than the speed which would be applicable in respect of that road and that class or description of motor vehicle under subsection (1)(a) or (b), as the case may be, and which is imposed under subsection (2) or (3).

**62A.** (1) A person shall not—

(a) equip a motor vehicle with; or

(b) use, buy, possess, manufacture, sell, or otherwise distribute,

Prohibition on  
devices  
designed to  
detect speed  
measuring  
devices.  
[12 of 2014].

any device that is designed for jamming, scrambling, neutralising, disabling, or otherwise interfering with a speed

measuring device used by a constable to measure the speed at which a person is driving a motor vehicle.

(2) A person who contravenes subsection (1) commits an offence and is liable on summary conviction to a fine of ten thousand dollars and imprisonment for six months.

Motor racing  
and speed  
trials.  
[47 of 1956  
9 of 2017].

**63.** (1) Any person who, except under and in accordance with the written permission of the Commissioner of Police, promotes or takes part in a race or trial of speed between motor vehicles on a road shall be liable to a fine of six thousand dollars.

(2) *(Repealed by Act No. 9 of 2017).*

Traffic signs.  
[47 of 1956  
17 of 1986  
9 of 2017].

**64.** (1) (a) The Licensing Authority may cause or permit traffic signs to be placed, erected or otherwise marked on or near any road, and may authorise any traffic signs so placed, erected or otherwise marked before 2nd March 1957 [that is, the date of commencement of the Motor Vehicles and Road Traffic (Amendment) Ordinance, 1956] to be retained.

47 of 1956.

(b) The Licensing Authority may not cause or permit any traffic sign to be placed, erected or otherwise marked, or authorise the retention of any traffic sign, on or near any road in respect of which an Order of the Minister made under section 65 is in force, where such sign relates to the subject matter of such Order but is not in conformity with the provisions thereof.

(2) The size, colour and type of any traffic sign may be prescribed, and in such event the traffic sign shall be of the prescribed type and substantially of the prescribed size and colour and, where the size, colour and type thereof are not prescribed, shall be of a character authorised by the Licensing Authority.

(3) Every traffic sign erected, placed, marked or retained on or near any road shall, unless the contrary is proved, be deemed—

(a) to have been lawfully so erected, placed, marked or retained; and

(b) to be of the prescribed type and substantially of the prescribed size and colour, where the size,

colour and type of the same have been prescribed, and in other cases to be of a character authorised by the Licensing Authority under this section.

(4) (a) Notwithstanding anything contained in subsection (3), after the commencement of the Motor Vehicles and Road Traffic (Amendment) Ordinance, 1956 no person other than the Licensing Authority or any person acting under his directions may, except with the general or special permission in writing of the Licensing Authority—

- (i) erect, place or mark any traffic sign on or near any road; or
- (ii) retain any traffic sign erected, placed or marked, or caused to be erected, placed or marked, by him on or near any road.

(b) Without prejudice to the operation of subsection (5), nothing in this subsection shall apply to any traffic sign—

- (i) which the owner of any land erects, places, marks or retains, or causes to be erected, placed, marked or retained, on or near any private road which is situated on such land; or
- (ii) which any person erects, places, marks or retains, or causes to be erected, placed, marked or retained, on or near any road in pursuance of any authority conferred upon him by or under any law of Trinidad and Tobago other than this Act.

(c) For the purposes of this subsection—

“owner”, in relation to any land, includes any person in lawful occupation of such land; and

“private road” means any privately owned street, road or open space to which the public are granted access conditionally.

(5) The Licensing Authority may, by notice in writing, require the owner or occupier of any land on which there is a traffic sign, or any object which so closely resembles a traffic sign that it

might reasonably be taken to be such a sign, to remove it, and if any such person fails to comply with such a notice, the Licensing Authority may himself effect or authorise the removal, doing as little damage as may be, and may, except where such sign was erected, placed, marked or retained by the Licensing Authority, recover in a Court of competent jurisdiction as a civil debt from the person so in default the expense incurred by him in doing so.

(6) The Licensing Authority or any person authorised by him in that behalf may, on any land near to or adjoining a road, cut branches of trees, or other vegetation, or remove any other thing which obscures or is likely to cause damage to a traffic sign; but the Licensing Authority or any person authorised by him shall not exercise any powers under this section until after the expiration of three days' notice in writing of his intention to exercise the relevant power given to the occupier of the land or posted up conspicuously thereon.

(7) The Licensing Authority or any person authorised by him in that behalf may enter any land near to or adjoining a road—

- (a) for the purpose of exercising any power conferred by this section upon the Licensing Authority; or
- (b) for the purpose of replacing or maintaining traffic signs.

The Licensing Authority shall do as little damage as may be in executing any work authorised by this section.

(8) In any case where a constable is for the time being engaged in the regulation of traffic in a road, or where any traffic sign, other than a traffic light signal, being a sign for regulating the movement of traffic or indicating the route to be followed by traffic, has been lawfully placed, erected, marked or retained on or near any road, then in any such case any person driving or propelling any vehicle—

- (a) who neglects or refuses to stop the vehicle or to make the vehicle proceed in or keep to a particular line of traffic when directed or signalled to do so by the constable in the execution of his duty; or

(b) who fails to conform to the indication given by the traffic sign,  
is liable to a fine of four thousand dollars.

(9) Any person who—

- (a) unlawfully places, erects, marks or retains, or causes to be placed, erected, marked or retained, any traffic sign on or near any road; or
- (b) removes, defaces, damages, alters or obscures, or in any way interferes with, any traffic sign lawfully placed, erected, marked or retained on or near any road,

is liable to a fine of five hundred dollars.

(10) Notwithstanding the provisions of section 100, “prescribed” for the purposes of this section means prescribed by Order of the Minister and any such Order may revoke any Regulations in force in respect of the size, colour and type of any traffic sign.

(11) (a) If any person owning or having any interest in any property suffers pecuniary loss by reason of any damage to such property resulting from the exercise by the Licensing Authority of the powers conferred upon him by subsection (1) to cause traffic signs to be placed, erected or otherwise marked on or near any road, compensation shall be payable to such person in respect of such loss.

(b) If any difference arises between any person claiming compensation under paragraph (a) and the Licensing Authority as to whether such person is entitled to any such compensation or as to the amount of such compensation, such difference shall, on the written application of such person or of the Attorney General, be determined—

- (i) if the amount of the compensation claimed does not exceed two hundred and forty dollars, by a Magistrate; and
- (ii) if the amount of the compensation exceeds two hundred and forty dollars, by a Judge of the Supreme Court,

Ch. 5:01. in like manner as if such Magistrate or Judge were a single arbitrator appointed pursuant to the provisions of the Arbitration Act, and the provisions of the said Act shall apply accordingly.

(c) Compensation payable under this subsection shall be defrayed out of moneys provided for the purpose by Parliament.

Parking of vehicles and one-way roads. [47 of 1956 17 of 1986 5 of 2010 9 of 2017].

**65.** (1) The Minister may by Order—

- (a) prohibit or regulate the parking of vehicles on any road; or
- (b) prohibit the driving of any vehicle on any specified road otherwise than in a specified direction.

(2) An Order made under this section may prescribe in respect of any contravention thereof a penalty not exceeding a fine of three thousand dollars and any such Order may revoke any Regulations in force in respect of any of the matters specified in subsection (1).

(3) Where any provision in an Order made under this section conflicts with any Order made to meet the exigencies of a special occasion, or notice issued under section 68 the operation of such provision shall be suspended during the continuance in force of such last mentioned Order or notice, as the case may be.

Drivers to comply with traffic directions. [3 of 1969 5 of 2010 12 of 2014 9 of 2017].

**66.** Where a police constable in uniform is engaged in the regulation of traffic in a road or where a traffic sign, other than a traffic light signal being a sign of the prescribed size, colour and type or of another character authorised by the Licensing Authority under section 64 or where a notice of the Commissioner of Police under section 68 has been lawfully placed on or near a road, a person driving or propelling a vehicle who—

- (a) neglects or refuses to stop the vehicle or to make it proceed in or keep to, a particular line of traffic when directed to do so by the police constable in the execution of his duty; or
- (b) fails to comply with the indication given by the sign or the notice,

is liable to a fine of two thousand dollars for the first traffic violation and to a fine of four thousand dollars for every traffic violation thereafter.

**66A.** (1) A person driving or propelling a vehicle, who fails to comply with the indication given by a traffic light signal is liable to a fine of five thousand dollars for the first traffic violation and a fine of seven thousand dollars for any subsequent traffic violation.

Failure to  
comply with a  
traffic light.  
[9 of 2017].

(2) This section does not apply to an emergency vehicle.

**67.** (1) Where it appears to the Commissioner of Police expedient to do so for the purpose of carrying out an experimental scheme of traffic control he may, with the consent of the Minister, and after giving such notice as the Minister may direct, make Regulations for regulating vehicular traffic in any manner specified in the Third Schedule.

Experimental  
traffic schemes.  
[3 of 1969  
17 of 1986  
9 of 2017].

Third  
Schedule.

(2) Any provision contained in Regulations under this section may be made so as to apply at all times on specified days or during specified periods, and either throughout the day or during any specified part of the day, and to vehicular traffic generally or to such traffic of any class or description specified in the Regulations, and Regulations under this section may make different provision for different classes or descriptions of traffic.

(3) Any person who contravenes Regulations under this section is liable to a fine of seven hundred and fifty dollars for the first traffic violation and to a fine of one thousand dollars for every traffic violation thereafter.

(4) Where there is any conflict or variance between Regulations made under this section and Regulations made by the President, the Regulations made by the President shall be read with such modifications as are necessary to bring them into conformity with those of the Commissioner under this section.

(5) Regulations under this section shall not continue in force for a period longer than three months after the making thereof, together with such further period (if any) not exceeding

six months as the Minister may at any time before the expiration of the Regulations direct.

(6) Regulations made under this section shall be published in the *Gazette* and in at least one daily newspaper circulating in Trinidad and Tobago.

Temporary prohibition or restriction of traffic on roads. [3 of 1969, 5 of 2010, 9 of 2017].

**68.** (1) Subject to this section in any case where a road is liable to be thronged or obstructed, the Commissioner of Police may by Order restrict or prohibit the use of that road or of any part thereof by vehicles or by vehicles of any particular class or description to such extent and subject to such conditions or exceptions as he may consider necessary.

(2) The Commissioner may at any time by notice restrict or prohibit temporarily the use of a road or any part of a road by vehicles or by vehicles of any particular class or description for the purpose of—

- (a) avoiding danger or obstruction to persons or other traffic using the road or any other road; or
- (b) preventing damage to the road or to any building on or near the road; or
- (c) facilitating the passage of vehicular traffic on the road or any other road or from any premises.

(3) The provisions which may be made by a traffic regulation, Order or notice shall be any provision prohibiting, restricting or regulating the use of a road or any part of the width thereof by vehicular traffic or by such traffic of any class or description specified in the Order, either generally or subject to exceptions so specified, and either at all times or at times on days or during periods so specified and, without prejudice to the generality of this subsection, any provision—

- (a) requiring such traffic to proceed in a specified direction or prohibiting its so proceeding;
- (b) specifying the part of the carriageway to be used by such traffic proceeding in a specified direction;
- (c) prohibiting or restricting the parking, stopping or waiting of vehicles or the loading and unloading of vehicles;

- (d) prohibiting the use of roads by through traffic;
- (e) prohibiting or restricting overtaking;
- (f) regulating the speed of vehicles.

(4) An Order made or notice issued under the above provisions of this section may suspend any statutory provision of a description which could have been contained in the Order or notice or, in the case of an Order under subsection (1), any statutory provision prohibiting the use of roads by through traffic, and any such provision (other than one contained in the Order or notice) shall have effect subject to the Order or notice.

(5) An Order under subsection (1) shall not without the approval of the Minister continue in force for a longer period than one month from the making thereof.

(6) A notice issued under subsection (2) shall not continue in force for a longer period than fourteen days from the date thereof.

(7) Any person who uses or permits the use of a vehicle in contravention of a restriction or prohibition imposed by an Order under subsection (1) is liable to a fine of one thousand, five hundred dollars for the first traffic violation and to a fine of three thousand, five hundred dollars for every traffic violation thereafter.

(8) Any person who unlawfully and without just cause or excuse removes from the position where it is placed, alters or defaces a notice of the Commissioner under subsection (2) is liable to a fine of seventy-five dollars.

**69.** (1) Notwithstanding any rule of law to the contrary, but subject to this section, a motor vehicle shall not be parked—

- (a) at anytime of the day or night on any portion of—
  - (i) Knox Street, between St. Vincent Street and Abercromby Street; and
  - (ii) Abercromby Street, between Hart Street and Knox Street,

in the City of Port-of-Spain, by any person not being a member of the House of

Restrictions on  
parking in  
certain streets.  
[3 of 1969  
5 of 2010].

Representatives or of the Senate or his servant or agent; and

(b) at such times and on such portion of any road as are designated by the Minister by Notification, by any person not being—

(i) a member of the diplomatic corps and his staff (duly authorised by the Head of Mission) representing such countries and institutions as are specified in the Notification or his servant or agent;

(ii) a person belonging to such other classes of persons as are specified in the Notification or his servant or agent,

and any statutory provision respecting parking on such roads (other than one contained in the Notification) shall have effect subject to the Notification.

(2) Where a member of the House of Representatives or of the Senate or a member of the diplomatic corps or his staff or other person as is mentioned in subsection (1)(b)(ii) or their servants or agents parks a motor vehicle on a road pursuant to this section, the motor vehicle shall have attached to it, in the prescribed position, a special identification mark of the kind prescribed by the Minister.

(3) Any person who contravenes the provisions of subsection (1) is liable to a fine of four thousand dollars.

Driving when under influence of liquor. [22 of 2000, 19 of 2007, 2 of 2015, 9 of 2017].

**70.** (1) Any person who, when driving or attempting to drive or when in charge of a motor vehicle on a road, is under the influence of a drug to such an extent as to be incapable of having proper control of the vehicle, is liable on first conviction to a fine of twelve thousand dollars and to imprisonment for three years and on any subsequent conviction to a fine of twenty-two thousand, five hundred dollars and to imprisonment for five years.

Disqualification from driving upon conviction.

(2) A person convicted of—

(a) two consecutive offences under this section shall, unless the Court for special reasons thinks fit to

order otherwise and without prejudice to the power of the Court to order a longer period of disqualification, be disqualified for a period of three years from the date of the conviction from holding or obtaining a driving permit; and

(b) a third conviction for a like offence, shall be permanently disqualified from holding or obtaining a driving permit.

(3) Any constable may arrest without a warrant any person committing an offence under this section.

(4) The Minister may, by Order, approve the device to be used for the detection of drugs pursuant to subsection (1).

**70A.** (1) No person shall drive or attempt to drive, or be in charge of a motor vehicle on a road or other public place if he has consumed alcohol in such a quantity that the proportion thereof in his breath or blood exceeds the prescribed limit.

Driving or being in charge of a vehicle while blood alcohol levels exceed prescribed limit. [19 of 2007 2 of 2015].

(2) Any person who contravenes subsection (1) is guilty of an offence and is liable—

(a) in the case of a first conviction, to a fine of twelve thousand dollars or to imprisonment for three years; and

(b) in the case of a second or subsequent conviction, to a fine of twenty-two thousand, five hundred dollars or to imprisonment for five years.

(3) A person convicted of—

(a) two consecutive offences under this section shall, unless the Court for special reasons thinks fit to order otherwise and without prejudice to the power of the Court to order a longer period of disqualification, be disqualified for a period of three years from the date of the conviction from holding or obtaining a driving permit; and

(b) a third conviction for a like offence, shall be permanently disqualified from holding or obtaining a driving permit.

(4) No person shall be convicted under this section of being in charge of a motor vehicle under subsection (1) if he proves that at the material time, the circumstances were such that there was no likelihood of his driving the motor vehicle while there was alcohol in his breath or blood in a proportion exceeding the prescribed limit.

(5) Any constable may arrest without a warrant, any person committing an offence under this section.

Breath test.  
[19 of 2007  
5 of 2010  
2 of 2015].

- 70B.** (1) Where a constable has reasonable cause to suspect—
- (a) that a person driving or attempting to drive or in charge of a motor vehicle on a road or other public place has alcohol in his breath or blood exceeding the prescribed limit or is in breach of section 70;
  - (b) that a person has been driving or attempting to drive or been in charge of a motor vehicle on a road or other public place with alcohol in his breath or blood exceeding the prescribed limit and that the person still has alcohol in his breath or blood; or
  - (c) that a person has been driving, attempting to drive or been in charge of a motor vehicle on a road or other public place and has committed an offence against this Act whilst the vehicle was in motion,

he may, subject to subsection (4), require him to provide a specimen of breath for a breath test at or near the place where the requirement is made.

(2) No requirement may be made by virtue of paragraph (b) or (c) of subsection (1) unless it is made as soon as reasonably practicable after the commission of the offence.

(3) Where an accident occurs involving a motor vehicle on a road, a constable may, subject to subsection (4), on arriving at the place of the accident, require the driver of the vehicle, whom the constable has reasonable cause to believe was driving

or attempting to drive the vehicle after consuming alcohol in a quantity that the proportion of the alcohol in his breath or blood exceeds the prescribed limit at the time of the accident, to provide a specimen of breath for a breath test—

- (a) either at or near the place where the accident occurred; or
- (b) at a police station within reasonable proximity to the place where the accident occurred.

(4) Where a person referred to in subsection (3) is at a hospital as a patient, he may be required by a constable to give a specimen of breath at the hospital but no such requirement may be made unless the medical practitioner in charge of his case—

- (a) is given prior notice of the proposal to make the requirement; and
- (b) does not object to the provision of a specimen on the ground that its provision or the requirement to provide it would be prejudicial to the proper care or treatment of the patient.

(5) Where a person, without reasonable excuse, fails to provide a specimen of breath under subsection (1), (3), (4) or (8) he is guilty of an offence and shall be liable on conviction to a fine of twelve thousand dollars or to imprisonment for three years.

(6) A constable may arrest without warrant any person who, as a consequence of a breath test, is found to have a proportion of alcohol in his breath exceeding the prescribed limit but no such arrest may be made while the person is at a hospital as a patient.

(7) Where a person required by a constable under subsection (1), (3), (4) or (8) to provide a specimen of breath for a breath test fails to do so and the constable has reasonable cause to suspect that the person has alcohol in his breath or blood above the prescribed limit, the constable may, without prejudice to sections 70(3) and 70A(5), arrest the person without a warrant but no such arrest may be made if the person is at a hospital as a patient.

(8) A person arrested under subsection (7), section 70(3) or 70A(5) shall, while at a police station, be given an opportunity to provide a specimen of breath for a breath test at the police station.

(9) The Minister may, by Order, approve the device to be used for the purpose of obtaining an indication of alcohol in a person's breath.

Breath analysis.  
[19 of 2007  
2 of 2015].

**70C.** (1) Subject to subsections (2) and (3) where—

- (a) any person required by a constable under section 70B to undergo a breath test fails to undergo that test; or
- (b) in consequence of a breath test carried out under section 70B, it is indicated that there may be present in that person's breath, a concentration of alcohol in excess of the prescribed limit,

the constable may require that person to submit, in accordance with the directions of the constable, to a breath analysis and on any such requirement, warn him that a failure to so submit may render him liable to prosecution.

(2) The breath analysis required under subsection (1) shall be carried out by a constable authorised in that behalf by the Minister to whom responsibility for national security has been assigned—

- (a) at or near the place where the requirement is made if facilities for the specimens to be taken are available and it is practicable to conduct the analysis there; or
- (b) at a police station,

as the constable may direct.

(3) For the purpose of the breath analysis—

- (a) a person must provide two separate specimens of breath for analysis;
- (b) such specimens must be provided in accordance with the directions of the constable referred to in subsection (2);

- (c) there must be an interval of not less than two minutes and not more than ten minutes between the provision of specimens; and
  - (d) the reading from the specimen that indicates the lower concentration of alcohol in the person's breath shall be taken to be the result of the breath analysis.
- (4) A constable shall not require any person to undergo a breath test or to submit to a breath analysis—
- (a) if the person has been admitted to hospital for medical treatment and the medical practitioner in immediate charge of his treatment has not been notified of the intention to make the requisition, or objects on the ground that compliance therewith would be prejudicial to the proper care or treatment of that person;
  - (b) if it appears to the constable that it would, by reason of injuries sustained by the person, be dangerous to that person's medical condition to undergo a breath test or submit to a breath analysis; or
  - (c) at that person's usual place of abode.
- (5) Notwithstanding subsection (4)(c), a person may be required to submit to a breath test at that person's usual place of abode—
- (a) if the constable has reasonable cause to believe that—
    - (i) the person was involved in an accident on a road or other public place within the preceding two hours resulting in death or serious injury; and
    - (ii) at the time when the accident occurred, the person had an alcohol level in his breath exceeding the prescribed limit; and
  - (b) if it was not feasible for a constable to require the person to submit to a breath test at the scene of the accident.

(6) Any person who—

- (a) upon being required under subsection (1) to submit to a breath analysis fails to do so in accordance with the directions of a member of the Police Service; or
- (b) wilfully does anything to alter the concentration of alcohol in his breath or blood between the time of the event referred to in section 70B (in respect of which he has been required to undergo a breath test) and the time when he undergoes that test or, if he is required to submit to a breath analysis, the time when he submits to that analysis,

is guilty of an offence and is liable—

- (c) in the case of a first conviction, to a fine of twelve thousand dollars or to imprisonment for three years; and
- (d) in the case of a second or subsequent conviction, to a fine of twenty-two thousand, five hundred dollars or to imprisonment for five years.

(7) It shall be a defence to a prosecution for an offence under subsection (5)(a) if the accused satisfies the Court that he was unable on medical grounds at the time he was required to do so, to undergo a breath test or to submit to a breath analysis, as the case may be.

(8) Within one hour after a person has submitted to a breath analysis, the constable operating the breath analysing instrument shall deliver to that person, a statement in writing signed by that constable specifying—

- (a) the concentration of alcohol determined by the analysis to be present in that person's breath and expressed in microgrammes of alcohol in one hundred millilitres of breath; and
- (b) the time of day and the day on which the breath analysis was completed.

(9) In proceedings for an offence under section 70, 70A or 70C—

- (a) evidence may be given of the concentration of alcohol present in the breath of the accused as determined by the breath analysing instrument operated by the constable authorised in that behalf under subsection (2); and
- (b) the concentration of alcohol so determined shall be deemed to be the concentration of alcohol in the breath of the accused at the time of the occurrence of the event mentioned in section 70B(1)(a) unless the accused proves that the concentration of alcohol in his breath at the time did not exceed the prescribed limit.

(10) In proceedings for an offence under this section, a certificate purporting to be signed by a constable certifying that—

- (a) he is authorised by the Minister to whom responsibility for national security has been assigned to operate breath analysing instruments;
- (b) a person named therein submitted to a breath analysis;
- (c) the apparatus used by him to make the breath analysis was a breath analysing instrument approved by the Minister;
- (d) the analysis was made on the date and completed at the time stated in the certificate;
- (e) a concentration of alcohol determined by the breath analysing instrument and expressed in microgrammes of alcohol in one hundred millilitres of breath was present in the breath of that person on the date and at the time stated in the certificate; and
- (f) a statement in writing required by subsection (8) was delivered in accordance with that subsection,

shall be *prima facie* evidence of the particulars certified in and by the certificate.

(11) In proceedings for an offence under this section, a certificate purporting to be signed by the Minister responsible for national security that the constable named therein is authorised to operate breath analysing instruments, shall be *prima facie* evidence of the particulars certified in and by the certificate.

(12) In any proceedings for an offence under this section, evidence of the condition of a breath analysing instrument or the manner in which it was operated shall not be required unless evidence that the instrument was not in proper condition or was not properly operated has been adduced.

(13) The Minister may, by Order, approve the device to be used for the quantitative measuring of the proportion of alcohol in a person's breath.

Laboratory test.  
[19 of 2007].

**70D.** (1) Subject to subsections (2) and (3), in the course of an investigation as to whether a person has committed an offence under section 70A, a constable may require a person under investigation to provide a specimen of blood for a laboratory test if the person is unable, by reason of his physical condition, to provide a specimen of breath for a breath test.

(2) A person shall not be required to provide a specimen of blood for a laboratory test under subsection (1) if he is at a hospital as a patient and the medical practitioner in immediate charge of his case is not first notified of the proposal to make the requirement or objects to the provision of a specimen on the ground that the requirement to provide such specimen could be prejudicial to the proper care or treatment of that person.

(3) A constable shall not require a person to submit a specimen of blood for a blood analysis once a breath analysis has been carried out in respect of that person and the result is available.

(4) Nothing in subsections (1) to (3) shall affect the provisions of section 70F.

(5) For the purposes of this section and sections 70A, 70E and 70F, where any person is required to provide a specimen of blood, such specimen shall be taken only—

- (a) with the consent of that person;
- (b) at a hospital; and

(c) by a medical practitioner or qualified laboratory technician.

(6) The Minister to whom responsibility for health is assigned, shall by Order designate laboratories for the purpose of giving effect to this section.

**70E.** (1) Any person who is under investigation in relation to an offence under section 70A and who refuses to provide a sample of blood for a blood test when required to do so under section 70D(1), is guilty of an offence and shall be liable—

Refusal to consent to taking of or providing specimen. [19 of 2007 2 of 2015].

(a) in the case of a first conviction, to a fine of twelve thousand dollars or to imprisonment for three years; and

(b) in the case of a second or subsequent conviction, to a fine of twenty-two thousand, five hundred dollars or to imprisonment for five years.

(2) A person shall not be treated as failing to provide a specimen of blood if he is unable to do so for the reasons set out in section 70D(2).

**70F.** (1) For the purposes of any proceedings for an offence under section 70A, a certificate signed by an authorised analyst, certifying the proportion of alcohol found in a specimen identified by the certificate shall, subject to subsection (3), be evidence of the matters so certified and of the qualifications of the analyst.

Ancillary provisions as to evidence in proceedings for an offence under section 70A or 70B. [19 of 2007].

(2) For the purposes of any proceedings for an offence under section 70A, a certificate purporting to be signed by the medical practitioner that he took a specimen of blood from a person with that person's consent shall, subject to subsection (3), be evidence of the matters so certified and of the qualifications of the medical practitioner.

(3) Subsections (1) and (2) shall not apply to a certificate tendered on behalf of the prosecution—

(a) unless a copy has been served personally on the accused or on his Attorney-at-law or by prepaid registered post not less than seven days before the hearing or trial; or

(b) if the accused, not less than seven days before the hearing or trial, or within such further time as the Court may in the circumstances of the case allow, has served notice on the prosecution requiring the attendance at the hearing or trial of the person by whom the certificate was signed.

(4) Where, in proceedings for an offence under section 70A the accused, at the time a specimen of blood was taken from or provided by him in accordance with this Act, asked to be supplied with such a specimen, evidence of the proportion of alcohol found in the specimen shall not be admissible on behalf of the prosecution unless—

(a) the specimen is either one of two taken or provided on the same occasion or is part of a single specimen which was divided into two parts at the time it was taken or provided; and

(b) the other specimen or part was supplied to the accused.

(5) The Minister to whom responsibility for health is assigned may designate qualified persons to conduct laboratory tests in accordance with this Act, to determine the concentration of alcohol in a person's blood.

Interpretation  
of sections 70A  
to 70F.  
[19 of 2007  
5 of 2010].

**70G.** (1) In sections 70A to 70F, except so far as the context otherwise requires—

“authorised analyst” means a person designated as such by the Minister to whom responsibility for health is assigned, under section 70F(5);

“breath analysis” means the quantitative measuring of the proportion of alcohol in a person's breath, carried out by means of a device prescribed for the purpose by the Minister, under section 70C(13);

“breath test” means a test for the purpose of obtaining an indication of the proportion of alcohol in the person's breath carried out by means of a device approved for the purpose of such a test by the Minister, under section 70B(9);

“constable” means a member of the Police Service or a Transport Officer;

“drug” includes any intoxicant other than alcohol;

“fail”, in relation to providing a specimen, includes refuse;

“hospital” means an institution which provides medical or surgical treatment for in-patients or out-patients and includes a laboratory accredited under the Standards Act and recognised by the Minister to whom responsibility for health is assigned, as a place where laboratory tests are carried out;

Ch. 82:03.

“laboratory test” means the analysis of a specimen provided for the purpose;

“the prescribed limit” means in respect of—

- (a) breath alcohol concentration, thirty-five microgrammes of alcohol in one hundred millilitres of breath or such other proportion as may be prescribed; and
- (b) blood alcohol concentration, eighty milligrammes of alcohol in one hundred millilitres of blood, or such other proportion as may be prescribed.

(2) References in section 70B to providing a specimen of breath shall be construed as references to providing a specimen thereof in sufficient quantity to enable a breath test to be carried out.

**70H.** The Minister may, subject to affirmative resolution of Parliament, make Regulations for giving effect to the purposes and provisions of sections 70A to 70G.

Regulations.  
[19 of 2007].

**71.** (1) Any person who causes the death of another person by driving a motor vehicle dangerously on a road, commits an offence and is liable on conviction on indictment to imprisonment for fifteen years.

Causing death  
by dangerous  
driving.  
[22 of 2000].

(2) A person convicted of an offence under this section shall, without prejudice to the power of the Court to order a longer period of disqualification, be disqualified for a period of fifteen years from the date of the conviction from holding or obtaining a driving permit, and on a second conviction for a like offence he shall be permanently disqualified from holding or obtaining a driving permit.

(3) Any constable may arrest without warrant the driver of any motor vehicle who commits an offence under this section within his view, if he refuses to give his name and address, or if the constable has reason to believe that the name or address so given is false, or if the motor vehicle does not bear an identification plate.

Dangerous  
driving.  
[22 of 2000].

**71A.** (1) A person who drives a motor vehicle dangerously on a road commits an offence and is liable on summary conviction to a fine of ten thousand dollars and to imprisonment for five years.

(2) A person convicted of an offence under this section shall, without prejudice to the power of the Court to order a longer period of disqualification, be disqualified for a period of twelve months from the date of the conviction from holding or obtaining a driving permit, and on a third conviction for a like offence he shall be permanently disqualified from holding or obtaining a driving permit.

(3) Section 71(3) shall apply where an offence is committed under this section.

Interpretation.  
[22 of 2000].

**71B.** (1) For the purposes of sections 71 and 71A a person is to be regarded as driving dangerously if—

- (a) the way in which he drives falls below what would be expected of a competent and careful driver; and
- (b) it would be obvious to a competent and careful driver that driving in that way would be dangerous.

(2) A person is also to be regarded as driving dangerously for the purposes of sections 71 and 71A if it would be obvious to a competent and careful driver that driving the vehicle in its current state would be dangerous. In determining the state of a vehicle, regard may be had to anything attached to or carried on or in it and to the manner in which it is attached or carried.

(3) In subsections (1) and (2) “dangerous” refers to danger either of injury to any person or of serious damage to property; and in determining for the purposes of those subsections what would be expected of, or obvious to, a competent and careful driver in a particular case, regard shall be

had not only to the circumstances of which he would be expected to be aware but also to any circumstances shown to have been within the knowledge of the driver.

**72.** Any person who drives a motor vehicle on a road without due care and attention or without reasonable consideration for other persons using the road, is liable, on summary conviction, to a fine of one thousand dollars and to be disqualified for holding or obtaining a driving permit for such period as the Court thinks fit. On a second or subsequent conviction for a like offence the period of disqualification shall not be less than one month.

Careless driving.  
[9 of 2017].

**73.** (1) Subject to subsections (2) and (3), where a person is prosecuted for an offence under any of the preceding sections relating respectively to the maximum speed at which motor vehicles may be driven, dangerous driving or causing death by dangerous driving, and to careless driving, he shall not be convicted unless either—

Warning to be given of intended prosecution.  
[22 of 2000].

- (a) he was warned on the day the offence was committed that the question of prosecuting him for an offence under some one or other of the sections aforesaid would be taken into consideration; or
- (b) within fourteen days of the commission of the offence a summons for the offence was served on him; or
- (c) within the said fourteen days a notice of the intended prosecution specifying the nature of the alleged offence and the time and place where it is alleged to have been committed was served on or sent by registered post to him or to the person registered as the owner of the vehicle at the time of the commission of the offence.

(2) Failure to comply with the requirement of subsection (1) shall not be a bar to the conviction of the accused in any case where the Court is satisfied that—

- (i) neither the name and address of the accused nor the name and address of the registered owner of the vehicle, could with reasonable diligence have been

ascertained in time for a summons to be served or for a notice to be served or sent as aforesaid; or

- (ii) the accused by his own conduct contributed to the failure.

(3) The requirement of subsection (1) shall in every case be deemed to have been complied with unless and until the contrary is proved.

Taking vehicle  
without consent  
of owner.

**74.** (1) (a) Any person who uses a vehicle without the consent of the owner or other lawful authority, is guilty of an offence.

(b) A person shall not be convicted under this section if he proves either—

- (i) that he had good reason to believe, and did in fact believe, that the owner of the vehicle would, had he been present, have consented to the vehicle being used in the manner in which it was used; or
- (ii) that he had reasonable cause to believe, and did in fact believe, that he had lawful authority to use the vehicle.

(2) If any person is convicted under this section, the Magistrate may, if he thinks fit, either in addition to or without inflicting any punishment, order that the person convicted do pay to the owner of the vehicle either or both of the following sums, namely—

- (a) such sum as, in the opinion of the Magistrate, would have been charged if the vehicle had been hired by the person convicted;
- (b) such sum as, in the opinion of the Magistrate, represents fair compensation for any damage done to and for the use of the vehicle.

(3) If on the trial of any indictment for stealing a vehicle the jury are of opinion that the defendant was not guilty of stealing the vehicle but was guilty of an offence under this section, the jury may find him guilty of an offence under this section and thereupon he shall be liable to be punished accordingly.

(4) Any constable may arrest without a warrant any person suspected by him of having committed an offence under this section.

75. Any person who, without the knowledge or permission of the owner, gets onto or attempts to manipulate any of the levers, the starter, brakes or machinery of a motor vehicle, or in any way interferes with or damages a motor vehicle while the vehicle is on a road or parking place, is guilty of an offence and is liable on summary conviction to a fine of five thousand dollars and imprisonment for nine months; but a person shall not be convicted under this section when such motor vehicle is obstructing his own or another motor vehicle.

Interfering with motor vehicle. [9 of 2017].

76. (1) It shall not be lawful for more than one person to be carried on a road on a bicycle not propelled by mechanical power unless it is constructed for the carriage of more than one person.

Restrictions on persons being towed on bicycles.

(2) If any person is carried on such a bicycle in contravention of this section, each of the persons carried shall be liable on first conviction to a fine of two hundred dollars and on any subsequent conviction to a fine of four hundred dollars.

(3) In this section references to a person carried on a bicycle shall include reference to a person riding a bicycle.

77. (1) It shall not be lawful for more than two persons to ride abreast on a road either upon motorcycles or upon bicycles not propelled by mechanical power; but a person shall not be liable under this section in respect of the overtaking of two persons so riding and in the absence of other traffic on the road at the point of overtaking.

Restriction on cyclists riding abreast or holding on to other moving vehicles. [5 of 2010 9 of 2017].

(2) It shall not be lawful for any person while riding a motorcycle, or a bicycle not propelled by mechanical power, on a road—

- (a) to hold on to any other moving vehicle; or
- (b) to ride such motorcycle or bicycle without at least one hand being on the handle bars of such motorcycle or bicycle.

(3) It shall not be lawful for more than one person in addition to the driver to be carried on any two-wheeled motorcycle, nor shall it be lawful for any such one person to be so carried otherwise than sitting astride the motorcycle and on a proper seat securely fixed to the motorcycle behind the driver's seat.

(4) Any person who contravenes this section is liable to a fine of two thousand, five hundred dollars.

Distribution of advertisements from vehicles prohibited. [11 of 1959 5 of 2010 9 of 2017].

**78.** (1) Any person who throws or distributes from any vehicle on any road any picture, print or any other article of whatsoever nature by way of advertisement, or any handbill, is liable on summary conviction to a fine of two thousand dollars.

(2) *(Repealed by Act No. 9 of 2017).*

Duty to stop, give aid, and report in case of accident. [9 of 2017].

**79.** (1) Where, owing to the presence of a vehicle on a road, an accident occurs whereby injury or damage is caused to any person, animal or property, the driver of such vehicle shall immediately stop, and—

- (a) if any person has been injured in the accident, the driver shall render such person aid, and if the person wishes to be taken to hospital or to a doctor, or is unconscious, convey or cause to be conveyed the injured person without delay to the nearest hospital or to a doctor;
- (b) if requested by the injured person or by the owner of the damaged property or some person on such owner's behalf, the driver shall give his name and address and particulars of his driving permit and the name and address of the owner of the vehicle;
- (c) unless a report is made by the driver at the time and place of the accident to a member of the Police Service, the person riding in, driving or in charge of the vehicle shall proceed with all proper despatch to the nearest Police Station or police constable in uniform and shall report the accident, and shall give his name and address

and the name and address of the owner of the vehicle and the names of any persons in the vehicle at the time of the accident.

(2) Any person who contravenes this section commits an offence and is liable to a fine of five thousand dollars and imprisonment for nine months.

**PART VA**

**RED-LIGHT CAMERA SYSTEM**

**79A.** For the purposes of this Part—

“citation notice” means the Notice approved by the Authority under section 79G;

Definitions.  
[9 of 2017  
15 of 2020].

“Court” has the meaning assigned by the Summary Courts Act;

Ch. 4:20.

“fixed penalty” means the penalty prescribed under section 84;

“Inspection Officer” means a constable, Transport Officer or Traffic Warden certified by the Commissioner of Police as trained to analyse and certify the authenticity of photographic images or video recordings obtained with a red-light camera;

“Magistracy Registrar and Clerk of the Court” has the meaning assigned by the Criminal Division and District Criminal and Traffic Courts Act, 2018;

Ch. 4:22.

“notice to contest” means a Notice requesting a hearing by a Court in respect of a traffic violation indicating that the owner wishes to contest responsibility for the payment of a fixed penalty as stated in the Citation Notice;

“red-light camera” means an electronic device, approved by the Minister under section 79B, for the purpose of capturing and producing photographic images and video recordings of traffic violations committed under section 66A.

**79B.** (1) The Licensing Authority may cause or permit a red-light camera to be installed on, or near any traffic light signal.

Installation of  
red-light  
camera.  
[9 of 2017].

(2) The Minister may by Order approve the red-light camera for the purposes of this Part.

Unlawful interference.  
[9 of 2017].

**79C.** A person who unlawfully interferes with a red-light camera or its proper functioning commits an offence and is liable on summary conviction to a fine of ten thousand dollars.

Owner deemed responsible.  
[9 of 2017].

**79D.** (1) For the purposes of this Part, where a red-light camera captures a photographic image or video recording of a motor vehicle that fails to comply with the indication given by a red light of a traffic light signal in contravention of section 66A, the owner of the motor vehicle involved in the traffic violation shall be responsible for ensuring the payment of the fixed penalty stipulated in the citation notice served under section 79H.

(2) Where there is more than one owner of the motor vehicle referred to in subsection (1), the owners shall be jointly responsible for ensuring the payment of the fixed penalty.

(3) Where an owner pays a fixed penalty under this Part, he may recover the sums paid from the person who was driving the motor vehicle at the time the photographic image or video recording referred to in subsection (1) was captured.

Photographic image or video recording captured by red-light camera system.  
[9 of 2017].

**79E.** A photographic image or video recording of a motor vehicle captured by a red-light camera shall be evidence—

- (a) that the motor vehicle was used in the commission of a traffic violation under section 66A; and
- (b) that the information shown on the photographic image or video recording is a true and accurate record of the registration number of the motor vehicle used in the commission of the traffic violation.

Preparation of citation notice.  
[9 of 2017].

**79F.** (1) Where a red-light camera captures a photographic image or video recording of the commission of a traffic violation under section 66A, an Inspection Officer shall, within thirty days of the commission of the traffic violation, prepare a citation notice to be served on each owner of the motor vehicle involved in the commission of the traffic violation.

(2) The citation notice prepared under subsection (1) shall state that the owner has the option of either—

- (a) paying the stipulated fixed penalty for the traffic violation, within the time specified in the citation notice; or
- (b) filing a notice to contest within the time specified in the citation notice in accordance with section 79J.

**79G.** A citation notice prepared under section 79F shall be in the form approved by the Licensing Authority and published in the *Gazette*, and shall include—

Form of  
citation notice.  
[9 of 2017  
15 of 2020].

- (a) the date, time and place of the traffic violation;
- (b) the section of the written law creating the traffic violation and such particulars of the traffic violation as are required for proceedings under the Summary Courts Act;
- (c) the photographic image showing the commission of the traffic violation and the registration number of the motor vehicle involved in the commission of the traffic violation;
- (d) the certificate of the Inspection Officer;
- (e) the fixed penalty that is to be paid;
- (f) the payee to whom the fixed penalty may be paid;
- (g) the time specified within which the fixed penalty may be paid in accordance with section 79I(1); and
- (h) that the owner may file a notice to contest in accordance with section 79J and in such manner as may be specified.
- (i) ***(Deleted by Act No. 15 of 2020).***

Ch. 4:20.

**79H.** (1) A citation notice prepared under section 79F shall be served on each owner of a motor vehicle involved in a traffic violation under section 66A—

Service of  
citation notice.  
[9 of 2017  
15 of 2020].

- (a) by delivering it to each owner or some adult at his usual or last known place of residence

or any address furnished by him to the Licensing Authority; or

- (b) by sending it by way of normal post or registered post to the owner at his usual or last known place of residence or business or any other address furnished by him to the Licensing Authority.

(2) In the case of a citation notice to be served on an owner whose usual or last known place of residence cannot with reasonable diligence be ascertained, service may be effected by means of publication in at least one newspaper in daily circulation in Trinidad and Tobago or electronic transmission through e-mail.

(3) Service of a citation notice under this section is deemed to be effected on the owner on the eighth day following the date on which the notice is delivered, published, or electronically transmitted.

Payment of  
fixed penalty.  
[9 of 2017].

**79I.** (1) Where service of a citation notice has been effected in accordance with section 79H, the owner of the motor vehicle shall, unless he files a notice of contest, pay the fixed penalty within forty-five days from the deemed date of service under section 79H(3) of the citation notice or such longer period as the Minister may prescribe by Order.

- (2) Payment of a fixed penalty under this section shall be—
- (a) accompanied by the citation notice served under section 79H; and
- (b) paid to a payee prescribed by the Minister under section 88D.

(3) Where the fixed penalty is duly paid in accordance with the citation notice, no person shall be liable to any sanction for the traffic violation in respect of which the citation notice was served.

Filing of notice  
of contest.  
[9 of 2017  
15 of 2020].

**79J.** (1) Where an owner of a motor vehicle is served with a citation notice under section 79H for a traffic violation and is desirous of contesting the traffic violation in the citation notice,

the owner may file a notice to contest within thirty days from the deemed date of service of the citation notice.

(2) An owner may file a notice to contest on the grounds that at the time the traffic violation was committed—

- (a) the motor vehicle was stolen; or
- (b) he is no longer the owner having duly registered a change of possession of the motor vehicle in accordance with section 19(1).

(3) Notwithstanding the filing of a notice to contest under subsection (1), an owner shall be permitted to pay the fixed penalty specified in the citation notice in accordance with section 79I and the matter shall be removed from the list of hearing at the Court.

**79K.** Proceedings in respect of a traffic violation under section 66A, for which a citation notice was served, shall not be listed for trial in Court unless a notice to contest has been filed by the owner of the vehicle within thirty days from the deemed date of service of the citation notice in accordance with section 79J.

Proceedings for traffic violation under section 66A. [9 of 2017, 15 of 2020].

**79L.** Where an owner has filed a notice to contest, the Inspection Officer shall transmit to the Magistracy Registrar and Clerk of the Court in the district in which the hearing is to occur, a certified copy of—

Transmission of documents to Court. [9 of 2017, 15 of 2020].

- (a) the citation notice;
- (b) ***(Deleted by Act No. 15 of 2020);***
- (c) the photographic image or video recording of the motor vehicle captured by the red-light camera in relation to the traffic violation; and
- (d) proof of service of the citation notice.

**79M.** In proceedings for a traffic violation under this Part, a certificate on the citation notice signed by an Inspection Officer which states that—

Certificate of Inspection Officer. [9 of 2017].

- (a) he is certified by the Commissioner of Police as trained to analyse the information captured by a red-light camera;

- (b) the red-light camera used to capture the photographic image or video recording was approved by the Minister;
- (c) the photographic image or video recording captured by the red-light camera was obtained on the date and time stated therein;
- (d) the red-light camera was operating accurately at the time the photographic image or video recording was captured; and
- (e) the contents of the information shown on the photographic image or video recording are true and correct,

is *prima facie* evidence of the matters stated in the certificate.

Certificate of  
Commissioner  
of Police.  
[9 of 2017].

**79N.** In proceedings for a traffic violation under this Part, where the credential of an Inspection Officer is reasonably brought into question, the Court may authorise the submission of a certificate purporting to be signed by the Commissioner of Police that the Inspection Officer named therein is qualified to operate and analyse a red-light camera, and the certificate shall be *prima facie* evidence of the particulars specified in, and by the certificate.

Evidence of  
condition of  
red-light  
camera.  
[9 of 2017].

**79O.** In proceedings for a traffic violation under this Part, evidence of the condition of the red-light camera or the manner in which it was operated shall not be required unless evidence that it was not in proper condition or was not properly operated at the time of the traffic violation has been adduced.

No  
complainant in  
proceedings.  
[9 of 2017].

**79P.** (1) In proceedings for a traffic violation under this Part, the information that is sent to the Court under section 79L shall be sufficient evidence to call upon the person charged to answer.

(2) Notwithstanding any law to the contrary, in proceedings for a traffic violation under this Part, the Court shall not require the presence of a complainant, but this shall not debar the person in receipt of the citation notice from summoning any person in his defence.

**79Q.** Notwithstanding section 44 of the Summary Courts Act, where an owner who files a notice to contest does not appear before the Court at the date, at the time and place, or in the manner notified by the District Criminal and Traffic Court, the Magistrate shall not issue a warrant for the arrest of the owner, but may proceed *ex parte* to the hearing of the matter, and adjudicate thereon as fully and effectually as if the owner had personally appeared before the Court.

Magistrate to proceed *ex parte* where owner is absent. [9 of 2017 15 of 2020].

**79R.** (1) Where an owner does not pay the fixed penalty and does not file a notice to contest, in accordance with this Act, he shall be liable to pay, to a payee, the fixed penalty plus one-quarter of the amount of that fixed penalty.

Non-payment of fixed penalty and failure to file notice to contest. [9 of 2017].

(2) Where an owner does not pay the sum required under subsection (1) within fourteen days of the date on which it became payable, he shall be liable to pay the fixed penalty plus one-half of the amount of the fixed penalty.

(3) Where an owner fails to pay the required sums in accordance with this section, the Licensing Authority may suspend the driving permit of the owner or cease all transactions in relation to the motor vehicle which was involved in the commission of the traffic violation or with the owner of the said motor vehicle.

**79S.** Where section 79R of the Act becomes applicable, the Licensing Authority shall issue a notice, in writing, to the owner indicating that—

Notice to owner of possible sanctions. [9 of 2017].

- (a) the fixed penalty specified in the citation notice was not paid;
- (b) a notice to contest in respect of the traffic violation was not filed;
- (c) the sum stated in section 79R(a) has become due for payment;
- (d) it intends to impose the sanction specified at section 79R(3), which would be lifted upon the payment of the applicable penalty; and

(e) he has fourteen days, from the date of receipt of the notice, to show cause, in writing, why the Licensing Authority should not impose the intended sanctions.

Imposition of sanctions by Licensing Authority. [9 of 2017].

**79T.** (1) An owner may show cause, as stated in section 79S, why the Licensing Authority should not impose the sanctions specified in section 79R(3).

(2) After consideration of representations made by an owner pursuant to subsection (1), the Licensing Authority may impose any combination of sanctions specified in section 79R(3), or decline to impose any sanctions and require the owner to pay the applicable sum due under section 79R.

(3) The Licensing Authority shall inform the owner of its decision, in writing, as soon as possible.

(4) The Licensing Authority shall immediately lift any sanction imposed under this section upon the payment of the applicable sum specified in section 79R.

**PART VI**  
**FIXED PENALTY ENFORCEMENT**  
**AND ADMINISTRATION**

Definitions. [9 of 2017].

Ch. 4:20.

Ch. 15:01.

Ch. 15:02.

Eighth Schedule.

Ninth Schedule.

**80.** For the purposes of this Part—  
“Clerk” and “Court” have the meanings assigned by the Summary Courts Act;  
“constable” includes—  
(a) a police officer as defined in the Police Service Act;  
(b) a Transport Officer;  
(c) a Traffic Warden appointed under section 10A; and  
(d) an estate constable employed under the Supplemental Police Act, in a public body listed in the Eighth Schedule;  
“demerit points” means the points specified in the Fourth Column of the Ninth Schedule;

“fixed penalty” means the penalty prescribed under section 84;

“fixed penalty notice” means a notice issued under section 82 and includes a duplicate of such notice;

“notice to contest” means a notice requesting a hearing by a Court in respect of a traffic violation specified in a fixed penalty notice;

“proceedings” means proceedings before a Magistrate.

**81.** (1) Where a constable has reason to believe that a person is committing or has committed a traffic violation, the constable may issue the driver with a fixed penalty notice that offers the driver the opportunity to pay the fixed penalty within the time specified in the fixed penalty notice and discharge of any liability for the traffic violation or to file a notice to contest where the driver is desirous of contesting the fixed penalty notice issued to him.

Constable may issue fixed penalty notice. [9 of 2017 15 of 2020].

(2) Where a constable finds a vehicle on any occasion and has reason to believe that a traffic violation is being or has been committed in respect of that vehicle, the constable may affix a fixed penalty notice to any part of the vehicle where the fixed penalty notice may be easily seen and for the purposes of this Part, the affixed fixed penalty notice shall be deemed to have been served upon the person liable for the traffic violation.

(3) Notwithstanding any law to the contrary, the owner of a vehicle on which a fixed penalty notice was affixed under subsection (2) shall be presumed to be the person liable for the traffic violation and shall be required to either pay the fixed penalty within the time specified in the fixed penalty notice or to file a notice to contest where the owner is desirous of contesting the fixed penalty notice affixed.

(4) A fixed penalty notice affixed to a vehicle under subsection (2) shall not be removed or interfered with except by, or under the authority of the driver of the vehicle or the person liable for the traffic violation.

(5) A person who contravenes subsection (4) commits an offence and is liable on summary conviction to a fine of three thousand dollars.

(6) Where a fixed penalty notice has been issued or affixed under this section, the police officer in charge of the police station for the district in which the fixed penalty notice was issued shall send a duplicate of the fixed penalty notice to the Licensing Authority within one day from the date of issue or affixing of the fixed penalty notice.

Contents of  
fixed penalty  
notice.  
[9 of 2017  
15 of 2020].

**82.** (1) A fixed penalty notice issued or affixed under section 81, shall bear the signature of the constable and shall specify—

- (a) the date, time and place that the fixed penalty notice was issued or affixed;
- (b) the section of the written law creating the traffic violation and such particulars of the traffic violation as are required for proceedings under this Act or the Summary Courts Act;
- (c) the time within which the fixed penalty may be paid in accordance with section 83(1);
- (d) the amount of the fixed penalty;
- (e) the payee to whom the fixed penalty may be paid;
- (f) the applicable number of demerit points for the traffic violation as specified in the Fourth Column of the Ninth Schedule; and
- (g) that the person may contest the fixed penalty notice by filing a notice to contest in accordance with section 85.
- (h) ***(Deleted by Act No. 15 of 2020).***

(2) A notice under this Part shall be in the form approved by the Licensing Authority and published in the *Gazette*.

Payment of  
fixed penalty.  
[9 of 2017].

**83.** (1) Where a fixed penalty notice has been issued or affixed under section 81, the driver or owner of the vehicle, as the case may be, shall, unless he files a notice to contest, pay the fixed penalty within thirty days from the date that the fixed penalty notice was issued or affixed, or such longer period as the Minister may by Order prescribe.

(2) Subject to section 88K, where a fixed penalty is paid in accordance with a fixed penalty notice, a person shall not be liable to any sanction for the traffic violation in respect of which the fixed penalty notice was issued or affixed.

(3) Payment of a fixed penalty under subsection (1) shall be—

- (a) accompanied by the fixed penalty notice issued under section 81; and
- (b) paid to a payee as prescribed by the Minister under section 88D.

**84.** The fixed penalty for a traffic violation shall be the amount specified in the Third Column of the Ninth Schedule. Amount of fixed penalty. [9 of 2017].

**84A.** Where a traffic violation has been committed by a child, in addition to the payment of a fixed penalty or the allocation of demerit points against the child's driving permit record, he may be referred to a child traffic counselling programme by the Licensing Authority. Referral to a child traffic counselling programme. [20 of 2020].

**84B.** (1) A child who is referred to a child traffic counselling programme under this Act, shall attend the programme. Attendance at a child traffic counselling programme. [20 of 2020].

(2) Where a child fails to comply with subsection (1), the Licensing Authority shall allocate demerit points against the child's driving permit record in accordance with the Ninth Schedule.

**85.** (1) Where a person is desirous of contesting a fixed penalty notice, he shall file a notice to contest with the Court within fifteen days from the date that the fixed penalty notice was issued or affixed. Notice to contest to be filed. [9 of 2017, 15 of 2020].

(2) Notwithstanding subsection (1), a person may at any time within the period specified in the fixed penalty notice for the payment of the fixed penalty pay the fixed penalty in accordance with section 83 and the matter shall be removed from the list of hearing at the Court.

Transmission of documents to Court. [9 of 2017 15 of 2020].

**86.** Where a notice to contest has been filed, the constable shall immediately transmit to the Magistracy Registrar and Clerk of the Court, a copy of the fixed penalty notice.

Listing of proceedings in respect of fixed penalty notice. [9 of 2017 15 of 2020].

**87.** Proceedings in respect of a traffic violation for which a fixed penalty notice was issued or affixed shall not be listed for trial in Court unless a notice to contest has been filed in accordance with section 85 within fifteen days from the date that the fixed penalty was issued or affixed.

Temporary suspension of permit pending determination of charge. [9 of 2017].

**87A.** (1) Where any person is charged with manslaughter or offence committed by use of a motor vehicle as a weapon or with contravening the provisions of section 70 or section 71, it shall be lawful for the Licensing Authority to order the suspension of the driving permit of the person so charged pending the determination of the charge.

(2) Any such permit so suspended under subsection (1) shall be surrendered to the Clerk of the Court before which the person so charged is to appear.

(3) Where the Court makes an Order for suspension of a person's driving permit this Order shall be reviewed on every occasion that the matter is listed.

Appearance of parties in proceedings where notice to contest was filed. [9 of 2017 15 of 2020].

**88.** (1) Where a notice to contest is filed within the period specified in the fixed penalty notice, the constable who issued or affixed the fixed penalty notice shall be notified and shall be required to attend Court on the date, at the time and place and in the manner specified by the Court.

(2) Notwithstanding section 44 of the Summary Courts Act, where a person files a notice to contest and does not appear before the Court on the date, at the time and place or in the manner specified in the fixed penalty notice, the Magistrate shall not issue a warrant for the arrest of the person but may proceed *ex parte* to hear the matter and adjudicate thereon as fully and effectually as if the person had personally appeared before the Court.

**88A.** (1) Where a fixed penalty notice was issued or affixed and the driver or owner, as the case may be, does not pay the fixed penalty and does not file a notice to contest, in accordance with this Act—

Non-payment of fixed penalty and failure to file notice to contest. [9 of 2017].

- (a) he shall be liable to pay to a payee, the fixed penalty plus one-quarter of the amount of that fixed penalty; and
- (b) the applicable number of demerit points for the traffic violation shall be recorded against his driving permit record.

(2) Where the driver or owner, as the case may be, does not pay the sum required under subsection (1) within fourteen days of the date on which it became payable, he shall be liable to pay the fixed penalty plus one-half of the amount of the fixed penalty.

(3) Where the driver or owner, as the case may be, fails to pay the required sums in accordance with this section, the Licensing Authority may suspend the driving permit of the driver or owner, as the case may be, or cease all transactions in relation to the motor vehicle which was involved in the commission of the traffic violation or with the driver or owner of the said motor vehicle, as the case may be.

**88B.** (1) Where section 88A of the Act becomes applicable, the Licensing Authority shall issue a notice, in writing, to the driver or owner, as the case may be, indicating that—

Notice to driver or owner of possible sanctions. [9 of 2017].

- (a) the fixed penalty specified in the fixed penalty notice was not paid;
- (b) a notice to contest in respect of the traffic violation was not filed;
- (c) the applicable number of demerit points for the traffic violation, as specified in the Fourth Column of the Ninth Schedule was recorded against his driving permit;
- (d) the sum stated in section 88A(1)(a) has become due for payment;

- (e) it intends to impose the sanctions specified at section 88A(3), which would be lifted upon the payment of the applicable penalty; and
- (f) he has fourteen days, from the date of receipt of the notice, to show cause, in writing, why the Licensing Authority should not impose the intended sanctions.

Imposition of sanctions by Licensing Authority. [9 of 2017].

**88C.** (1) A driver or owner, as the case may be, may show cause, as stated in section 88B, why the Licensing Authority should not impose the sanctions specified in section 88A(3).

(2) After consideration of representations made by the driver or owner, as the case may be, pursuant to subsection (1), the Licensing Authority may impose any combination of sanctions specified in section 88A(3), or decline to impose any sanctions and require the driver to pay the applicable sum due under section 88A.

(3) The Licensing Authority shall inform the driver or owner, as the case may be, of its decision, in writing, as soon as possible.

(4) The Licensing Authority shall immediately lift any sanction imposed under this section upon the payment of the applicable sum specified in section 88A.

Minister may by Order prescribe fixed penalty traffic violations. [9 of 2017, 20 of 2020].

**88D.** (1) The Minister may from time to time by Order—

- (a) add any traffic violation to the Ninth Schedule and prescribe in respect of that traffic violation a fixed penalty not exceeding seventy-five per cent of the fine prescribed for the traffic violation;
- (b) remove any traffic violation from the Ninth Schedule;
- (c) alter the fixed penalty for any traffic violation listed in the Ninth Schedule to an extent that the fixed penalty as altered does not exceed seventy-five per cent of the fine prescribed for the traffic violation;

- (ca) add to, or remove any penalty from the Fifth Column of the Ninth Schedule;
- (d) add, alter or remove the number of demerit points in respect of any traffic violation;
- (e) prescribe the methods and payees for payment of a fixed penalty; and
- (f) add to, or remove from the Eighth Schedule the name of any Corporation or public body.

(2) An Order made under subsection (1) shall be subject to negative resolution of Parliament.

PART VIA

**LEGAL PROCEEDINGS, DEMERIT POINTS,  
SUSPENSION AND CANCELLATION OF  
DRIVING PERMITS**

**88E.** Upon the trial of a person who is indicted for manslaughter in connection with the driving of a motor vehicle by him, it shall be lawful for the jury, if they are satisfied that he is guilty of an offence under section 71, to find him guilty of that offence, whether or not the requirements of section 73 have been satisfied as respects that offence.

Power to convict for reckless or dangerous driving on trial for manslaughter. [9 of 2017].

**88F.** (1) Where a person is charged with an offence under section 70 or section 71A and the Court determines that the offence is not proved, then, at any time during the hearing or immediately thereafter, the Court may, without prejudice to any other direction or order that may be made, direct or allow a charge for an offence under section 72 to be preferred against the defendant and may thereupon proceed with that charge.

Power to proceed on charge for careless driving on hearing of charge under section 70 or 71A. [9 of 2017].

(2) A defendant under subsection (1) or his Attorney-at-law shall be informed of the new charge and be given an opportunity, whether by way of cross-examining any witness whose evidence has already been given against the defendant or otherwise, of answering the new charge, and the Court shall, if it considers that the defendant is prejudiced in his defence by reason of the new charge being preferred, adjourn the hearing.

Power of Court  
to require a  
suspended  
permit be  
produced.  
[9 of 2017].

**88G.** (1) Where a person is convicted of an offence under section 70, 70A, 71, or 71A and an order has been imposed for the disqualification of the person from holding or obtaining a driving permit for a stated period or permanently and where the person holds a driving permit, the Court before which the person is convicted shall require him to produce the permit and upon the making of an order of disqualification, shall forfeit the permit and return it to the Licensing Authority.

(2) A person who is disqualified from holding or obtaining a driving permit under subsection (1) may, after the expiration of six months from the date of the disqualification, apply to the Court by which he was disqualified to remove the disqualification.

(3) Where an application for removal of the disqualification from holding or obtaining a driving permit is made under subsection (2) the Court may, as it thinks proper, having regard to the character of the person disqualified and his conduct subsequent to the disqualification, the nature of the offence and any other circumstances of the case, either by order, remove the disqualification as from the date specified in the order or refuse the application.

(4) Where an application is refused under this section a further application shall not be made within six months from the date of the refusal.

(5) Particulars of a conviction or disqualification or of the removal of a disqualification under this Act shall be furnished to the Transport Commissioner.

(6) The costs of any application referred to in this section may be borne in whole or in part by the applicant, as the Court may order.

(7) In this section, “driving permit” includes a provisional permit.

Right of  
appeal.  
[9 of 2017].

**88H.** A person who, by virtue of an order of a Court under section 88F is disqualified from holding or obtaining a driving permit may appeal against the order in the same manner as

against a conviction, and the Court may, if it thinks fit, pending the appeal, suspend the operation of the order.

**88I.** Where a person who holds a driving permit is convicted of an offence under section 70, 70A, 71, or 71A, the Court may in order to impose an appropriate penalty, require the Transport Commissioner to produce for its inspection the offender's Record of Conviction.

Production of  
offender's  
Record of  
Conviction.  
[9 of 2017].

**88J.** (1) The Licensing Authority shall, for the purpose of administering demerit points, establish and maintain a register to be known as "the Demerit Points Register".

Establishment  
of Demerit  
Points Register.  
[9 of 2017].

(2) All demerit points recorded against the driving permit record of a person for an offence or a traffic violation shall be duly recorded by the Licensing Authority in the Demerit Points Register.

(3) The contents of the Demerit Points Register shall, for the purposes of all proceedings in a Court, be *prima facie* evidence of all information contained therein and extracts of the Demerit Points Register purporting to be certified as such by the Transport Commissioner, shall be admissible in evidence in Court.

**88K.** (1) Subject to subsection (2), where a person is convicted for an offence or a traffic violation listed in the First Column of the Ninth Schedule that carries demerit points, the demerit points as prescribed in the Fourth Column in the Ninth Schedule for that offence or traffic violation shall be recorded against the driving permit record of the person so convicted.

Demerit points.  
[9 of 2017].

(2) Where a person appeals against conviction under subsection (1), no demerit points shall be recorded against the driving permit record of the person unless the conviction is confirmed on appeal.

(3) Where a fixed penalty notice is issued under section 81 for a traffic violation that carries demerit points—

- (a) the fixed penalty for the traffic violation is paid in accordance with the requirements of the fixed penalty notice; or

- (b) the time specified for the payment of the fixed penalty has expired and a notice to contest was not filed by the driver or owner within the specified time,

the number of demerit points as prescribed in the Fourth Column of the Ninth Schedule for the traffic violation shall be recorded against the driving permit record of the person.

Simultaneous traffic violations. [9 of 2017].

**88L.** (1) Subject to subsection (2), where a person is charged with more than one traffic violation or served with more than one fixed penalty notice for traffic violations that carry demerit points and those traffic violations arise out of one incident and that person—

- (a) is convicted of two or more of the traffic violations for which he was charged; or  
(b) has made payment in respect of two or more of the traffic violations for which he was issued a fixed penalty notice,

he shall be liable to have recorded against his driving permit record, demerit points for the traffic violation that carries the highest number of demerit points and where the traffic violations carry an equal number of demerit points, the person shall be liable to have recorded against his driving permit record, demerit points for only one traffic violation.

(2) Where a person is charged for a traffic violation under this Act that involves—

- (a) a failure to comply with the indication given by a traffic light signal under section 66A; or  
(b) exceeding the specified speed limit,

that person shall be liable to have recorded against his driving permit record the demerit points prescribed for both traffic violations in addition to the highest number of demerit points for any other traffic violation arising out of the same incident.

Accumulation of demerit points and disqualification. [9 of 2017].

**88M.** (1) Where a newly licensed driver or the holder of a provisional permit accumulates seven or more demerit points within a period of twelve months from the date of issue of the

driving permit or the provisional permit, the Licensing Authority shall disqualify that person from holding or obtaining a driving permit for a period of one year.

(2) Where a person who holds a driving permit for more than twelve months, accumulates within a period of three years—

- (a) ten or more but less than fourteen demerit points, the Licensing Authority shall disqualify that person from holding or obtaining a driving permit for a period of six months;
- (b) fourteen or more but less than twenty demerit points, the Licensing Authority shall disqualify that person from holding or obtaining a driving permit for a period of one year; or
- (c) twenty or more demerit points, the Licensing Authority shall disqualify that person from holding or obtaining a driving permit for a period of two years.

(3) The Licensing Authority shall, before disqualifying a person under subsection (2), give that person notice in writing of its intention to do so, and shall specify a date not less than fourteen days after the date of the notice, upon which the suspension shall be made and call upon the person to show cause why he should not be disqualified.

(4) Where a person fails to show cause under subsection (3) and the Licensing Authority after taking into consideration any facts in mitigation, decides to disqualify that person from holding or obtaining a driving permit, the Authority shall forthwith, in writing, notify that person of the disqualification.

(5) A disqualification imposed under this section shall not take effect until the expiration of fourteen days after the Licensing Authority has informed the person of the disqualification.

(6) Where a person has been disqualified from holding or obtaining a driving permit under this section, that person shall, within fourteen days of being informed of the disqualification, surrender his driving permit to the Licensing Authority.

(7) A person who fails to surrender his driving permit to the Licensing Authority as required under subsection (6), commits an offence and is liable to a fine of five thousand dollars and further disqualification for an additional period of one year.

(8) Where the disqualification period under this section expires, all demerit points recorded against the driving permit record of the person shall be expunged.

(9) A person who is disqualified from holding or obtaining a driving permit under this section may, within fourteen days of the receipt of the notice under subsection (4), appeal to a Court of competent jurisdiction against that decision and the decision of that Court shall be final.

(10) For the purposes of subsection (1), “newly licensed driver” means a person who is the holder of a driving permit for a period of twelve months or less from the date of issue.

Reissue of  
driving permit  
after  
disqualification.  
[9 of 2017].

**88N.** (1) A driving permit suspended by a Court or by the Licensing Authority shall, during the period of suspension, be of no effect.

(2) A person whose driving permit is suspended, or who is declared by a Court or by the Licensing Authority to be disqualified from holding or obtaining a driving permit, shall, during the period of suspension or disqualification, not apply to the Licensing Authority to have his permit reissued unless the period of disqualification has expired or is removed under section 88M(8).

(3) A person who is disqualified from holding or obtaining a driving permit may be reissued with a driving permit by the Licensing Authority where he—

- (a) participates in a driver’s rehabilitation programme approved by the Licensing Authority;
- (b) passes a driving test; and
- (c) pays the prescribed fee for the reissue of the driving permit.

(4) A person who contravenes subsection (2) commits an offence and is liable to a penalty of ten thousand dollars.

**88O.** (1) Subject to subsection (2), where demerit points have been recorded against the driving permit record of a person and two continuous years have elapsed without additional demerit points being recorded, the demerit points recorded against that person's driving permit record shall be expunged.

Demerit points to be expunged after two years. [9 of 2017].

(2) Where a person is disqualified by an order of a Court from holding or obtaining a driving permit, any demerit points recorded against the driving permit record of that person shall be expunged.

(3) The Licensing Authority shall have responsibility for calculating the two-year period prescribed under subsection (1) and in calculating the period, shall not take into account any period of suspension or disqualification by virtue of an order of the Court or any written law.

**88P.** (1) The Minister may from time to time by Order, prescribe the traffic violations specified in the First Column of the Ninth Schedule that will carry double demerit points and the period during which the imposition of the double demerit points shall apply.

Double demerit points. [9 of 2017].

(2) An Order made under subsection (1) shall be published at least five days prior to the commencement of a prescribed period in the *Gazette* and in at least one daily newspapers circulating in Trinidad and Tobago.

(3) For the purposes of this section, "prescribed period" means any period not exceeding ten consecutive days.

**88Q.** Where a person who, under this Part, is disqualified from holding or obtaining or has been refused from obtaining a driving permit, with intent to deceive—

Fraudulent application for driving permit. [9 of 2017].

(a) applies for a permit; or

(b) obtains a permit,

while so disqualified, he is liable to a fine of two thousand dollars and imprisonment for six months.

PART VII  
GENERAL

Fees and duties.  
First Schedule.  
[1 of 2016].

**89.** (1) The fees and duties specified in the First Schedule shall be payable to the Licensing Authority in respect of the several matters to which they are applicable.

First Schedule.

(1A) Notwithstanding subsection (1), a citizen of Trinidad and Tobago who is sixty years of age or over is exempt from the payment of the fees in respect of a driving permit in the First Schedule.

(2) All fees and duties received by the Licensing Authority shall be paid to the Comptroller of Accounts on account of the general revenue of Trinidad and Tobago.

(3) Such percentage or proportion of the annual licence duties in respect of motor vehicles collected under this Act by the Licensing Authority which are paid by the owners of motor vehicles who are resident within any City or Municipality shall be paid to the Council of such City or Municipality by the Comptroller of Accounts as may be directed by the President.

(4) Subject to affirmative resolution of Parliament, the President may by Regulations amend, vary, suspend or revoke the provisions of the First Schedule.

**89A. (Repealed by Act No. 9 of 1997).**

Fraudulent  
imitation, etc.,  
of documents.  
[2 of 2015].

**90.** Any person who fraudulently imitates, alters, mutilates, destroys or uses, or fraudulently lends or allows to be used by any other person any identification mark, motor vehicle licence, certificate of registration or driving permit issued or deemed to have been issued under this Act is liable to a fine of three thousand dollars and to imprisonment for six months.

Offences and  
general penalty.  
[30 of 1952  
\*8 of 1978  
14 of 1979  
5 of 2010  
9 of 2017].

**91.** (1) Any person who contravenes this Act is, unless otherwise specifically provided, liable to a fine of three thousand dollars.

\*Came into operation on 10th April 1978—GN 54/1978.

(2) Any person who contravenes the provisions of any Regulations made under this Act is, unless otherwise specifically provided, liable to a fine of three thousand dollars.

(3) The driver of a motor vehicle who stands for hire at any road or place not appointed under this Act for the purpose, or who contravenes any Order made under this Act, is liable to a fine of three thousand dollars.

(4) Unless otherwise expressly provided, all offences under this Act may be prosecuted, and all penalties incurred may be imposed or recovered, in the manner provided by the Summary Courts Act.

Ch. 4:20.

**92.** Nothing in this Act shall affect any liability of the driver or owner of a motor vehicle by virtue of any Act or at Common Law.

Liability at  
Common Law.

**93.** (1) Any driver or conductor of a motor vehicle who commits a traffic violation or an offence under this Act or any Regulations made thereunder and refuses to give his name and address or gives a false name or address is guilty of an offence; and it shall be the duty of the owner of the motor vehicle if required to give any information which it is within his power to give and which may lead to the identification and apprehension of the driver or conductor, and any owner who fails to do so within four days of his being notified of such request is guilty of an offence.

Refusing to  
give name or  
address or  
giving false  
name or  
address.  
[9 of 2017].

(2) Any constable may arrest without a warrant the driver or conductor of any motor vehicle who within view commits any offence under this Act or under the Regulations unless the driver or conductor either gives his name and address or produces his permit for examination.

**94.** If any person in or in connection with an application for a motor vehicle licence or the registration of a motor vehicle, or a driving permit or the endorsement of such a permit, or any change or correction in a motor vehicle licence or the registration of a motor vehicle or in giving any information lawfully demanded or required under this Act or any Regulations made thereunder makes any statement which to his knowledge is false, or in any material respect misleading, he is liable to a fine of two thousand dollars.

Giving false  
information.  
[9 of 2017].

Duplicate licences, permits and certificates.

**95.** Any authority or person having power to issue any certificate or licence under this Act shall, on proof to his satisfaction that such certificate or licence has been lost or destroyed, and on payment of the prescribed fee, issue a duplicate of the certificate or licence to the person entitled thereto.

Liability of driver and person in charge of vehicle for offences. [9 of 2017].

**96.** (1) If—

- (a) any motor vehicle is used which contravenes any provision of this Act or of any Regulation, or of any Order lawfully made under this Act or any Regulation; or
- (b) any motor vehicle is used in such a state or condition or in such a manner as to contravene any such provision; or
- (c) anything is done or omitted in connection with a motor vehicle in contravention of any such provision,

then, unless otherwise expressly provided by this Act, the driver or person in charge of the motor vehicle at the time of the offence or traffic violation is liable unless the offence or traffic violation was not due to any act, omission, neglect or default on his part.

(2) Any person authorised in writing by the Licensing Authority may, at all reasonable times, enter any premises for the purpose of ascertaining whether any vehicle is kept on such premises contrary to this Act, and for the purpose of inspecting any vehicle on such premises.

Power to require motor vehicles licensed according to M.G.W. to be weighed. [25 of 1997 9 of 2017].

**97.** (1) The driver or other person in charge of a motor vehicle or trailer registered according to its maximum gross weight may, on demand by any person authorised in writing by the Licensing Authority or by a constable, be required to satisfy such person or constable that the load which is being carried on such motor vehicle or trailer does not contravene the provisions of the registration or this Act or any Regulations made thereunder, and may be required by such person or constable to drive him with such vehicle or trailer to the nearest weighbridge for the purpose of weighing such load.

(2) Any person who fails to comply with a request to proceed to the nearest weighbridge as aforesaid may be arrested forthwith without a warrant and he is liable to a fine of four hundred dollars. The vehicle or trailer may be detained at the expense and risk of the owner and taken to a place for safe keeping until such request is complied with, and any excess load found on weighing shall first be removed before the vehicle or trailer is permitted to proceed on its journey.

(3) The Licensing Authority or any person authorised by the Licensing Authority may, before registration (including a renewal) in respect of a motor vehicle or trailer, require such motor vehicle or trailer to be weighed by and at the expense of the owner in the presence of a person authorised by the Licensing Authority.

**98.** (1) If by reason of an offence or traffic violation against this Act any injury is caused to any road or bridge, the authority responsible for the repair of the road or bridge may cause such injury to be made good, and may, either before or after the injury is made good, recover the estimated or actual cost thereof from the owner of the motor vehicle by the use of which the offence or traffic violation was committed.

Recovery of damage to road or bridge. [9 of 2017].

(2) A certificate under the hand of the Chief Technical Officer (Works), or any person authorised by him in that behalf, of the amount of the cost of making good such injury shall, without proof of signature, be *prima facie* evidence of the amount payable by the owner of the vehicle.

**99.** If in any proceedings under this Act any question arises whether a motor vehicle does or does not comply with any provision of this Act or any Regulations made thereunder the certificate of any person appointed by the Public Service Commission, in the exercise of its power under the Constitution, as a Transport Officer that he has examined the vehicle and as to the result of his examination shall be admissible in evidence and shall be sufficient *prima facie* evidence of any fact or opinion stated therein relating to the matter in question, and the Court shall

Certificate as to damage to be admissible in evidence. [25 of 1997].

not permit the officer to be called for cross-examination on the certificate unless contrary evidence is given which appears to the Court to be credible, or unless for any reason the Court considers cross-examination to be necessary in the interests of justice.

Regulations.  
[\*47 of 1956  
12 of 1961  
†32 of 1964  
11 of 1965  
25 of 1997  
5 of 2010  
15 of 2020].

**100.** Subject to negative resolution of Parliament, the Minister may make Regulations in respect of all or any of the following matters:

- (a) anything which by this Act may or is to be prescribed;
- (b) the forms to be used under this Act;
- (c) the construction, fittings, dimensions and design of any motor vehicle;
- (d) the character and nature of horns or other instruments capable of giving audible and sufficient warning of motor and other vehicles and regulating their use;
- (e) the number, position and kind of lights and reflectors to be carried on motor and other vehicles and the times during which they are to be exhibited;
- (ea) the restrictions on the degree or shade of tint on the windows or windscreen of a vehicle or trailer;
- (f) the duties and powers of Motor Vehicles Inspectors with regard to the inspection of motor and other vehicles;
- (fa) parking for persons with a disability or other persons in special circumstances;
- (g) the inspection of motor and other vehicles and the times, places and manner of such inspection;
- (h) the form of identification marks to be fixed on motor vehicles and trailers in respect of

\*Act No. 47 of 1956 deleted the former paragraphs (k) and (l) of this section but provided for any Regulations made under them to continue in force.

†Section 10 of Act No. 32 of 1964 provides that nothing in this section or in any Regulations made under this Act (the Motor Vehicles and Road Traffic Act) relating to the granting or operation of concessions shall apply to motor omnibuses operated by Government under that Act.

registration and licensing and the sizes and colour of the letters of and the manner of displaying such marks;

- (i) the classification of roads and the prohibition or restriction of the use of any classified roads by vehicles of any specified class or description;
- (j) the precedence of vehicles and pedestrians respectively at and in the vicinity of crossings;
- (k) the issue of licences to drivers of taxis by the Licensing Authority and the conditions to be observed by the holders of such licences;
- (l) the badges and uniforms to be worn by drivers and conductors of public service vehicles and the conduct of drivers, conductors and passengers;
- (m) the prevention of indecent or immoral behaviour in taxis;
- (n) passenger fares and tolls in respect of public service vehicles;
- (o) the maximum hours of employment of persons as drivers of goods vehicles;
- (p) generally, for the better carrying out of the provisions of this Act and in particular for the safety, control and regulation of traffic and the use of vehicles or any class of vehicles on any road and the conditions under which they may be used;
- (q) health, safety or environmental matters with respect to the registration of motor vehicles or trailers including the prescribed vehicle emissions, use of unleaded fuels, and vehicle specifications for motor vehicles or classes of motor vehicles for the purpose of registration;
- (r) passenger transport.

**101. (Repealed by Act No. 25 of 1997).**

**102. (1)** Regulations under section 100 may make provision as to the conduct of persons licensed to act as drivers or conductors of public service vehicles when acting as such.

Regulation of  
conduct of  
drivers and  
conductors.  
[11 of 1965  
47 of 1980  
25 of 1997].

(2) Any person to whom Regulations having effect by virtue of this section apply, who contravenes any of the Regulations, is liable to a fine of one hundred and fifty dollars.

Regulation of  
conduct of  
passengers.  
[11 of 1965  
25 of 1997].

**103.** (1) Regulations under section 100 may make provision generally as to the conduct of passengers in public service vehicles and in particular for—

- (a) authorising the removal from a public service vehicle of a person infringing the Regulations by the driver or conductor of the vehicle or on the request of the driver or conductor by a police constable;
- (b) requiring a passenger in a public service vehicle who is reasonably suspected by the driver or conductor thereof of contravening the Regulations to give his name and address to a police constable or to the driver or conductor on demand;
- (c) requiring a passenger to declare, if so requested by the driver or conductor, the journey he intends to take or has taken in the vehicle, and to pay the fare for the whole of that journey and to accept any ticket provided therefor;
- (d) requiring on demand being made for the purpose by the driver or conductor or other person authorised by the Corporation established under the Public Transport Service Act production during the journey and surrender at the end of the journey by the holder thereof of any ticket issued to him;
- (e) requiring a passenger, if so requested by the driver or conductor, to leave the vehicle on the completion of the journey the fare for which he has paid;
- (f) requiring the surrender by the holder thereof on the expiry of the period for which it is issued of a ticket issued to him.

Ch. 48:02.

(2) Any person who contravenes, a provision of Regulations having effect by virtue of this section is liable to a fine of seventy-five dollars.

**104.** (1) Regulations under section 100 may make provision with respect to public service vehicles providing for—

- (a) the determination by or under the Regulations of the number of the seated passengers and standing passengers respectively whom a vehicle is constructed or adapted and fit to carry;
- (b) the determination by or under the Regulations of the number of such passengers respectively who may be carried in a vehicle;
- (c) the marks to be carried on a vehicle showing the number aforesaid and the manner in which those marks are to be carried.

Control of number of passengers. [11 of 1965 25 of 1997].

(2) Any person who contravenes a provision of Regulations having effect by virtue of this section is liable to a fine of seven hundred and fifty dollars.

**105.** (1) The Minister may make Regulations generally as to the conduct of persons using a station and in particular—

- (a) for appointing any place, being the property of the Corporation or being part of a road, a station for public service vehicles;
- (b) in the case of a road, for authorising the Corporation to do all things as are necessary to adapt the station for use as such, and in particular to provide and maintain waiting rooms, ticket offices, refreshment places and lavatories and other similar accommodation in connection therewith;
- (c) for authorising the Corporation to make reasonable charges for the use of, or to let on hire to any person, any accommodation so provided; and
- (d) for the use of any such accommodation.

Control of bus terminals and coach stations. [11 of 1965 25 of 1997].

Ch. 48:02. (2) In this section “Corporation” means the Corporation established under the Public Transport Service Act, and “station” includes bus stops and coach stations and terminals that may be used by public service vehicles belonging to the Corporation as parking places.

Offences in connection with Regulations. [11 of 1965, 25 of 1997, 9 of 2017].

**106.** Regulations under sections 100, 102, 103 and 104 may contain provisions for imposing on any person contravening the Regulations a fine of fifteen hundred dollars for each traffic violation and a fine recoverable on summary conviction of fifteen hundred dollars or imprisonment for three months for each offence.

Rules and Practice Direction for traffic matters. Ch. 4:01. [15 of 2020].

**106A.** (1) Notwithstanding section 9 of the Summary Courts Act, the Rules Committee established under section 77 of the Supreme Court of Judicature Act may make Rules with respect to—

- (a) the location for the hearing of traffic matters;
- (b) the manner in which cases will be listed for hearing and parties will be notified; and
- (c) all other matters necessary to give effect to this Act.

(2) Rules made under subsection (1) shall be subject to negative resolution of Parliament.

(3) The Chief Justice may by Practice Direction, determine the Court locations at which traffic matters will be heard.

Parking in grounds, etc., of public officers restricted. [11 of 1963, 5 of 2010, 9 of 2017].

**107.** (1) Notwithstanding any other provision of this Act, no person shall park or cause any motor vehicle to be or to remain parked in or on any grounds or other open space adjoining or attached to any public building unless he has been granted permission by a person authorised in that behalf under subsection (2).

(2) The President may by Order authorise a public officer specified in the Order to grant permission to any person to park a vehicle in or on any grounds or open space adjoining or attached to a public building expressed in the Order to be under the control of that public officer.

(3) A public officer referred to in subsection (2) shall issue to every person to whom he grants permission to park in

or on any such grounds or open space a distinguishing mark or symbol which such person shall affix to the lower left front windshield of the vehicle.

(4) Any person who contravenes subsection (1) is liable to a fine of one thousand, five hundred dollars.

(5) In this section, “public buildings” means any building occupied for use as offices by any Government Ministry or Department and includes a building used as a Court of law; “grounds” includes forecourt, courtyard, footpath, driveway and alleyway.

**108.** (1) Where a vehicle is parked in contravention of any provisions of this Act or of any Regulations or Orders made thereunder, or is left on any road in such a manner that it is likely to cause any obstruction to persons lawfully using any such road, any member of the Police Service may —

Powers of police where vehicles parked in contravention of Act or left on road. [11 of 1963 9 of 2017].

- (a) require the driver or other person in control or in charge thereof to remove it or cause it to be removed, and any person who fails to comply with any such requirement is liable to a fine of three hundred dollars;
- (b) if the driver or other person in control or in charge of such vehicle cannot be found or refuses to remove it when required to do so, remove such vehicle or arrange for it to be removed from the place in which it is parked to a place of safe custody either by towing or driving the vehicle or in such other manner as he may think necessary.

(2) When any member of the Police Service removes or provides for the safe custody of any motor vehicle or arranges for any person to remove it or provide for its removal under subsection (1) then, except upon proof of failure to exercise reasonable care, neither such member of the Police Service nor any such other person shall be liable in any action or demand for any damages arising from the loss or damage to such vehicle in the course of its removal or otherwise.

Charges payable before delivery of vehicle; and sale of vehicles in custody. [11 of 1963 20 of 1983 6 of 1993 5 of 2010].

**109.** (1) Where a motor vehicle is removed to a place of safe custody under section 108, the vehicle shall not be released to the owner unless there is paid to the Commissioner of Police a sum for—

- (a) the removal of the vehicle; and
- (b) each day or part thereof during which the vehicle is kept in custody,

Sixth Schedule. as specified in the Sixth Schedule.

(1A) The Minister may, by Order subject to negative resolution of Parliament, vary from time to time the sums specified in the Sixth Schedule.

(2) Notwithstanding the provisions of subsection (1), where any vehicle is left in custody for any period exceeding thirty days any police officer not below the rank of superintendent may direct that such vehicle be sold by public auction and any moneys arising from the sale shall be applied in the following order:

- (a) in defraying the expenses of sale, if any;
- (b) in settlement of any sum payable by the owner under subsection (1); and
- (c) to the credit of the registered owner of the vehicle.

(3) At least fourteen days' notice shall be given in a daily newspaper of any sale by public auction of a motor vehicle under this section.

(4) Where a vehicle is sold under this section, the police officer who authorised the sale shall issue to the purchaser a certificate to that effect and such certificate shall be sufficient authority to the Licensing Authority to register the vehicle in the name of the purchaser; and any right, title or interest of the former registered owner in the vehicle shall be extinguished on the issue of such certificate.

(5) Any moneys received by the Commissioner of Police under subsection (1) shall be used in defraying any expenses incident on the removal or custody of the vehicle and the balance, if any, shall be paid to the Comptroller of Accounts.

**110.** (1) Whenever the provisions of this Act or of any Regulations made hereunder are in conflict with the provisions of any other law relating to the control of vehicles and road traffic the provisions of this Act and the Regulations made hereunder shall prevail.

In the event of a conflict of laws, the provisions of this Act to prevail.

(2) Whenever any powers conferred on the Licensing Authority or the Commissioner of Police under this Act are similar to powers conferred on a Municipal or Road Authority under any other law and there shall arise any conflict or dispute as to the exercise of such powers, the matter at issue shall be referred to the Trinidad Transport Board who shall decide which authority shall exercise such powers and the manner in which such powers shall be exercised. The decision of the Board shall be final and conclusive.

Where similar powers are granted under this and any other law the Board shall decide as to the exercise of those powers.

**111.** (1) The Licensing Authority shall, as soon as may be after the 13th March 1948, prepare a Code (hereinafter referred to as the Highway Code) comprising such directions as appear to him to be proper for the guidance of persons using roads and may from time to time revise the Code by revoking, varying, amending or adding to the provisions thereof in such manner as he thinks fit.

Highway Code. [9 of 2017].

(2) The Highway Code and any alterations proposed to be made in the provisions of the Code on any revision thereof shall, as soon as prepared by the Licensing Authority, be laid before Parliament and the Code or revised Code, as the case may be, shall not be issued until the Code or the proposed alterations have been approved by Parliament.

(3) Subject to the foregoing provisions of this section, the Licensing Authority shall cause the Code and every revised edition of the Code to be printed and issued to the public at a price to be fixed by the President.

(4) A failure on the part of any person to observe any provision of the Highway Code shall not of itself render that person liable to proceedings of any kind, but any such failure may in any proceedings (whether civil or criminal, and including proceedings for an offence under this Act) be relied upon by any party to the proceedings as tending to establish or to negative any liability which is in question in those proceedings.

Section 89.  
[5 of 2010  
2 of 2013  
1 of 2016].

**\*FIRST SCHEDULE**

**FEES AND DUTIES**

(1)	}		
	to	(Deleted by Act No. 9 of 1997).	
(6)	}		
(7)		Driving Permits—	\$
		(a) five-year permit ... ..	500.00
		(aa) ten-year permit ... ..	1,000.00
		(b) four-year permit ... ..	80.00
		(c) three-year permit ... ..	60.00
		(d) two-year permit ... ..	40.00
		(e) one-year permit ... ..	20.00
		(f) persons who have attained the age of sixty years may renew their driving permits without charge	
(8)		Maxi-taxi conductor's licence ... ..	50.00
(9)		Motor omnibus conductor's licence ... ..	5.00
(10)		Registration of motor vehicle or trailer ... ..	100.00
(11)		Re-classification of registration of vehicle ... ..	100.00
(12)		Certificate of extract of entry in Register of Motor Vehicles other than on registration ... ..	100.00
(13)		Any duplicate or copy of a licence or permit authorised or required to be issued ... ..	70.00 for first duplicate or copy 300.00 for subsequent duplicate or copy
(14)		Examination of driver under section 53 ... ..	175.00

\*This Schedule has also been amended by the following: GNs 197/1957; 2/1963, 21/1963; Act No. 36 of 1967; GN 2/1968; Act No. 15 of 1968; GNs 13/1974, 27/1974; Acts Nos. 31 of 1976; 36 of 1976; 19 of 1978; 14 of 1979; LNs 146/1982; 3/1983; 4/1985, 23/1985; Acts Nos. 17 of 1986; 11 of 1988; 6 of 1993; 3 of 1994; 9 of 1997 and 2 of 2002.

**FEES AND DUTIES—Continued**

	\$
(15) Certificate of competency under section 53 ... ..	35.00
(16) Annual inspection of a—	
(a) trailer ... ..	300.00
(b) motor vehicle (commercial) ... ..	300.00
(c) motor vehicle (private) ... ..	251.00
(17) Dealer's licence ... ..	5,000.00
(18) Provisional permit ... ..	35.00
(19) Amendment to Register (other than a transfer of registration of the change of possession of a motor vehicle) ...	35.00
(20) Study guide booklet (including Highway Code) ...	15.00
(21) Permit to convey persons other than persons employed to load or unload goods, merchandise or other loads on goods vehicles, agricultural trailers or trailers for a period not exceeding six months ... ..	90.00 per month or part thereof
(22) Application for a taxi (other than a maxi-taxi) ... ..	70.00
(23) Taxi driver's licence/badge (renewable every three years)	40.00
(24) Duplicate licence/badge for taxi drivers under item (22) ...	40.00 for first duplicate 100.00 for subsequent duplicates
(25) Certified extract of motor vehicle Inspector's report ...	35.00

Section 62.  
[47 of 1956  
146/1969  
14 of 2017].

**SECOND SCHEDULE**

**SPEED LIMITS**

Class or Description of Vehicle	Maximum Speed kilometres per hour	
	Outside a Built-up Area	Within a Built-up Area
(a) Tractor (except a goods vehicle or private motor car with or without trailer) ... ..	35	20
(b) Motor omnibus ... ..	65	50
(c) Motor vehicle constructed to carry more than ten passengers ... ..	65	50
(d) Goods vehicle the licenced M.G.W. of which exceeds 3 200 kilogrammes with or without trailer ... ..	65	50
(e) Goods vehicle the licenced M.G.W. of which does not exceed 3 200 kilogrammes with trailer ... ..	65	50
(f) Goods vehicle the licenced M.G.W. of which does not exceed 3 200 kilogrammes without a trailer ... ..	100	50
(g) Private motor car with trailer ... ..	65	50
(h) Any other motor vehicle ... ..	100	50

**THIRD SCHEDULE**

Section 67.  
[3 of 1969].

**SCOPE OF EXPERIMENTAL TRAFFIC REGULATIONS  
THAT MAY BE MADE BY  
THE COMMISSIONER OF POLICE**

1. For prescribing the routes to be followed by all classes of traffic, or by any particular class or classes of traffic or vehicles, from one specified point to another, either generally or between any specified times.
2. For prescribing streets which are not to be used for traffic by vehicles, or by vehicles of any specified class or classes, either generally or at specified times.
3. For regulating the relative position in the roadway of traffic of differing speeds or types.
4. For prescribing the places where vehicles or vehicles of any particular class or description may not turn so as to face in the opposite direction to that in which they were proceeding, or where they may only so turn under conditions prescribed by the Regulations.
5. For prescribing the conditions subject to which, and the times at which, articles may be loaded on to or unloaded from vehicles, or vehicles of any particular class or description, on streets.
6. For prescribing the conditions subject to which, and the times at which, vehicles, or vehicles of any particular class or description, delivering or collecting goods or merchandise, or delivering goods or merchandise of any particular class or classes, may stand in streets, or in streets of any class or description, or in specified streets.
7. For prescribing rules as to precedence to be observed as between vehicles proceeding in the same direction, in opposite directions, or when crossing.
8. For prescribing places in streets where vehicles, or vehicles of any particular class or description, may, or may not, wait either generally or at particular times.
9. For prescribing cab ranks and ranks and stopping places of omnibuses and other public conveyances.

Section 14.

**\*FOURTH SCHEDULE**

Tax payable on registration of certain motor vehicles.

1. There shall be charged, levied and collected in respect of every motor vehicle of a class or description specified in the first column of Parts I and IA of Appendix A a tax (in this Act referred to as “motor vehicles tax”) calculated on such basis as is specified in the second column of the respective Part of Appendix A in relation to a motor vehicle of that class or description.

University of the West Indies exempted from motor vehicles tax.

1A. (1) Notwithstanding paragraph 1, all motor vehicles (including agricultural tractors) purchased by the University of the West Indies for its own use shall be exempt from motor vehicles tax.

(2) Where the University of the West Indies transfers ownership of a motor vehicle that is exempt from motor vehicles tax under paragraph 1 within five years from the date of registration of the motor vehicle, the motor vehicles tax shall immediately become payable.

Payment of motor vehicles tax. [14 of 1979 9 of 2017].

2. (1) Where motor vehicles tax is required to be paid on a motor vehicle, it shall be paid in the case of an imported motor vehicle by the importer of the vehicle and in the case of a locally assembled motor vehicle, by the assembler of the vehicle.

(2) Where a person who is required by this section to pay motor vehicles tax fails to do so, he is liable to a fine of one thousand dollars and to a further fine of one hundred dollars for each day that the motor vehicles tax remains unpaid after conviction.

Rebate of motor vehicles tax. [6 of 1977].

3. (1) Subject to this paragraph and to paragraphs 4 to 6 where motor vehicles tax has been paid on the sale of a private motor car, a taxi or a rented car (hereinafter referred to as a “motor car”) assembled in Trinidad and Tobago a rebate of tax shall be made to the manufacturer.

(2) For the purposes of subparagraph (1), motor vehicles tax shall be deemed to have been paid where the purchaser of the motor car was exempt from the payment of the tax or any part thereof or where the tax or any part thereof has been remitted.

(3) Subject to paragraph 7, the rebate of tax in respect of any such motor car shall be computed in accordance with Appendix B according to the local value added in the assembly of the motor car.

(4) Nothing in this paragraph shall apply in any case where the motor car is sold for export.

(5) In this paragraph and in paragraphs 5 and 6 “manufacturer” means a person who carries on in Trinidad and Tobago the business of assembling motor cars.

\*This Schedule has been amended by the following: Act No. 35 of 1957; GNs 115/1958; 2/1963, 21/1963; 27/1966; 6/1968; 2/1973; 11/1974; 6/1975; Acts Nos. 6 of 1977; 28 of 1978; 14 of 1979; 2 of 1982; LNs 146/1982; 3/1983, 157/1983; Acts Nos. 9 of 1990; 3 of 1994; 2 of 2002; 30 of 2007; 1 of 2009; 13 of 2010; 2 of 2013; 48/2014; †2 of 2015; 7 of 2016, 18/2016; 9 of 2017, 15 of 2017, 117/2017; 30 of 2020; 16 of 2021; 109/2022 and 245/2024.

†See Note on page 5.

‡Confirmed by LN 138/2017.

4. (1) In this paragraph, in paragraphs 3, 5 and 6 and in Appendix B and Appendix C, the local value added is the aggregate amount of the expenses specified in Appendix C incurred during the immediately preceding year in the assembly of motor cars similar to the motor cars in respect of which the claim for rebate of tax is made apportioned over the number of motor cars assembled during that year and expressed as a percentage of the showroom price of such motor car.

Local value added.  
[6 of 1977].

(2) Notwithstanding subparagraph (1) in any case where the Minister so directs the Board of Inland Revenue may reduce the aggregate amount of the expenses incurred in the assembly of any such motor cars by an amount representing the excess over the level of profits that the Minister considers appropriate to be taken into account in determining the local value added of any such motor cars.

(3) In any case where there is no immediately preceding financial year or the immediately preceding financial year is less than twelve months, the aggregate amount of expenses incurred in the assembly of similar motor cars in the current financial year shall be estimated in the claim for the rebate of tax and subject to subparagraph (4) be applied in determining the local value added.

(4) In any case where the aggregate amount of the expenses incurred in the assembly of similar motor cars is estimated under subparagraph (3), the Board of Inland Revenue shall as soon as it considers it convenient determine the twelve-month period to be taken as the immediately preceding financial year for the purpose of calculating the local value added with respect to any such motor cars for the first financial year.

(5) In this section “financial year” means the period of twelve months during which the business of a person is made up.

5. (1) The rebate of tax provided for in paragraph 3 shall be made monthly in arrear to a manufacturer upon a claim therefor.

Claim for rebate.  
[6 of 1977].

(2) Every claim for rebate of tax in respect of any motor car shall contain the following information:

- (a) the make, chassis number, registration number, engine number (measured in cubic centimetres) and the showroom price of the motor car sold in the current financial year with respect to which the claim is made;
- (b) the make, chassis number, registration number, engine number (measured in cubic centimetres) and the showroom price of similar motor cars sold during the immediately preceding financial year;
- (c) the local value added showing additional particulars required for the calculation thereof, or the estimated local value added; and

- (d) the amount of motor vehicles tax paid in respect of the motor car, the date of payment and the name and address of the office into which payment of the motor vehicles tax has been paid.

Examination of books of account. [6 of 1977].

6. The Board of Inland Revenue or any officer acting under its authority, may examine the books of account of a manufacturer for the purpose of determining the local value added in the assembly of the motor car in respect of which the claim for rebate of tax is made.

Commencement dates. [6 of 1977].

7. (1) Subject to subparagraphs (2) and (4), paragraphs 3 to 6 and subparagraph (3) of this paragraph shall be deemed to have come into operation on 4th July 1973.

Rate of rebate as from 1975.

(2) The rate of rebate of tax provided in Appendix B shall have effect in respect of the financial year ending in 1975 and subsequent years.

Rate of rebate until 1975.

(3) Until the rate of rebate of tax provided in Appendix B takes effect in accordance with subparagraph (2), the rate of rebate of tax, shall be as follows:

(a) Where the local value added exceeds 30 per cent but does not exceed 40 per cent, the rebate shall be—

(i) in the case of motor cars the showroom price of which is less than three thousand, five hundred dollars, 15 per cent of the motor vehicles tax;

(ii) in the case of motor cars the showroom price of which is three thousand, five hundred dollars or more but under five thousand dollars, 10 per cent of the motor vehicles tax;

(iii) in the case of motor cars the showroom price of which is five thousand dollars or more but under seven thousand dollars, 5 per cent of the motor vehicles tax.

(b) Where the local value added exceeds 40 per cent, the rebate shall be—

(i) in the case of motor cars the showroom price of which is less than three thousand, five hundred dollars, 20 per cent of the motor vehicles tax;

(ii) in the case of motor cars the showroom price of which is three thousand, five hundred dollars or more but under five thousand dollars, 15 per cent of the motor vehicles tax;

- (iii) in the case of motor cars the showroom price of which is five thousand dollars or more but under seven thousand dollars, 10 per cent of the motor vehicles tax.

(4) For the purposes of making rebate of tax during the period 1st January 1973 to 3rd July 1973, paragraphs 3, 4, 5 and 6 (together with Appendices B and C) shall be deemed to have come into operation on 1st January 1973 and shall be read and construed with such adaptations and modifications as are necessary or expedient, as if the Customs (Amendment) Act, 1968 was still in force.

Retrospective application to CARIFTA. [12 of 1968].

8. (1) Notwithstanding paragraph (1), motor vehicles tax shall not be charged, levied and collected in respect of a—

No motor vehicles tax on vehicles manufactured to use compressed natural gas. [7 of 2016, 18 of 2016, 15 of 2017, 30 of 2020].

- (a) new motor vehicle, imported for commercial use, with an engine size not exceeding 1 599 cc, which is manufactured to use compressed natural gas;
- (b) used motor vehicle, imported for commercial use, with an engine size not exceeding 1 599 cc, which is—
- (i) manufactured to use compressed natural gas; and
- (ii) not older than three years from the year of manufacture;
- (c) new motor vehicle, imported for commercial use, with an engine size exceeding 1 599 cc, which is manufactured to use compressed natural gas; and
- (d) used motor vehicle, imported for commercial use, with an engine size exceeding 1 599 cc, which is—
- (i) manufactured to use compressed natural gas; and
- (ii) not older than three years from the year of manufacture.

9. (1) Notwithstanding paragraph (1), motor vehicles tax shall not be charged, levied and collected in respect of a—

No motor vehicles tax on electric vehicles. [7 of 2016, 9 of 2017, 15 of 2017, 30 of 2020, 16 of 2021] \*246/2024.

- (a) new electric motor vehicle imported for private use; or
- (b) used electric motor vehicle imported for private use, which is not older than two years from the year of manufacture;

(2) In this paragraph, an “electric motor vehicle” means a motor vehicle, using only an electric motor for propulsion, referred to in the First Schedule to the Customs Act classified under Tariff Heading Numbers—

- (a) 8703.80.00; and
- (b) 8711.60.90.

\*Amendments made to paragraph 9(2) by LN 245/2024 took effect on 1st January 2025.

No motor vehicles tax on hybrid vehicles. [7 of 2016 9 of 2017 15 of 2017 30 of 2020 109/2022 \*245/2024].

10. (1) Notwithstanding paragraph (1), motor vehicles tax shall not be charged, levied and collected in respect of a—

- (a) new hybrid vehicle, imported for commercial use, with an engine size not exceeding 1 599 cc;
- (b) used hybrid vehicle, imported for commercial use, with an engine size not exceeding 1 599 cc, which is not older than three years from the year of manufacture;
- (c) new hybrid vehicle, imported for commercial use, with an engine size exceeding 1 599 cc but not exceeding 1 999 cc; and
- (d) used hybrid vehicle, imported for commercial use, with an engine size exceeding 1 599 cc not exceeding 1 999 cc, which is not older than three years from the year of manufacture.

(2) Notwithstanding paragraph (1), motor vehicles tax shall not be charged, levied and collected in respect of a—

- (a) new private hybrid vehicle, imported for private use, with an engine size not exceeding 1 599 cc; and
- (b) used private hybrid vehicle, imported for private use, with an engine size not exceeding 1 599 cc, which is not older than three years from the year of manufacture.

(3) In this paragraph—

“hybrid vehicle” means a vehicle which is capable of being propelled by a combination of an internal combustion engine and an on-board rechargeable energy system or other energy storage device; and

“private hybrid vehicle” means a vehicle which is—

- (a) capable of being propelled by a combination of an internal combustion engine and an on-board rechargeable energy system or other energy storage device, where the electric motor does not exceed a maximum power of 105 kW; and
- (b) referred to in the First Schedule to the Customs Act classified under Tariff Heading Numbers—
  - (i) 8703.40.00;
  - (ii) 8703.50.00;
  - (iii) 8703.60.00. and
  - (iv) 8703.70.00

\*Amendments made to paragraph 10(3) (b) by LN 245/2024 took effect on 1st January 2025.

**\*APPENDIX A**

Paragraph 1.

In this Appendix—

- (a) engine size references expressed in cm<sup>3</sup> means the total volume of the cylinders measured in cubic centimetres;
- (b) “showroom price” means such sum as in the opinion of the Board of Inland Revenue is the ordinary retail selling price of the motor vehicle without having regard to any discounts, commissions, monetary deductions, or other allowances given or made by the seller thereof.

**PART I**

**PARTICULARS OF TAX**

<i>Class of Description of Motor Vehicles Tax</i>	<i>Vehicle</i>
	\$
<b>(1) Private Motor Cars or Rented Cars, Station Wagons or Estate Wagons:</b>	
(a) Engine size not exceeding 1 599 cc ... ..	5.00 per cc
(b) Engine size exceeding 1 599 cc but not exceeding 1 799 cc ... ..	10.00 per cc
(c) Engine size exceeding 1 799 cc but not exceeding 1 999 cc ... ..	18.75 per cc
(d) Engine size exceeding 1 999 cc but not exceeding 2 499 cc ... ..	25.00 per cc
(e) Engine size exceeding 2 499 cc but not exceeding 2 999 cc ... ..	30.00 per cc
(f) Engine size exceeding 2 999 cc but not exceeding 3 499 cc ... ..	35.00 per cc
(g) Engine size exceeding 3 499 cc ... ..	50.00 per cc

\*This Appendix (Appendix A to the Fourth Schedule) has been amended by the following: Act No. 35 of 1957; GNs 115/1958; 2/1963, 21/1963; 27/1966; 6/1968; 2/1973; 11/1974; 6/1975; Acts Nos. 28 of 1978; 2 of 1982; LNs 146/1982; 3/1983, 157/1983; Acts Nos. 9 of 1990; 4 of 1992; 3 of 1994; 5 of 1995; 8 of 1996; 9 of 1997; 2 of 2002; 30 of 2007; 1 of 2009; 2 of 2013; 2 of 2015; 47/2016, 61/2016; 117/2017 and 30 of 2020.

Amendments made to this Appendix by LN 117/2017 were confirmed by Resolution—See LN 138/2017.

L.R.O.

**(2) Taxis:**

(a) Engine size not exceeding 999 cc	...	...	0.75 per cc
(b) Engine size exceeding 999 cc but not exceeding 1 499 cc	...	...	1.50 per cc
(c) Engine size exceeding 1 499 cc but not exceeding 1 799 cc	...	...	3.00 per cc
(d) Engine size exceeding 1 799 cc but not exceeding 1 999 cc	...	...	6.00 per cc
(e) Engine size exceeding 1 999 cc but not exceeding 2 499 cc	...	...	15.75 per cc
(f) Engine size exceeding 2 499 cc but not exceeding 2 999 cc	...	...	18.75 per cc
(g) Engine size exceeding 2 999 cc but not exceeding 3 499 cc	...	...	22.50 per cc
(h) Engine size exceeding 3 499 cc	...	...	33.75 per cc

**(3) Maxi-Taxis:**

(a) Engine size not exceeding 2 499 cc	...	...	6.00 per cc
(b) Engine size exceeding 2 499 cc	...	...	8.00 per cc

**\* (4) Goods Vehicles** ... .. 2.50 per cc

**(5) Tractors:**

(a) Agricultural tractors	...	...	1.00 per cc
(b) Industrial tractors	...	...	1.00 per cc

**(6) Completely Built-up Foreign-used Motor Vehicles**

imported by persons other than returning nationals, seventy-five per cent of the tax specified in subparagraph (1), (2), (3) or (4).

\*Note—For the purposes of this Part of this Schedule, a station wagon or estate vehicle is not a goods vehicle.

<i>Class of Description of Motor Vehicles</i>	<i>Vehicle Tax</i> \$
<b>(7) Motor Cycles:</b>	
(a) Engine size exceeding 300 cc ... ..	2.00 per cc
<b>(8) Private School Buses:</b>	
(a) Engine size not exceeding 2 499 cc ... ..	6.00 per cc
(b) Engine size exceeding 2 499 cc ... ..	8.00 per cc
<b>(9) Motor Omnibuses:</b>	
(a) Engine size not exceeding 2 499 cc ... ..	6.00 per cc
(b) Engine size exceeding 2 499 cc but not exceeding 3 499 cc ... ..	8.00 per cc
(c) Engine size exceeding 3 499 cc ... ..	12.00 per cc
<b>(10) Private Motor Cars which are manufactured to use compressed natural gas:</b>	
(a) new motor vehicles with an engine size not exceeding 1 599 cc ... ..	4.00 per cc
(b) used motor vehicles, with an engine size not exceeding 1 599 cc, which are not older than three years from the year of manufacture ...	3.00 per cc
<b>(11) Private Motor Cars which are manufactured as hybrid vehicles:</b>	
(a) new motor vehicles with an engine size not exceeding 1 599 cc ... ..	4.00 per cc
(b) used motor vehicles, with an engine size not exceeding 1 599 cc, which are not older than three years from the year of manufacture ...	3.00 per cc

PART IA

**PARTICULARS OF TAX FOR ELECTRIC VEHICLES**

<i>Class of Description of Motor Vehicles</i>	<i>Vehicle Tax</i> \$
<b>(1) Private Motor Cars or Rented Cars, Station Wagons or Estate Wagons:</b>	
(a) Engine size not exceeding 159 kilowatts	5.00 per kilowatt
(b) Engine size exceeding 159 kilowatts but not exceeding 179 kilowatts    ...    ...    ...	10.00 per kilowatt
(c) Engine size exceeding 179 kilowatts but not exceeding 199 kilowatts    ...    ...    ...	18.75 per kilowatt
(d) Engine size exceeding 199 kilowatts but not exceeding 249 kilowatts    ...    ...    ...	25.00 per kilowatt
(e) Engine size exceeding 249 kilowatts but not exceeding 299 kilowatts    ...    ...    ...	30.00 per kilowatt
(f) Engine size exceeding 299 kilowatts but not exceeding 349 kilowatts    ...    ...    ...	35.00 per kilowatt
(g) Engine size exceeding 349 kilowatts    ...	50.00 per kilowatt
<b>(2) Taxis:</b>	
(a) Engine size not exceeding 159 kilowatts    ...	1.50 per kilowatt
(b) Engine size exceeding 159 kilowatts but not exceeding 179 kilowatts    ...    ...    ...	3.00 per kilowatt
(c) Engine size exceeding 179 kilowatts but not exceeding 199 kilowatts    ...    ...    ...	6.00 per kilowatt
(d) Engine size exceeding 199 kilowatts but not exceeding 249 kilowatts    ...    ...    ...	15.75 per kilowatt
(e) Engine size exceeding 249 kilowatts but not exceeding 299 kilowatts    ...    ...    ...	18.75 per kilowatt
(f) Engine size exceeding 299 kilowatts but not exceeding 349 kilowatts    ...    ...    ...	22.50 per kilowatt
(g) Engine size exceeding 349 kilowatts    ...	33.75 per kilowatt
<b>(3) Maxi-Taxis:</b>	
(a) Engine size not exceeding 249 kilowatts    ...	6.00 per kilowatt
(b) Engine size exceeding 249 kilowatts    ...	8.00 per kilowatt

<i>Class of Description of Motor Vehicles</i>	<i>Vehicle Tax</i> \$
<b>(4) Goods Vehicles</b>	
<b>(5) Tractors:</b>	
(a) Agricultural tractors ... ..	1.00 per kilowatt
(b) Industrial tractors ... ..	1.00 per kilowatt
<b>(6) Private School Bus:</b>	
(a) Engine size not exceeding 249 kilowatts ...	6.00 per kilowatt
(b) Engine size exceeding 249 kilowatts ...	8.00 per kilowatt
<b>(7) Omni Bus:</b>	
(a) Engine size not exceeding 249 kilowatts ...	6.00 per kilowatt
(b) Engine size exceeding 249 kilowatts ...	8.00 per kilowatt
<b>(8) Private Motor Cars:</b>	
(a) new motor vehicles with an engine size not exceeding 159 kilowatts ... ..	4.00 per kilowatt
(b) used motor vehicles with an engine size not exceeding 159 kilowatts, which are not older than three years from the date of manufacture ... ..	3.00 per kilowatt

[28 of 1978  
30 of 2007  
2 of 2013].

PART II

RELIEF FOR CITIZENS RETURNING FROM ABROAD

1. (a) A returning national of Trinidad and Tobago who returns to Trinidad and Tobago to reside permanently after residing abroad for a continuous period of not less than five years, where he imports a vehicle of a class or description set out in item 1 in Part I of this Appendix, shall be entitled to full relief from motor vehicles tax.

(aa) Notwithstanding item 1(a), where a transfer of ownership of the motor vehicle occurs within two years of the date of its importation into Trinidad and Tobago, there shall become immediately due and payable by the transferor, the motor vehicles tax which would have been payable had the relief not been granted.

(ab) For the purposes of this Part, residing abroad for a continuous period of not less than five years shall not be affected by temporary visits to Trinidad and Tobago for periods not exceeding three months.

(b) A person seeking relief from motor vehicles tax shall satisfy the Board of Inland Revenue—

- (i) that he is the registered owner of the motor vehicle in respect of which he is required to pay motor vehicles tax;
- (ii) that he acquired the motor vehicle while abroad and was the owner of that vehicle for the entire period on which his claim for relief from motor vehicles tax is based.

2. *(Deleted by Act No. 30 of 2007).*

Paragraph 4(1).  
[6 of 1977].

APPENDIX B

RATE OF REBATE OF MOTOR VEHICLES TAX

Rate of rebate  
as from 1975.

(1) Where the local value added is 35 per cent or more but does not exceed 45 per cent the rebate shall be—

- (a) in the case of motor cars with an engine rating of under 1 500 cm<sup>3</sup>, 15 per cent of the motor vehicles tax;

- (b) in the case of motor cars with an engine rating of 1 500 cm<sup>3</sup> and over but under 1 800 cm<sup>3</sup>, 10 per cent of the motor vehicles tax;
  - (c) in the case of motor cars with an engine rating of 1 800 cm<sup>3</sup> and over but under 2 500 cm<sup>3</sup>, 5 per cent of the motor vehicles tax.
- (2) Where the local value added exceeds 45 per cent the rebate shall be—
- (a) in the case of motor cars with an engine rating of under 1 500 cm<sup>3</sup>, 20 per cent of the motor vehicles tax;
  - (b) in the case of motor cars with an engine rating of 1 500 cm<sup>3</sup> and over but under 1 800 cm<sup>3</sup> 15 per cent of the motor vehicles tax;
  - (c) in the case of motor cars with an engine rating of 1 800 cm<sup>3</sup> and over but under 2 500 cm<sup>3</sup>, 10 per cent of the motor vehicles tax.

### APPENDIX C

Paragraph 4(1).  
[6 of 1977].

#### EXPENSES FOR DETERMINING LOCAL VALUE ADDED

1. The expenses to be computed in determining the local value added are as follows:

- (a) wages and other earnings of wage labour paid, excluding overtime earnings, and wages and other earnings of wage labour paid to non-nationals;
- (b) salaries and other earnings of salaried staff and management fees paid, not including salaries and other earnings of salaried staff and management fees paid to non-nationals and to non-resident principals of resident companies;
- (c) any interest paid, not being interest paid to non-nationals and to non-resident principals of resident companies;
- (d) normal depreciation on physical assets, other than imported assets, as shown in the books of account;
- (e) payments for patents, royalties, licences and similar charges, not including payments for patents, royalties, licences and similar charges made to non-nationals and to non-resident principals of resident companies;
- (f) rent paid, not including rent paid to non-nationals and to non-resident principals of resident companies;
- (g) the cost of raw materials (including components and fuel power) other than imported raw materials, used in productions;

- (h) other overhead expenses apportionable to production, not including similar expenses incurred to non-nationals and to non-resident principals of resident companies; and
- (i) plant profit, not including profits distributed or remitted directly or indirectly to non-nationals and to non-resident principals of resident companies.

2. In this Appendix –

Ch. 78:01.

“Caribbean Common Market”, “Common Market Origin” and “Member State” have the same meanings respectively as in the Customs Act;

“imported” means imported from outside the Caribbean Common Market or imported from the Caribbean Common Market but not qualifying for treatment as goods of Common Market Origin;

“non-national” means a person who is not a citizen of a Member State and includes a person whose connection with such a State does not entitle him to be regarded as belonging to, or being a native or resident of the State for the purposes of the laws relating to immigration for the time being in force;

“non-resident-principal” means a person (including a company) who is not resident in a Member State;

“resident company” means a company incorporated in a Member State and not controlled directly or indirectly by a person (including a company) who is not resident in a Member State.

---

**FIFTH SCHEDULE**

Section 19A.  
[3 of 1994  
195/2009].

**PARTICULARS OF MOTOR VEHICLES TRANSFER TAX**

	\$	¢
(a) Used motor vehicles (other than motorcycles) over ten years old ... ..	150.00	
(b) Used motor vehicles (other than motorcycles) over seven years old, but not more than ten years old ...	1,350.00	
(c) Used motor vehicles (other than motorcycles) over five years old but not more than seven years ...	3,000.00	
(d) Used motor vehicles (other than motorcycles) over two years old but not more than five years old ...	4,500.00	
(e) Used motor vehicles (other than motorcycles) two years old and under ... ..	6,000.00	
(f) Used motorcycles not exceeding 250 cc ...	150.00	
(g) Used motorcycles exceeding 250 cc ... ..	300.00	

**SIXTH SCHEDULE**

Section 109.  
[5 of 2010].

**PARTICULARS OF THE SUMS REQUIRED TO BE PAID  
TO THE COMMISSIONER OF POLICE FOR  
ILLEGAL PARKING**

<i>Particulars</i>	\$
Removal Charge ... ..	300.00
Custody of Vehicle ... ..	200.00

(Section 20B).  
[9 of 2017].

**SEVENTH SCHEDULE**

**BREACH OF CONDITION CONSTITUTING  
A TRAFFIC VIOLATION**

Section	Condition
15(2)	Notification of destroyed or permanently unserviceable vehicles or vehicles that have been removed from Trinidad and Tobago.
19(6)	Registration of transfer within fourteen days of change of possession of a vehicle.
21	Vehicle to be used in compliance with its registration.
23(1B)	Windscreen or window of motor vehicle not to obscure view of inside of the vehicle from outside.
43B(2)	Motor vehicle to be fitted with seat belts.
43C(1)	Failure of a driver and any passenger seventeen years and over to wear a seat belt while the vehicle is in motion.
43C(1A)	Driving a vehicle with a person in the front seat who is not wearing a seat belt.
43D	Children under the age of five years to be properly restrained in motor vehicle.
46	Instructor to be holder of valid driving permit and give instructions to persons with a valid provisional permit.
48	Person to be physically fit to be the holder of a driving permit.
56	Person driving to be in possession of his driving permit while driving.
56A	Holder of driving permit from another country to have his travel document showing date of arrival while driving.
62	Driving within prescribed speed limits.
63	Take part in race or trial of speed with written permission of the Commissioner of Police.

Section	Condition
64	Comply with traffic signs.
65	Comply with Orders of the Minister in respect of one-way roads and parking of motor vehicles.
66	Comply with traffic direction.
66A	Comply with traffic light signal.
67	Comply with experimental traffic schemes.
68	Comply with Orders of the Commissioner of Police in respect of the prohibition or restriction of traffic on roads.
77	Person on motorcycle not to ride abreast of each other, not to hold on to another moving vehicle and not to carry unauthorised persons.
78	Driver not to distribute or allow the distribution of advertisements from a moving vehicle.
107	Person not to park in space adjoining or attached to a public building unless granted permission.
108(1)(a)	Remove vehicle parked in contravention of Act at the direction of police officer.
Fourth Schedule	Pay required motor vehicle tax.

**EIGHTH SCHEDULE**

(Section 80).  
[9 of 2017].

**PUBLIC BODIES ALLOWED TO ISSUE  
FIXED PENALTY NOTICES**

Airport Authority

Public Transport Service Corporation

The Chaguaramas Development Authority

The National Hospital Management Company Limited

(Sections 80,  
82, 84, 88B,  
88D, 88K,  
88P).  
[9 of 2017  
20 of 2020  
16 of 2021  
19/2022  
82/2024  
203/2024].

**NINTH SCHEDULE**  
**FIXED PENALTY AND DEMERIT POINTS**

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
1.	Using or altering a motor vehicle or trailer for a purpose not authorised by the registration or Licensing Authority	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 21(1)(b)	1,000.00	3	
2.	Public Service Vehicle carrying excess passengers	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 21(1)(c)	750.00	3	
3.	Goods vehicle carrying excess weight	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 21(1)(c)	4,000.00	4	
4.	Failure to comply with the permissible visible light transmittance of material on windscreen and window of motor vehicle	Motor Vehicles and Road Traffic (Windscreen and Window Tint) Regulations, Chap. 48:50, Regulation 3(1)	2,000.00	3	
4A.	Failure to maintain windscreen or window free from scratches, laminated glazing or glass that shows discolouration, material with any bubbling or other defects	Motor Vehicles and Road Traffic (Windscreen and Window Tint) Regulations, Chap. 48:50, Regulation 4(2)	450.00		

**NINTH SCHEDULE—Continued**

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
4B.	Installing unauthorised curtains, screens or other devices on motor vehicles	Motor Vehicles and Road Traffic (Windscreen and Window Tint) Regulations, Chap. 48:50, Regulation 5(1)	750.00	2	
4C.	Failure to have exemption certificate in a motor vehicle and failure to produce the exemption certificate upon request by a constable in uniform	Motor Vehicles and Road Traffic (Windscreen and Window Tint) Regulations, Chap. 48:50, Regulation 9(1)	1,000.00	2	
5.	Use of motor vehicle under dealer's licence by a person other than a dealer	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 39	1,000.00	3	
6.	Driving while disqualified from holding or obtaining a driving permit	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 42		14	Attendance at child traffic counselling programme
7.	Riding Motor Cycle without safety helmet	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 43(1)	1,000.00	4	Attendance at child traffic counselling programme

**NINTH SCHEDULE—Continued**

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
8.	Failure of a driver and any passenger seventeen years and over to wear a seat belt while the vehicle is in motion	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 43C(1)	1,000.00	4	Attendance at child traffic counselling programme
9.	Driving a vehicle with a person in the front seat who is not wearing a seat belt	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 43C(1A)	1,000.00	4	
10.	Driving a vehicle with a child in the front seat who is five years and under	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 43D(1)(a)	1,000.00	4	Attendance at child traffic counselling programme
11.	Failing to place a child who is five years and under in a child restraint or booster seat in the vehicle while driving the vehicle	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 43D(1)(b)	1,000.00	4	
12.	Offences of driving instructor	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 46	2,000.00	9	

**NINTH SCHEDULE—Continued**

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
13.	Exceeding the specified speed limit—  by 1 to 9 km per hour  by 10 to 20 km per hour  by 21 to 30 km per hour  by 31 km or more per hour	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 62(1)	  1,000.00  1,500.00  2,000.00  3,000.00	  0  2  4  6	Attendance at child traffic counselling programme
14.	Motor racing and speed trials between motor vehicles without permission	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 63	1,000.00	6	Attendance at child traffic counselling programme
15.	Traffic Signs	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 64	500.00	2	Attendance at child traffic counselling programme
16.	Breach of Traffic Order made by the Minister	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 65(1)	500.00	2	

**NINTH SCHEDULE—Continued**

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
17.	Failing to comply with directive of a police constable	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 66(a)	1,000.00	3	Attendance at child traffic counselling programme
18.	Failing to comply with a traffic sign or notice authorised by the Licensing Authority or Commissioner of Police, respectively	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 66(b)	500.00	2	Attendance at child traffic counselling programme
19.	Failing to comply with a traffic light signal	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 66A	1,000.00	3	Attendance at child traffic counselling programme
20.	Failing to comply with a traffic light signal captured under Part VA	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 66A	1,000.00		Attendance at child traffic counselling programme
21.	Contravention of Traffic Order made by the Commissioner of Police	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 68(7)	500.00	2	Attendance at child traffic counselling programme
22.	Breach of parking restriction made by the Minister	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 69(1)(b)	500.00	2	

**NINTH SCHEDULE—Continued**

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
23.	Driving when under the influence of drug	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 70		9	Attendance at child traffic counselling programme
24.	Driving or being in charge of a vehicle while blood alcohol levels exceed prescribed limit	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 70A		9	Attendance at child traffic counselling programme
25.	Failure to provide a specimen of breath or blood	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 70B		14	Attendance at child traffic counselling programme
26.	Failure to submit breath analysis or wilful alternation of concentration of alcohol in his breath or blood	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 70C		14	Attendance at child traffic counselling programme
27.	Careless Driving	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 72		6	Attendance at child traffic counselling programme
28.	Motor Cyclist holding onto another moving vehicle	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 77(2)(a)	750.00	2	
29.	Motor Cyclist riding with no hands on the handle bar	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 77(2)(b)	750.00	2	

**NINTH SCHEDULE—Continued**

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
30.	Throwing or distributing advertisements or handbills from a vehicle	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 78(1)	300.00		
30A.	Failure to attend child traffic counselling programme	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 84B		1	Attendance at child traffic counselling programme
31.	Standing for hire at a place not appointed for the purpose	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 91(3)	500.00	2	
32.	Unauthorised parking on grounds of a public building	Motor Vehicles and Road Traffic Act, Chap. 48:50, section 107(1)	750.00	2	
33.	Defaced or defective identification plate	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 7	450.00	2	
34.	No identification plate fixed to the front or back of the vehicle	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 9	750.00	3	
35.	No identification lights for the illumination of identification marks on vehicle at night	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 10	300.00		

**NINTH SCHEDULE**—*Continued*

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
36.	Failing to observe restrictions on pedestrian crossings	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulations 16, 17 and 18	1,200.00		
37.	Number of passengers to be carried not printed on right front door of taxi	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 17(a)	300.00		
38.	Failure to produce a vehicle for inspection/Driving a vehicle without a valid inspection sticker and certificate	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 27(11)	1,000.00	6	
39.	No Tare and M.G.W. painted on vehicles	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 28(1)(h)	1,000.00		
40.	Vehicle with defective fittings	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 28(1)(i)	450.00		
41.	Vehicle without silencers or fitted with cut outs	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 28(1)(j)	300.00	2	
42.	Unauthorised lights to front or rear of vehicle	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 28(1)(k)	750.00	3	

**NINTH SCHEDULE—Continued**

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
43.	Unauthorised letters and figures on vehicle	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 28(1)(l)	750.00		
44.	Vehicle without two head lamps	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 28(1)(m)(i)	1,000.00		
45.	Vehicle without park lights	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 28(1)(m)(ii)	1,000.00		
46.	Vehicle without tail lights	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 28(1)(m)(iii)	1,000.00		
47.	Vehicle with unauthorised spot or swivel lights	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 28(1)(m)(iv)	1,000.00	4	
48.	No “left hand drive” notice affixed to appropriate vehicle	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 31(2)	300.00		
49.	Reversing on roads for an unreasonable distance	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 1	750.00	3	Attendance at child traffic counselling programme

**NINTH SCHEDULE—Continued**

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
50.	Reversing at the junction of roads or around corner in the City of Port-of-Spain or San Fernando	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 1	1,000.00	2	
51.	Quitting vehicle before applying brakes and switching off engine	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 3	1,000.00		
52.	Failing to keep vehicle to left on road	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 5(1)	1,000.00		
53.	Improper overtaking on the left side of the road	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 5(3)	1,000.00	3	
54.	Obstructing overtaking traffic	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 5(4)	1,000.00	3	
55.	Improper overtaking on the right, cutting in	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 5(5)	1,000.00	3	
56.	Overtaking traffic at a place dangerous to do so	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 5(6)	1,000.00	3	

**NINTH SCHEDULE—Continued**

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
57.	Parking within nine metres of a corner	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 5(10)	500.00		
58.	Drawing up alongside another vehicle; backing motor vehicle to kerb or roadside	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 5(11)	500.00		
59.	Parking within three metres of a fire hydrant	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 5(12)	500.00	2	
60.	Parking within three metres of the front of a fire station	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 5(13)	1,000.00	2	
61.	Negligently or wilfully interrupting the free passage or causing an unnecessary obstruction	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 6	600.00	3	
62.	Failing to draw up as close as possible to the side of the road	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 11	300.00		
63.	Vehicle without horn	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 12(1)	300.00	3	

**NINTH SCHEDULE**—*Continued*

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
64.	Permitting excess sparks, smoke or visible vapour to come from vehicle	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 13	1,000.00		
65.	Vehicle carrying excessive projection	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 15	750.00	2	
66.	Overcrowded vehicle	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 16	1,000.00	3	
67.	Carrying persons in a dangerous manner	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 17	1,000.00	3	Attendance at child traffic counselling programme
68.	Leaving broken-down vehicle on road unattended	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 18	500.00		
69.	Failing to draw up vehicle for passage of any engine or other apparatus of the Fire Service, Police Vehicles, Defence Force Vehicles or Ambulances.	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 19	1,000.00	3	

**NINTH SCHEDULE—Continued**

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
70.	Towing other than a motor vehicle without written permission of the Licensing Authority	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 20	600.00	2	
71.	Length of tow rope exceeding five metres	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 38, Rule 21	450.00		
72.	Vehicle without reflecting mirror	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 40	750.00		
73.	Vehicle carrying unsecured load	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 42	750.00	2	
74.	Use of noisy vehicle	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 43	300.00	2	
75.	Use of vehicle with defective tyres	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 44	1,000.00	3	
76.	Use of vehicle with no windshield wiper or defective wiper	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 46	300.00		

**NINTH SCHEDULE—Continued**

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
77.	Playing a musical or noisy instrument in a vehicle without permission of the Licensing Authority	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 49	1,000.00		
78.	Driving vehicle on footpath or pavement	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 57	1,000.00	3	
79.	Public Service vehicle without spare tyre	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 76(j)	750.00		
80.	Public Service vehicle importuning of passenger	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 78	750.00		
81.	Taxi Driver unsuitably attired	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 79	750.00		
82.	Placing of advertisement on side of window of taxi	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 80	300.00		
83.	Taxi unattended at head of taxi stand	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 81(2)	600.00		
84.	Failing to occupy vacant space in taxi stand	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 94(2)	750.00		

**NINTH SCHEDULE—Continued**

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
85.	Parking in a public stand appointed for taxi	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 95	750.00	3	
86.	Stopping or parking or driving a motor vehicle on a surveillance bay	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 110A(2)	1,000.00	3	
87.	Failing to preserve taxi driver's badge against loss, destruction or defacement	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 115	300.00		
88.	Failing to produce taxi driver's badge and licence on demand	Motor Vehicles and Road Traffic Act, Chap. 48:50, Regulation 115	450.00	2	
89.	Use of Priority Bus Route by unauthorised vehicle	Special Roads (Traffic) Regulations Chap. 48:01, Regulation 2	2,000.00	6	Attendance at child traffic counselling programme
90.	Using or causing to be used or permitting a person to use a motor vehicle or licenced trailer on a public road without a valid policy of insurance	Motor Vehicles Insurance (Third-Party Risks) Act, Chap. 48:51, section 3	1,000.00	3	Attendance at child traffic counselling programme

**NINTH SCHEDULE**—*Continued*

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
91.	Unauthorised driving or parking within Queen's Park Savannah	Queen's Park Act, Chap. 41:04, Regulation 1A	1,000.00		
92.	Operation of maxi-taxis outside specified route	Maxi-Taxi Act, Chap. 48:53, Regulation 7(1)	1,000.00	3	
93.	Vehicle painted in such a manner as to be mistaken for a maxi-taxi	Maxi-Taxi Act, Chap. 48:53, section 12(1)	1,000.00	3	
94.	Driving while holding or using a hand-held mobile device	Motor Vehicles and Road Traffic (Mobile Devices) Regulations, Chap. 48:50, Regulation 4	1,000.00	3	Attendance at child traffic counselling programme
95.	Holding or using a hand-held mobile device while supervising the holder of a provisional permit	Motor Vehicles and Road Traffic (Mobile Devices) Regulations, Chap. 48:50, Regulation 5	1,000.00	3	
96.	Using a wireless communication device to view, send or compose an electronic message while driving or having charge of a vehicle	Motor Vehicles and Road Traffic (Mobile Devices) Regulations, Chap. 48:50, Regulation 57	1,000.00	3	Attendance at child traffic counselling programme

**NINTH SCHEDULE—Continued**

	First Column	Second Column	Third Column	Fourth Column	Fifth Column
	<i>Description of Traffic violation or Offence</i>	<i>Relevant Section/Regulation</i>	<i>Fixed Penalty \$</i>	<i>Demerit Points</i>	<i>Penalty where committed by a child</i>
97.	Failure to observe restrictions on the use of a disability parking permit in a disability parking zone or displaying a cancelled or expired disability parking permit or destroying, mutilating, defacing or altering a disability parking permit or failing to adhere to any condition for the use of a disability parking permit as registered in the register	Motor Vehicles and Road Traffic (Persons with Disability Parking Permit) Regulations, Chap. 48:50, Regulation 7	2,000.00	3	
98.	Failure to display a disability parking permit in or on a vehicle in such manner as directed by the Licensing Authority	Motor Vehicles and Road Traffic (Persons with Disability Parking Permit) Regulations, Chap. 48:50, Regulation 9	750.00		
99.	Failure to return an invalid disability parking permit to the Licensing Authority in specified circumstances	Motor Vehicles and Road Traffic (Persons with Disability Parking Permit) Regulations, Chap. 48:50, Regulation 12	500.00		

### NOTE ON TRANSITIONAL PROVISIONS

The Amendment Act 14 of 1979 contained the following transitional provisions:

17. (1) Subject to \*section 31, upon the commencement of this Act—
- (a) a person who is the holder of a learner's permit, may continue to use that permit until it expires or until he becomes entitled to be issued a drivers permit whichever happens first;
  - (b) a person who is the holder of a driving permit to drive a private motor car, is permitted to drive a Class 3 motor vehicle, save that in order to drive a taxi he is required to have in addition to the driving permit a taxi driver's licence and badge;
  - (c) a person who is the holder of a driving permit to drive a heavy goods vehicle, is permitted to drive a Class 4 motor vehicle.

(2) A person who immediately before the commencement of this Act was the holder of a permit to drive a heavy goods vehicle and who during the currency of that permit used to drive any vehicle which under this Act is a Class 5 vehicle may continue to drive such a vehicle for a period not exceeding six months from the commencement of this Act, and shall upon production to the Transport Commissioner within that period, of satisfactory evidence of the fact of his driving such a vehicle, be issued the appropriate driving permit under this Act.

(3) Where a person referred to in subsection (2) fails to produce satisfactory evidence as required by that subsection, he shall be required to take and pass a driving test in order to be issued a driving permit for a Class 5 motor vehicle.

---

\*Section 31 (now Section 48) of this Act, Act 14 of 1979 came into operation on 1st May 1979.

**SUBSIDIARY LEGISLATION**

---

**MOTOR VEHICLES AND ROAD TRAFFIC REGULATIONS**

ARRANGEMENT OF REGULATIONS

REGULATION

**PART I  
GENERAL**

1. Citation.
2. Interpretation.
3. Forms, as in First Schedule.

**PART II  
REGISTRATION**

4. Application by owner for registration.
5. Number to be assigned.
6. When Licensing Authority may cancel registration.
7. Identification mark.
- 7A. Identification marks for diplomatic vehicles or trailers.
8. Use for registered purpose only.
9. Position of identification mark.
10. Illumination of identification mark at night.
11. General identification marks for dealer.
12. Record Book.

**PART III  
LICENSING**

13. *(Revoked by Act No. 9 of 1997).*
14. Weighing of vehicles.
15. } *(Repealed by Act No. 9 of 1997).*
16. }
17. Number of persons to be carried.

REGULATION

PART IV

**DRIVING AND CONDUCTOR'S PERMITS**

18. Application for permit.
19. Form of driving permit or provisional permit.
20. Application for renewal prior to date of expiration.
- 20A. Application for renewal where applicant will be absent from country.
21. Conductor's permit.
22. Badges for conductors.
23. Re-issue of lost or defaced permit or badge.
24. Cancellation or suspension of conductor's permit.
25. Cancellation or suspension of driver's permit.
26. Medical certificate.

PART V

**INSPECTION OF MOTOR VEHICLES**

27. Inspection of motor vehicles, etc., and register.

\*PART VA

**AUTHORISED EXAMINERS AND PREMISES**

- 27A. Applications for authorisations.
- 27B. Authorisations.
- 27C. Conditions to be complied with by proprietors.
- 27D. Termination of authorisation.
- 27E. Forms and documents to be returned to Transport Commissioner.
- 27F. Application for examination.
- 27G. Requirements as to vehicles submitted for examination.
- 27H. Conditions as to responsibility for damage to vehicles and third party.
- 27I. Results of examinations.
- 27J. Refusal of a test certificate where braking test cannot be carried out.
- 27K. Removal of vehicles submitted for examination.

ARRANGEMENT OF REGULATIONS—*Continued*

**REGULATION**

- 27L. Appeal on refusal of a test certificate.
- 27M. Payment to proprietors at whose premises examinations on appeals are carried out.
- 27N. Fees for examination.
- 27O. Fees on appeals.
- 27P. Records to be kept and returns to be furnished by proprietors.
- 28. Conditions of use of motor vehicles on public road.
  - Reversing.
  - Width.
  - Length.
  - Overhang.
  - Distribution of weight.
  - Brakes.
  - Trailers.
  - Weight shown in certain cases.
  - Condition of vehicle.
  - Silencers.
  - Cut-outs.
  - Unauthorised lights.
  - Unauthorised letters and figures.
  - Lights.
- 29. Stationary motor vehicle.
- 30. Direction indicators.
- 31. Left-hand driven vehicles.

**PART VI**

**INSPECTION OF VEHICLES OTHER  
THAN MOTOR VEHICLES**

- 32. Definition.
- 33. Bells, etc.
- 34. Lights on vehicles other than motor vehicles.
- 35. Cycle brakes.

**REGULATION**

- 36. Constable may test cycle brakes.
- 37. Liability of parents and guardians.

**PART VII**

**USE OF MOTOR VEHICLES**

- 38. Rules to be observed by drivers.
  - Travelling backwards.
  - Full control and view to be maintained.
  - Brakes to be applied and engine stopped on quitting motor vehicle.
  - Restrictions as to sitting by driver.
  - To keep to the left.
  - To keep on the left on meeting other traffic.
  - Overtaking.
  - Being overtaken.
  - Cutting in.
  - Corners.
  - Crossings.
  - Turning to left.
  - Turning to right.
  - Stopping at corners.
  - Drawing up alongside other motor vehicles.
  - Drawing up and standing alongside of fire hydrant.
  - Obstruction.
  - Turnings and crossroads.
  - Traffic signals.
  - Traffic directions.
  - Slow moving traffic.
  - Drawing up at side of road.
  - Horns, etc.
  - Sparks, smoke, vapour, lubricating oil.
  - Stopping of motor vehicle at request of constable, or person in charge of horse.
  - Projections.
  - Overcrowding.

ARRANGEMENT OF REGULATIONS—*Continued*

REGULATION

- Riding outside.
- Motor vehicles unattended.
- Passage of Fire Brigade.
- Towing other vehicles.
- Length of tow rope.
- 39. Filling petrol into motor vehicles.
- 40. Reflecting mirror.
- 41. Fittings and equipment to be properly adjusted.
- 42. Load to be properly secured.
- 43. Noisy motor vehicles.
- 44. Tyres.
- 45. Safety glass windshield.
- 46. Windshield wiper.
- 47. Traffic signal.
- 48. Cyclists and pedestrians to comply with traffic control signal.
- 49. Prohibition on playing of musical or noisy instruments in a motor vehicle.

PART VIII

**USE OF VEHICLES OTHER THAN  
MOTOR VEHICLES AND OF ANIMALS**

- 50. Application of certain provisions of Part VII to drivers and riders of vehicles other than motor vehicles, and of animals.
- 51. Traffic signals.
- 52. Reckless driving.
- 53. Careless driving.
- 54. Driving or riding while under influence of drink.
- 55. Control of animal drawing vehicle.
- 56. Control of cattle.
- 57. Driving or riding on the footpath.

REGULATION

PART IX

**PUBLIC SERVICE VEHICLES—  
CONSTRUCTION AND MAINTENANCE**

**MOTOR OMNIBUSES**

58. Body and chassis.
59. Curtains, screens, etc., to be properly fastened.
60. Flooring.  
Fittings for motor omnibuses.
61. Seats, corridor and safety exits.
62. Steps, etc.
63. Toeguards.
64. Driver's seat.
65. Conductor's seat.
66. Motor omnibus to carry conductor.
67. Front protection.
68. Internal height.
69. Driver's uniform and badge.
70. Special regulations for motor bus conductors.
71. Motor bus to proceed direct to destination.
72. Entering or leaving bus.
73. Licensing Authority may delegate his powers.
74. Motor omnibuses registered prior to 1st January 1935.
75. Saving as to motor omnibus.

**PUBLIC SERVICE VEHICLES**

76. Special regulations for drivers of public service vehicles.
77. Lost property.
78. Touting.
79. Attire of taxi driver.
80. Advertisement.

ARRANGEMENT OF REGULATIONS—*Continued*

REGULATION

- 81. Refusal to hire motor vehicle.
- 82. *(Repealed by LN 197/1999).*
- 83. *(Deleted by LN 34/2003).*
- 84. Right to demand fare.

PART X

**RESTRICTIONS RELATING TO  
MOTOR OMNIBUSES**

- 85. Omnibus routes.
- 86. Routes to be specified on licence.
- 87. Special permits.
- 88. )
- to } *(Repealed by LN 197/1999).*
- 90. )
- 91. Reconsideration of Licensing Authority's decision.

PART XI

**RULES FOR PARKING OF VEHICLES**

- 92. No lighted lamps on motor vehicles required when in parking places and public stands.
- 93. Rules for parking of taxis.
- 94. Taxis leaving stands.
- 95. Parking of taxis.
- 96. Alignment of omnibuses.
- 97. Omnibuses leaving stands.
- 98. Parking.
- 99. )
- 100. } *(Repealed by LN 197/1999).*

REGULATION

PART XII

TRAFFIC LIGHT SIGNALS

101. Licensing Authority to erect and maintain light signals.
102. Significance of light signals.
103. *(Repealed by LN 197/1999).*
104. "Cross" and "Don't Cross" Signals.
- 104A. Inoperative traffic lights.

PART XIII

SPECIAL TRAFFIC DIRECTIONS

105. Traffic at dual carriageways.
106. Traffic at roundabouts.
107. Traffic at crossroads.
108. *(Repealed by LN 197/1999).*
109. Restricting lorries on part of High Street.
110. Parking of vehicles in San Fernando.
- 110A. Restriction on use of surveillance bays.

PART XIV

TAXIS

111. Taxi Drivers' licences.
112. Duplicate licences.
113. Cancellation of Taxi Drivers' licences.
114. Changes in particulars set out in taxi drivers' licences to be notified.
115. Production and inspection of taxi drivers' licences.
116. Only bona fide passengers to be in taxis plying for or on hire in taxi stands.  
No person to loiter on or about a taxi stand.
117. Taxi not to be used for indecent or immoral purpose.
118. *(Repealed by LN 197/1999).*
119. Exemption.
120. Rented cars not to be used as taxis.

**REGULATION**

**PART XV**

**MISCELLANEOUS**

121. Limitation of drivers' working hours.
122. Discretionary powers of Licensing Authority.
123. Eastern Main Road Regulations.
124. Eastern Main Road, Demerara Road, Aripo and Heights of Guanapo Roads.
125. Western Main Road.
126. Chaguanas Road.
127. Liability for contravention or failure to comply with Regulations.

**FIRST SCHEDULE.**

**SECOND SCHEDULE.**

**THIRD SCHEDULE.**

**FOURTH SCHEDULE.**

**FIFTH SCHEDULE.**

**SIXTH SCHEDULE.**

**SEVENTH SCHEDULE.**

---

**\*MOTOR VEHICLES AND ROAD TRAFFIC  
REGULATIONS**

G. 1.6.44.

*made under section 100*

**PART I  
GENERAL**

1. These Regulations may be cited as the Motor Vehicles and Road Traffic Regulations.

Citation.

2. In these Regulations—

“at night” means from half an hour after sunset until half an hour before sunrise, or such other period for the lighting of vehicles as shall be fixed from time to time by the Commissioner of Police and published in the *Gazette*;

Interpretation.  
[177/1956  
39/1957  
151/1971  
197/1999  
6 of 2023].

“Borough of Arima” means the Borough of Arima as defined in the First Schedule to the Municipal Corporations Act;

Ch. 25:04.

“Borough of Chaguanas” means the Borough of Chaguanas as defined in the First Schedule to the Municipal Corporations Act;

“Borough of Diego Martin” means the Borough of Diego Martin as defined in the First Schedule to the Municipal Corporations Act;

“Borough of Point Fortin” means the Borough of Point Fortin as defined in the First Schedule to the Municipal Corporations Act;

“Borough of Siparia” means the Borough of Siparia as defined in the First Schedule to the Municipal Corporations Act;

“centre line” means any line printed on, or made of metal or any other suitable material placed on, in or near the centre of a road for the purpose of dividing the directions in which traffic must flow or the lanes of traffic flowing in the same direction;

\*These Regulations were amended by the following: GNs 200/1951, 233/1951; 83/1952; 71/1953; 177/1956; 26/1957, 27/1957, 39/1957; 43/1958, 124/1958, 148/1958; 94/1959, 125/1959; 108/1960; 88/1961; 11 of 1963; 32/1964, 32 of 1964; 21/1966, 73/1966; 105/1970; 57/1971, 86/1971, 151/1971; 105/1972; 15/1977; 27/1979, 61/1979, 72/1979, 206/1979, 207/1979, 208/1979, 211/1979; 104/1982; 6 of 1993; 9 of 1997; 197/1999; (See Act No. 9 of 2001); 34/2003; 8 of 2009; 207/2011; 80/2013, Act No. 9 of 2017, LN 146/2017; 96/2018, 99/2018; 311/2020; LN 120/2022 and Act No. 6 of 2023.

*These Regulations, though made under section 100, are published first because of their importance and because it avoids the inconvenience of separating certain of the Orders from the others.*

\*Amendments made by LN 146/2017 took effect on 1st December 2017.

Ch. 25:04.

“City of Port-of-Spain” means the City of Port-of-Spain as defined in the First Schedule to the Municipal Corporations Act;

“City of San Fernando” means the City of San Fernando as defined in the First Schedule to the Municipal Corporations Act;

“cycle” means a pedal bicycle or pedal tricycle, not being in either case a mechanically propelled vehicle;

“identification mark” means the index mark and the separate number referred to in regulation 7(1)(a)(i);

“lateral overhang” means the distance measured from the outer face of the tyre on the rear wheel on the same side of the vehicle (and in the case of dual tyres from the outer face of the outer tyre) to a vertical line let fall from the extreme limit of the body;

“longitudinal overhang” means the distance measured from the centre of a hub of a rear wheel to a vertical line let fall from the extreme limit of the body;

“Municipal area” means the City of Port-of-Spain, the City of San Fernando, the Borough of Arima, the Borough of Chaguanas, the Borough of Diego Martin, the Borough of Point Fortin or the Borough of Siparia;

“overall length”, in relation to a single vehicle, means the length of the vehicle exclusive of the starting handle, if any, and of the hood, if any, when down, or, in the case of a trailer, the drawbar, measured between parallel planes passing through the extreme projecting points of the vehicle, and, in relation to a combination of vehicles, the length measured between parallel planes passing through the extreme forward projecting point of the tractor and the extreme rear projecting point of the last trailer being towed;

“overall width” means the width measured between parallel lines passing through the extreme projecting points of the vehicle exclusive of any driving mirror or of any direction indicator when in operation, and of so much of the distortion of any tyre as is caused by the weight of the vehicle;

“overcrowding” means more persons than will allow the driver to operate his vehicle freely without interference, and safely; that is,

if his movement as they affect the gear shift lever, the brakes, the clutch, the steering wheel, is interfered with, or if his vision is obstructed so that he cannot safely drive or operate his vehicle;

“public stand” means an appointed place where public service vehicles or any particular class of public service vehicles may wait;

“schedule” means a schedule to these Regulations;

“stopline” means any line painted on, or made of metal or other suitable material placed on, a road for indicating where traffic must stop when required to do so either by a constable engaged in the control of traffic or by a traffic sign or by a light signal.

3. For the purposes of the Act the forms set out in the First Schedule, or forms to the like effect, may be used in the cases to which they refer, with such variation as the Licensing Authority may consider desirable.

Forms, as in First Schedule.

## PART II REGISTRATION

4. The owner of a motor vehicle or trailer who desires to register it shall apply to the Licensing Authority and shall furnish him with the particulars set out in the form of application in the First Schedule.

Application by owner for registration. (Form 1).

First Schedule.

5. On receipt of any such application, with the particulars and the fee of ten dollars, the Licensing Authority shall, subject to the provisions of the Act, assign a separate number to the motor vehicle or trailer and register it by making the required entries in the register. On the registration of a motor vehicle or trailer, the Licensing Authority shall furnish the owner thereof with a certified copy of the entry.

Number to be assigned.

6. Where the Licensing Authority is satisfied that—

- (a) a motor vehicle or trailer is destroyed, broken up or permanently removed from Trinidad and Tobago;
- (b) the owner of a motor vehicle registered under section 12(3A) of the Act is no longer entitled to enjoy privileges and immunities under the Privileges and Immunities (Diplomatic, Consular and International Organisation) Act; or

When Licensing Authority may cancel registration. [80/2013].

Ch. 17:01.

- (c) an application is made to transfer a motor vehicle registered under section 12(3A) of the Act to a person who is not entitled to enjoy privileges and immunities under the Privileges and Immunities (Diplomatic, Consular and International Organisation) Act,

the Authority may cause the entries in the register with respect to that vehicle to be cancelled and may, where appropriate, assign the registered number of the motor vehicle or trailer to any other motor vehicle or trailer.

Identification  
mark.  
[151/1971  
27/1979  
72/1979  
9 of 1997  
96/2018].

7. (1) The identification mark to be carried by a registered motor vehicle or trailer in pursuance of section 12 of the Act, shall consist of two plates which must conform as to size, lettering, numbering and otherwise with the following provisions:

- (a) (i) subject to subregulation (1A), each plate must be rectangular and bear upon it the index mark of "P" for private motor vehicles, "T" for goods vehicles, "R" for rented cars, "H" for public service vehicles, "X" for any other vehicle and the separate number assigned to the motor vehicle by the Licensing Authority;
- (ii) the mark and number shall be arranged in conformity with the arrangement of letters and figures shown on one or other of the alternative diagrams in the Second Schedule: Provided that as regards numbers reassigned in series the letter of designation shall be prefixed as mentioned in subparagraph (i);
- (b) the two plates may, at the option of the owner, be of either of the shapes shown in the alternative diagrams in the Second Schedule or one of one shape and one of the other;
- (c) (i) the identification mark shall be formed of white letters and figures on a black surface, and every letter or figure shall be indelibly inscribed or so attached to such surface that it cannot readily be detached therefrom;

Second  
Schedule.

- (ii) the identification mark may, at the option of the owner, be constructed and used in a manner which illuminates it by reflection, transparency, translucency or otherwise. If the identification mark is so constructed and used, the letters and figures shall be black on a white surface, and every letter or figure shall be indelibly inscribed or so attached to such surface that it cannot readily be detached therefrom;
- (d) all letters and figures must be eighty-five millimetres high; every part of every letter and figure must be fifteen millimetres broad; and the total width of the space taken by every letter or figure, except in the case of the figure 1, must be sixty millimetres;
- (e)
  - (i) subject to subparagraph (ii), the space between adjoining letters and between adjoining figures on each plate shall be ten millimetres, and there shall be a margin between the nearest part of any letter or figure and the top and bottom of the plate of at least ten millimetres, and between the nearest part of any letter or figure and the sides of the plate of at least twenty-five millimetres;
  - (ii) where a registration number comprises three letters and four figures the space between adjoining letters and between adjoining figures on each plate shall be eight millimetres, and there shall be a margin between the nearest part of any letter or figure and the top and bottom of the plate of at least ten millimetres, and between the nearest part of any letter or figure and the sides of the plate of at least fifteen millimetres;

(f) in the alternative diagram No. 1, the space between the upper and lower lines must be fifteen millimetres. In the alternative diagram No. 2, the space between the letter and the figures must be thirty-five millimetres.

(1A) The number component of an identification mark issued under this regulation shall from time to time be assigned by the Licensing Authority in random or consecutive order from numbers 1 through 9999 for each series having a letter of the alphabet prefixed to the number.

Second  
Schedule.

(2) Letters and numbers as prescribed in the Second Schedule painted on or otherwise fixed to the motor vehicle or trailer, may be used instead of plates. Any reference to plates in these Regulations shall be construed to include a reference to numbers and letters so painted or fixed, and any reference to the fixing of plates to include a reference to the numbers and letters so painted or fixed or other delineation of the numbers and figures.

Identification  
marks for  
diplomatic  
vehicles or  
trailers.  
[80/2013].

**7A.** The identification mark to be carried by a motor vehicle registered in pursuance of section 12(3A) of the Act, shall consist of two plates which must conform to size, lettering, numbering and otherwise as follows:

- (a) each plate shall be rectangular and bear upon it the index mark of "DM" for diplomatic missions or diplomatic agents, "CP" for consular post or consular officers, and "IO" for regional or international organisations or officials of international organisations and a separate number assigned by the Licensing Authority;
- (b) the mark and number shall be arranged in conformity with the arrangement of letters and figures shown on one of the alternative diagrams in the Second Schedule;
- (c) the identification mark shall be formed of black letters and figures on a yellow surface and every letter or figure shall be indelibly inscribed or so attached to such surface that it cannot readily be detached therefrom;

Second  
Schedule.

- (d) all letters and figures shall be eighty-five millimetres high and every part of every letter and figure shall be fifteen millimetres broad and the total width of the space taken by every letter or figure, except in the case of figure 1, shall be sixty millimetres;
- (e) subject to paragraph (f), the space between adjoining letters and between adjoining figures on each plate shall be ten millimetres, and there shall be a margin between the nearest part of any letter or figure and the top and bottom of the plate of at least ten millimetres, and between the nearest part of any letter or figure and the sides of the plate of at least twenty-five millimetres; and
- (f) where a registration number comprises three letters and four figures, the space between adjoining letters and between adjoining figures on each plate shall be eight millimetres and there shall be a margin between the nearest part of any letter or figure and the top and bottom of the plate of at least ten millimetres and between the nearest part of any letter or figure and the sides of the plate of at least fifteen millimetres.

8. No person shall use a motor vehicle for a purpose other than that for which it is registered.

Use for registered purpose only. [11 of 1963].

9. The plates forming the identification mark shall be fixed, one on the front and the other on the back of the motor vehicle or trailer, in an upright position, so that every letter or figure on the plate is upright and easily distinguishable, in the case of the plate placed on the front of the motor vehicle or trailer from in front of the motor vehicle or trailer, and in the case of the plate placed on the back, from behind the motor vehicle or trailer.

Position of identification mark.

In the case of a motor cycle, the plate fixed on the front of the cycle may, if it is a plate having duplicate faces conforming with the Second Schedule be fixed so that from whichever side the

Second Schedule.

cycle is viewed the letters or figures on one or other face of the plate are easily distinguishable, though they may not be distinguishable from the front of the cycle.

Subject to the provisions of this regulation, the plates forming the identification mark shall be fixed on the motor vehicle or trailer in the position indicated in the particulars given in the application for the registration of the motor vehicle or trailer or subsequently furnished to the Licensing Authority or if he is not satisfied with the position so indicated, in such a position as he directs.

No motor vehicle shall be used on any road unless the plates forming the identification mark are clean and maintained in such condition as to render each letter or figure readily distinguishable.

Illumination of  
identification  
mark at night.

**10.** Whenever a motor vehicle or trailer is used on a public road at night a lamp shall be kept burning on the motor vehicle, or trailer so contrived as to illuminate by means of reflection, transparency or otherwise, and render easily distinguishable, every letter or figure on the identification plate fixed on the back of the motor vehicle or trailer.

In the application of this regulation to a motorcycle, the plate fixed on the front of the cycle may, if desired, be substituted for the plate fixed on the back of the cycle.

General  
identification  
marks for  
dealer.  
[197/1999].

**11.** (1) The Licensing Authority may assign to the holder of a dealer's general licence such number of general identification marks as he thinks fit. The marks shall be such as the Licensing Authority directs in each case—

Provided that—

- (a) they shall consist of two plates, each bearing some distinguishing letter or letters, and each having placed thereon or annexed thereto some distinguishing number; and
- (b) the colouring of the plates shall be different from that used for the plates forming the ordinary identification mark; and

(c) the lettering and numbering of the plates shall, so far as possible, be similar to those required in the case of the plates forming the ordinary identification mark.

(2) Every holder of a dealer's general licence to whom general identification marks have been assigned shall keep a Demonstration Book, and on every occasion on which such identification mark is used on a motor vehicle, he shall make or cause to be made in the Demonstration Book an immediate entry of the following particulars:

Date;

Identification mark;

Description of motor vehicle on which used;

Driver's name;

Time of departure from garage;

Time of return to garage;

Purpose for which the motor vehicle is used.

(3) The provisions of these Regulations which relate to the fixing and illumination of identification plates shall apply to the plates forming the general identification mark as they apply to the plates forming the ordinary identification mark.

(4) A motor vehicle used under the authority of a dealer's general licence shall not be used for any purposes other than those specified in section 35 of the Act and shall not be used for private or trade purposes either by the dealer or by any other person.

(5) Every holder of a dealers' general licence shall not operate under the authority of such licence between the hours of 8.00 p.m. and 5.00 a.m. without the express written permission of the Licensing Authority.

**12.** Every owner of a rented car shall keep a record book and on every occasion on which such car is hired out he shall make

Record Book.

or cause to be made in such record book an immediate entry of the following particulars:

- Date;
- Identification mark of rented car;
- Hirer's name and address;
- Time vehicle is hired out;
- Period for which vehicle is hired out;
- Time and date vehicle is returned.

**PART III**  
**LICENSING**

*(This Heading is deleted by Act No. 9 of 1997)*

**13. (Revoked by Act No. 9 of 1997).**

Weighing of  
vehicles.  
[71/1953  
6 of 1993  
9 of 1997  
197/1999].

**14.** The weighing of vehicles may be done at the weighbridges and portable scales maintained by the Licensing Authority, who is hereby authorised to charge therefor the following fees:

- (a) for the weighing of any vehicle for registration—twenty dollars;
- (b) for the weighing of any vehicle (with or without load) for other purposes—fifty cents per tonne or part thereof.

**15. } (Repealed by Act No. 9 of 1997).**  
**16. }**

Number of  
persons to be  
carried.  
[9 of 1997].

**17.** The owner of every public service vehicle shall keep distinctly painted on the outside of such vehicle the number of persons which, under the terms of its registration, may be carried in such vehicle. Such number shall be painted in conspicuous figures and shall ordinarily be placed in the following positions:

- (a) in the case of a taxi, on the outside of the right front door;
- (b) in the case of a motor omnibus, on the outside of the driver's seat.

PART IV

DRIVING AND CONDUCTOR'S PERMITS

18. Applications for the issue or renewal of a driving permit or a provisional permit shall be made in the form set out as Form 4 in the First Schedule.

Application for permit.  
[61/1979].  
Form 4.  
First Schedule.

19. A driving permit shall be in the form set out as Form 5A or Forms AA in the First Schedule and a provisional permit shall be in the form set out as Form 5B in that Schedule.

Form of driving permit or provisional permit.  
[61/1979  
120/2022].  
Form 5A.  
Forms 5AA.  
Form 5B.  
First Schedule.

20. Application for the grant or renewal of a driving permit may be received and dealt with at any time within one month before the date on which the renewal of the driving permit is to take effect.

Application for renewal prior to date of expiration.

20A. The Licensing Authority may receive and deal with applications for the renewal of a driving permit within six months before its date of expiration once it is proved to the Authority's satisfaction that the applicant will be absent from the country at the time of expiration of his permit.

Application for renewal where applicant will be absent from country.  
[197/1999].

21. (1) A person shall not act as a conductor of a motor omnibus unless he is the holder of a permit authorising him for the purpose; and no person shall employ any person who is not so authorised to act as such.

Conductor's permit.  
[15/1977  
197/1999  
9 of 2017].

(2) A person who desires to obtain the grant or renewal of a permit as a conductor of a motor omnibus shall apply to the Licensing Authority and shall furnish him with the particulars set out in the form in the First Schedule.

Form 6.  
First Schedule.

(3) Every applicant for a permit as a conductor of a motor omnibus shall satisfy the Licensing Authority that—

- (a) he is above the age of eighteen years and is physically and mentally fit;
- (b) he is of good character;
- (c) he has sufficient knowledge of the rules of the road and of the Motor Vehicles and Road Traffic Regulations.

(4) The Licensing Authority on being satisfied as above shall grant a permit to the applicant on payment of a prescribed fee.

(5) The permit shall be in such form as may be approved by the Licensing Authority and shall have attached thereto a photograph of the applicant, such photograph being supplied in duplicate by the applicant when applying for the permit. The permit shall commence on the day on which the same is granted and shall expire on 31st December next following.

(6) Every conductor shall, on being so required by any constable in uniform, produce his permit for examination so as to enable such constable to ascertain the name and address of the holder of the permit, the date of issue and the Police Officer or Transport Officer in uniform by whom it was issued, and if he fails to do so, he shall be liable under this regulation:

Provided that, if within forty-eight hours after the production of his permit was so required, the holder produces the permit in person at such Police Station as may be specified by him at the time its production was required, he shall not be convicted for such offence.

Badges for conductors. [197/1999].

**22.** On the grant of a permit to a driver or conductor of a motor omnibus a badge upon which there shall be marked the word “driver” or “conductor”, respectively, and the year of issue, shall be delivered to such person. Such badge shall be worn at all times when the driver or conductor is on duty in such a manner as to be easily seen.

Re-issue of lost or defaced permit or badge. [197/1999].

**23.** If a person to whom any permit or badge has been granted by the Licensing Authority satisfies the Licensing Authority that his permit or badge has been lost or defaced, the Licensing Authority shall on payment of a prescribed fee issue to him a duplicate of such permit or badge.

Cancellation or suspension of conductor's permit.

**24.** The Licensing Authority may cancel or suspend the permit of any conductor on any conviction or contravention of the Act or of these Regulations or on being satisfied that he is not a fit and proper person to hold a conductor's licence.

Cancellation or suspension of driver's permit. [197/1999].

**25.** (1) If it appears to the Transport Officer that there is reason to believe that any person who holds a driver's permit is

suffering from a disease or physical disability likely to cause the driving by him of a motor vehicle being a vehicle of any such class or description as he is authorised by the permit to drive, to be a source of danger to the public and, on enquiring into the matter, the Transport Officer is satisfied that the holder of the permit is suffering from such a disease or disability as aforesaid, then whether or not the holder of the permit so suffering as aforesaid has previously passed a driving test, the Transport Officer may, after giving to the holder of the permit notice of his intention to do so, revoke the permit, and the holder shall on receipt of such notice deliver the permit to the Transport Officer for cancellation.

(2) If any person is aggrieved by the revocation of a driving permit under this regulation, he may, after giving notice to the Transport Officer of his intention to do so, appeal to the Licensing Authority, and on any such appeal the Licensing Authority may confirm or revoke the decision of the Transport Officer.

(3) If it appears to the Licensing Authority that a driving permit has been obtained through misrepresentation or has been issued to a person under a wrong name or under an assumed name by which he is not generally known, the Licensing Authority may, after giving to the holder of the permit notice of his intention to do so, revoke the permit, and the holder shall, on receipt of such notice, deliver the permit to the Licensing Authority for cancellation.

**26.** Where a person is required by the Act or the Regulations to submit a medical certificate to the Transport Officer, that medical certificate shall be in the form set out as Form 12 in the First Schedule.

Medical certificate.  
[61/1979  
197/1999].  
Form 12.  
First Schedule.

#### PART V

#### INSPECTION OF MOTOR VEHICLES

**27.** (1) A registered owner of a public service vehicle, goods vehicle over 3 200 kg, rental car, omnibus, tractor or trailer shall produce his vehicle for inspection by a Transport Officer, annually

Inspection of motor vehicles, etc., and register.  
[197/1999  
34/2003  
9 of 2017  
96/2018  
99/2018].

L.R.O.

as the Licensing Authority may direct and shall, at the same time, furnish the Transport Officer with the following information:

- (a) the name of the manufacturer of the chassis;
- (b) model;
- (c) engine number and number of cylinders;
- (d) year of manufacture;
- (e) factory number of chassis, body number or VIN number;
- (f) maximum gross weight in kilogrammes;
- (g) type of body; and
- (h) such additional information as the Licensing Authority may from time to time direct.

(1A) A registered owner of a—

- (a) private motor vehicle or a motor cycle that is five years old or more; or
- (b) goods vehicle with a maximum gross weight of up to 3 200 kg that is two years old or more,

from the date of manufacture, shall produce his motor vehicle for inspection by an examiner biennially, at such premises designated for that purpose as the Licensing Authority may direct.

(2) Where an owner is unable to furnish the information required, the Transport Officer may describe such vehicle from his own observation.

(3) The examiner shall examine the motor vehicle or motorcycle, and if satisfied that it complies with the Act and these Regulations and on payment of the prescribed fee, shall issue a certificate containing such particulars as specified by the Licensing Authority.

First Schedule.

(4) The Transport Officer shall keep a register in the form in the First Schedule of all certificates granted by him.

(5) Every Transport Officer may call up for examination at any time any motor vehicle or trailer which he has reason to believe is not in a fit and proper state of repair or does not conform to the provisions of the Act and of these Regulations as regards construction, equipment and maintenance.

(6) The Licensing Authority may at any time by notice in writing require the registered owner of a motor vehicle or trailer to produce the same for its inspection, and such owner shall produce the same accordingly.

(7) The Licensing Authority may issue renewals of conductor's permits between 15th and 31st December, to become effective on the following 1st January.

(8) Where a Transport Officer has examined a motor vehicle or trailer under subregulation (5) and determines that it is not in a fit and proper state of repair he shall immediately report that fact to the Licensing Authority.

(9) Where a motor vehicle or trailer referred to in subregulation (8) was issued a certificate in accordance with subregulation (3) the person who issued the certificate would be liable where it is determined that the motor vehicle or trailer was defective at the time of inspection.

(10) A person who commits an offence under subregulation (9) is liable to a fine of fifty thousand dollars.

(11) A registered owner of a private motor vehicle or motorcycle, public service motor vehicle, rental car, goods vehicle, omnibus or trailer who fails to produce the vehicle for inspection or drives the vehicle without obtaining an inspection sticker and certificate in accordance with these Regulations is liable to a fine of five thousand dollars.

(12) A person who uses an inspection sticker or an inspection certificate, without authorisation, is liable to a fine of fifteen thousand dollars.

**\*PART VA**

**AUTHORISED EXAMINERS AND PREMISES**

**27A.** (1) Applications for authorisations of premises to be used for inspections of motor vehicles may be made by—

- (a) an individual proposing to carry out examinations otherwise than on behalf of any other person;

Applications  
for  
authorisations.  
[197/1999  
34/2003].

\*See Note on LN 197/1999 at page 3.

- (b) persons in partnership; or
- (c) a company,

hereinafter referred to as “proprietor”.

(1A) A person who desires to become an examiner shall apply to the Transport Commissioner.

(2) Every application shall be made on a form approved by the Licensing Authority and signed, where the application is made under paragraph (1)(a), by the individual making the application and, where the application is made under paragraph (1)(b) or (c) by a person duly authorised by the firm or company.

(3) In a case where the applicant proposes to carry out examinations at more than one place the Licensing Authority may require as many applications to be made as there are such places.

Authorisations.  
[197/1999  
34/2003  
9 of 2017].

**27B.** (1) When an application has been made in accordance with regulation 27A the Licensing Authority may, after making such investigations and carrying out such inspections as it may think fit, authorise the individual, persons in partnership or company by whom the application is made to have their premises used for the purpose of carrying out examinations of any class or classes of motor vehicles for a period of one year.

(2) The Licensing Authority may, at any time, if it so thinks fit, authorise in writing any person to carry out examinations notwithstanding that the requirements of regulation 27A have not been complied with.

(3) An application for the renewal of authorisation to carry out inspections may be made no more than one month before the expiration of the authorisation.

(4) A person who fails to apply for the renewal of authorisation prior to the expiration of the period of authorisation, shall submit forthwith to the Licensing Authority all—

- (a) unused inspection stickers;
- (b) unused inspection certificates;
- (c) check lists; and
- (d) monthly returns.

(5) A person who fails to comply with subregulation (4) is liable, on summary conviction, to a fine of five thousand dollars.

(6) A proprietor or examiner who conducts inspections of motor vehicles for the purpose of these Regulations without the required authorisation is liable to a fine of twenty thousand dollars.

(7) A person guilty of an offence under subregulation (6) shall, in addition to the penalty stipulated for the offence therein, be required to reimburse any fee paid by a motorist whose motor vehicle had been inspected by him during the period he was not authorised to inspect motor vehicles.

(8) A motorist whose vehicle was inspected by an unauthorised examiner shall, within thirty days of being informed by the Licensing Authority that his inspection was invalid, have his vehicle inspected in accordance with these Regulations.

**27C.** (1) Subject to these Regulations, every proprietor shall comply with such conditions set out in the document entitled “Responsibilities of a vehicle testing station Proprietor or Examiner” as indicated in the Sixth Schedule and also with the following conditions:

Conditions to be complied with by proprietors. [197/1999 34/2003]. Sixth Schedule.

- (a) the proprietor shall arrange in accordance with these Regulations examinations of motor vehicles of any such class as is specified in the authorisation of the proprietor and shall in all other respects comply with such of the provisions of these Regulations as apply to the proprietor;
- (b) the proprietor shall arrange for examinations to be carried out or to be personally supervised, and for test certificates to be signed, by persons who—
  - (i) are competent to act for such a purpose; and
  - (ii) if they are not the proprietor or, where the proprietor consists of persons in partnership with one of those persons, carry out the examination in a manner which is under the direct control of the proprietor, save that no

person shall be first authorised to carry out or supervise an examination or sign a test certificate unless he has successfully completed a course of instruction approved for the purpose by the Licensing Authority as set out in paragraph 4 of the Sixth Schedule;

Sixth Schedule.

- (c) the proprietor shall supply the Licensing Authority with the names of all persons who are from time to time authorised in pursuance of arrangements made in accordance with subparagraph (b) to carry out or personally supervise examinations at that station and in either case to sign test certificates; and such names shall be given within seven days after the date of any such authorisation;
- (d) the proprietor shall put up and keep exhibited inside the vehicle testing station of that proprietor in some conspicuous place so as to be legible to persons submitting vehicles for examination at that station—
  - (i) the authorisation in which that vehicle testing station is specified; and
  - (ii) a list of the names of the persons for the time being authorised to carry out or personally supervise examinations at that station and in either case to sign test certificates;
- (e) the proprietor shall put up and keep exhibited outside the vehicle testing station of that proprietor in a conspicuous place a sign of the size, colour and type shown in Part I of the Seventh Schedule and complying with the conditions specified in Part II of the Sixth Schedule;
- (f) the proprietor shall, after not less than three clear days' notice given to that proprietor by the Licensing Authority, make the vehicle testing station of that proprietor and the apparatus at that station with which examinations are carried out available for the purpose of an examination to be carried out by the Licensing Authority as

Seventh  
Schedule.

Sixth Schedule.

a result of an appeal which has been made against the refusal of a test certificate, whether by that or any other authorised proprietor or by an inspector appointed by the Licensing Authority;

- (g) the proprietor shall give notice to the Licensing Authority at the sub-office in which is situated the vehicle testing station of the proprietor—
- (i) in a case where the proprietor is the sole individual named in an authorisation, of his entering into any partnership with a view to carrying on a business which will comprise the carrying out of examinations at that station; and
  - (ii) in a case where the proprietor consists of persons in partnership, of any change in the constitution of the firm, and such notice shall be given not later than seven days after the occurrence of the entry into partnership or the change in the constitution, as the case may be.

(2) The Licensing Authority may give notice to a proprietor that in the opinion of the Licensing Authority a person should not carry out or supervise examinations, or sign test certificates, and on receipt of that notice the proprietor shall arrange that that person shall no longer carry out or supervise examinations or sign test certificates, as the case may require.

**27D.** (1) An authorisation of an individual as a proprietor terminates if he—

- (a) dies;
- (b) commits a criminal offence;
- (c) is adjudged bankrupt;
- (d) becomes mentally incapacitated; or
- (e) is found to be in breach of his duties under the Act.

Termination of  
authorisation.  
[197/1999].

(2) An authorisation as a proprietor of persons in partnership terminates if the firm is dissolved.

(3) An authorisation of a company as a proprietor terminates if in relation to the company—

- (a) a winding-up order is made;
- (b) a resolution for voluntary winding up is passed;
- (c) a receiver or manager of the body's undertaking is appointed; or
- (d) the taking of possession, by or on behalf of the holders of any debenture secured by a floating charge, or of any property of the body comprised in or subject to the charge occurs.

(4) Notwithstanding these Regulations, the person to whom is assigned responsibility for undertaking the activities specified in subregulation (3)(a) to (d) may apply for an authorisation in accordance with the provisions of regulation 27A to the Licensing Authority who may act in accordance with regulation 27B.

(5) A proprietor may at any time give notice to the Licensing Authority stating that after such date as may be specified in the notice that proprietor does not propose to continue to act as a proprietor under any of the authorisations of that proprietor or under such authorisation as may be specified in the notice, and any authorisation to which the said notice relates shall cease to have effect on the date so specified in relation to it.

(6) The Licensing Authority may terminate the authorisation of an individual as a proprietor or examiner on the following grounds:

- (a) the improper or fraudulent issue of a test certificate;
- (b) the deliberate failure to report the loss or theft of any certification relating to the inspection process to the Licensing Authority or the police;

- (c) the conviction of the proprietor or examiner under his control for any criminal offence that in the opinion of the Licensing Authority is likely to damage the integrity of the inspection programme;
- (d) the continued failure to comply with the provisions of these Regulations and any additional directives of the Licensing Authority.

(7) In pursuance of subsection (6), the Licensing Authority may at any time give to a proprietor a notice which states —

- (a) that from the date specified in the notice such one or other of the authorisations of the proprietor as specified in the notice shall, unless the notice is cancelled before that date, cease;
- (b) in a case where the date on which an authorisation ceases is less than twenty-one days from the date of the notice, that the Licensing Authority considers it necessary that the notice will have early effect;
- (c) that within twenty-one days from the date of the notice, the proprietor or any person acting on his behalf may appeal the decision of the Authority to the Trinidad Transport Board who shall determine whether the notice of termination shall be upheld or cancelled.

(8) An authorisation in respect of which a notice is given in accordance with subsection (6) shall, except as is provided in paragraph (6)(a), cease on the date specified in the notice as the date upon which the authorisation shall cease.

(9) The termination of an authorisation shall be effective from such time specified in the notice given under subsection (6) or for such period as is determined by the Trinidad Transport Board upon an appeal under subsection (6).

Forms and documents to be returned to Transport Commissioner. [197/1999 34/2003].

**27E.** (1) If an authorisation of a proprietor ceases to have effect, the former proprietor or, if appropriate, his authorised representative, shall send to the Licensing Authority such of the following documents as are then in the possession of the proprietor:

- (a) all unused forms of test certificates, inspection check lists, inspection stickers, monthly return forms and notices of refusal to issue a test certificate;
- (b) all copies of test certificates and notices of the refusal of test certificates;
- (c) all other records kept in accordance with regulation 27P; and
- (d) in the case of the authorisation of a proprietor ceasing to have effect, the document of authorisation,

save that where an authorisation of a proprietor ceases to have effect but some other authorisation of that proprietor continues in force the Licensing Authority may consent to the retention by that proprietor of all or any of the documents mentioned in paragraphs (a) to (d).

(2) On receipt by the Licensing Authority of any unused forms of test certificates sent to it in accordance with subregulation (1) it shall repay to the authorised proprietor or the authorised representatives of that proprietor, as the case may be, such amount as may have been paid to the Licensing Authority for the supply of the said forms.

(3) The Licensing Authority may in respect of unissued forms of test certificates which are returned to it as having been cancelled because they have been spoilt or defaced make an appropriate refund to the proprietor by whom the forms are so returned.

Application for examination. [197/1999 34/2003].

**27F.** (1) An application for an examination of a vehicle under these Regulations shall be made to the Transport Commissioner.

(2) An application for an examination (including a re-examination) of a vehicle in a class other than Class VI under these Regulations shall be made as indicated in the Table below —

(1)	(2)	(3)
Item No.	Person or body to whom application must be made	Manner in which Appointment must be made
1.	A proprietor	By arrangement following application made in writing or, during the normal working week, by telephone to, or in person at (whether by submitting the vehicle or not), the vehicle testing station where the applicant desires the vehicle to be examined.
2.	The Transport Commissioner	By arrangement following prior Application.

(3) Subject to the following provisions of these Regulations, proprietors shall ensure that:

- (a) where in accordance with the provisions of paragraph (2) an appointment is requested for the carrying out of an examination by the proprietor, an appointment is forthwith offered for the carrying out of the examination at the earliest time at which it is reasonably practicable for the examination to be carried out during the normal working week;
- (b) where in accordance with the provisions of paragraph (2) a vehicle is submitted for examination by the proprietor or, as the case may

be, the Licensing Authority without any appointment for the carrying out of the examination having been previously made, the applicant is informed either that the examination can be carried out forthwith or, if not, of the earliest time at which it is reasonably practicable for the examination to be carried out during the normal working week;

(c) except in so far as prevented by circumstances beyond the control of the proprietor or the Licensing Authority examinations are carried out in accordance with the appointments made or the information given in pursuance of the preceding provisions of this paragraph or at such other times as may be arranged between the applicant and the proprietor.

(4) On an appointment being made or a time being arranged for the carrying out of an examination in accordance with paragraph (3) the proprietor or the Licensing Authority as the case may be, shall record the hour and the date thereof and the name of the person by whom the application for the examination is made: Save that no such record needs to be made in a case where a vehicle is submitted for examination at a vehicle testing station of a proprietor, without any appointment for the carrying out of the examination having been previously made, and the examination is carried out forthwith.

(5) Any examiner and any inspector appointed by the Licensing Authority may carry out an examination of a motor vehicle in accordance with the provisions of these Regulations notwithstanding that the foregoing provisions of this regulation have not been complied with.

(6) Nothing in this regulation shall be taken as entitling an examiner to carry out an examination of a vehicle not being of a type included in the authorisation of the proprietor.

**27G.** A proprietor appointed shall not be under obligation to carry out an examination of a motor vehicle where—

- (a) on the submission of a vehicle for an examination the applicant does not, after being requested to do so, produce his driver's permit and certified copy of ownership of the vehicle and the serial number and the engine number given to the vehicle by its manufacturer and, if the manufacturer has also given the vehicle an identification number, that number also;
- (b) the vehicle or any part thereof or any of its equipment is so dirty as to make it unreasonably difficult for the examination to be carried out in accordance with the provisions of these Regulations;
- (c) the proprietor or Transport Officer is not able with the facilities and apparatus available to him at the place at which the examination would otherwise be carried out to complete the examination without the vehicle being driven and the vehicle is not when submitted for examination, either for want of fuel or oil or for any other reason, fit to be driven to such extent as may be necessary for the purposes of the carrying out of the examination;
- (d) before the carrying out of an examination of a motor vehicle, any things which are on the vehicle, and are not part of its equipment or accessories, are required by the proprietor or Transport Officer to be removed from the vehicle or to be secured in such manner as he may think necessary and the things are not removed or secured accordingly; and
- (e) in a case where the fee for the examination is payable in advance of the examination the examiner, or Transport Officer, or the Licensing Authority is not satisfied that the fee payable for the examination has been paid as required under these Regulations.

Requirements  
as to vehicles  
submitted for  
examination.  
[197/1999  
34/2003].

Conditions as  
to responsibility  
for damage to  
vehicles and  
third party.  
[197/1999].

**27H.** (1) Where a motor vehicle has been submitted for an examination to be carried out by a proprietor or the Licensing Authority, the proprietor or the Licensing Authority as the case may be, shall have the same responsibility for—

- (a) loss of or damage to the vehicle or its equipment or accessories occurring in connection with the carrying out of the examination during any period while the vehicle is, in connection with the carrying out of the examination, in the custody of the proprietor or the Licensing Authority; and
- (b) loss of or damage to any other property or personal injury, whether fatal or not, being loss, damage or injury arising out of the use of the vehicle in connection with the carrying out of the examination,

as would rest on a person who, having the same facilities for carrying out the examination as are available to the person who is to carry out the examination, had undertaken for payment to accept the custody of the vehicle and to carry out the same examination under a contract making no express provision with respect to the incidence of liability as between the parties thereto for any such loss, damage or injury.

(2) No person submitting a vehicle for an examination or having an interest in such a vehicle shall be requested or required by a proprietor or the Licensing Authority either directly or indirectly to accept any responsibility for, or to give any release or indemnity in respect of, any loss, damage or injury for which the proprietor or the Licensing Authority as the case may be is responsible under subregulation (1).

(3) Nothing in subregulation (1) or (2) shall preclude any person from being requested or required to accept any responsibility for, or to give a release or indemnity in respect of—

- (a) loss of or damage to a vehicle or its equipment or accessories occurring during any period while the vehicle is in the custody of a proprietor or the

Licensing Authority after the time when the vehicle is required to be removed from such custody in pursuance of the provisions of regulation 17(1); or

- (b) loss, damage or injury arising out of the carrying out by a proprietor, at the request of the person submitting the vehicle for an examination or of a person having an interest in the vehicle, of repairs to the vehicle or of repairs or replacements of its equipment or accessories.

(4) In this regulation—

- (a) references to an examination, in relation to a vehicle which, after the carrying out of an examination, remains in the custody of a proprietor, in order that a further examination of that vehicle may be carried out, include references to that further examination; and
- (b) references to a period while a vehicle is in the custody of the Licensing Authority include references to any period while a vehicle is, in connection with the carrying out of an examination of the vehicle by an inspector appointed by the Licensing Authority in the control or care of such an inspector.

**27I.** (1) Subject to the provisions of these Regulations, an examiner or the Licensing Authority shall, after an examination of a motor vehicle is completed and, subject to subregulation (2), on the same date as that on which the examination is completed—

- (a) where it is found on the examination that the prescribed statutory requirements are complied with in relation to the vehicle, issue a test certificate;
- (b) where it is not so found on the examination, issue a notice of the refusal of a test certificate; and
- (c) issue an inspection checklist on a form approved by the Licensing Authority.

Results of  
examinations.  
[197/1999  
34/2003].

(2) Where it is not practicable for a test certificate and inspection checklist to be issued on the same date as that on which the examination of the vehicle is completed the certificate and list may be issued within one day following that date, if between the time of the completion of the examination and the time of issue of the test certificate the vehicle has not been moved from the vehicle testing station at which the examination was carried out and the condition of the vehicle has not altered so as to result in the prescribed statutory requirements being no longer complied with in relation thereto, and where it is not practicable for a notice of the refusal of a test certificate and inspection checklist to be issued on the same date as that on which the examination of the vehicle is completed, the said notice and list may be issued within one day following that date.

(3) Subject to the provisions of these Regulations—

(a) every test certificate shall be on a form supplied by the Licensing Authority and shall contain—

- (i) particulars of the registration mark if any, exhibited on the vehicle or, if no such mark is exhibited, the chassis or serial number marked on the vehicle;
- (ii) the make of the vehicle, its approximate year of manufacture, and the mileage recorded by any odometer with which it is fitted;
- (iii) if the vehicle is a goods vehicle, its unladen weight specified in kilogrammes, or if it is not a goods vehicle, its horsepower or cylinder capacity;
- (iv) a statement that the vehicle has been found on examination to comply with the prescribed statutory requirements;
- (v) the number of the vehicle testing station where the examination occurred;
- (vi) the date of the issue of the test certificate and the date on which it will expire;

- (vii) if the date of the expiry of the certificate is more than twelve months after the date of its issue, the serial number of the certificate last issued in respect of the vehicle;
- (b) every notice of the refusal of a test certificate shall be on a form supplied by the Licensing Authority and shall contain—
  - (i) the information mentioned in subparagraph (a)(i), (ii) and (iii);
  - (ii) a statement that the application for a test certificate is refused, and the grounds of such refusal; and
  - (iii) the date on which the notification is issued and the number allotted by the Licensing Authority to the vehicle testing station at which it is issued.

(4) Every test certificate, notice of the refusal of a test certificate and inspection checklist issued in accordance with this regulation and regulation 27J shall, after the examination has been carried out, be signed—

- (a) where the examination is carried out at the premises of a proprietor, by the person who carried out the examination;
- (b) **(Deleted by LN 34/2003),**

and any signature on a test certificate or notice of refusal of a test certificate by a person in accordance with subparagraph (a) shall be accompanied by an embossment by a stamp of the proprietor or the Licensing Authority on whose behalf the certificate or notice is signed.

**27J.** (1) Where in the course of an examination of a vehicle by an examiner or the Transport Officer it is found that there are such defects in the construction or condition of the vehicle or its equipment or accessories that to carry out a braking test of the vehicle in the manner in which braking tests of such vehicles are carried out at the vehicle testing station at which the examination

Refusal of a test certificate where braking test cannot be carried out. [197/1999 34/2003].

is being carried out would be likely to cause danger to any person or damage to the vehicle or any other property, the proprietor or the Transport Officer shall not carry out the braking test but shall complete the rest of the examination in accordance with the provisions of these Regulations.

(2) Where in any such case as is mentioned in paragraph (1) a proprietor or the Licensing Authority does not carry out a braking test of a vehicle, he shall provide the applicant for the test with a notice on a form supplied by the Licensing Authority and stating—

- (a) that he could not safely carry out the braking test, and the reason therefor; and
- (b) the particulars mentioned in regulation 27I(3)(b)(ii) and (iii).

(3) In this regulation “braking test” means that part of the examination of that vehicle which is required or authorised to be carried out to ascertain whether the braking requirements are complied with.

Removal of  
vehicles  
submitted for  
examination.  
[197/1999].

**27K.** (1) Where a vehicle has been submitted for an examination at a vehicle testing station of a proprietor or the Licensing Authority, the person by whom the vehicle has been so submitted shall, save as may otherwise be permitted by the proprietor, or the Licensing Authority, as the case may be, cause it to be removed from the custody of the proprietor or the Licensing Authority, as the case may be—

- (a) where an appointment or arrangement has been made for the carrying out of the examination on a particular day and the examination has been completed on or before that day, before the end of the second day after that day; or
- (b) in any other case, before the end of the second day after the day on which the person submitting the vehicle for examination is given notice whether in writing or not—
  - (i) that the examination has been carried out; or

- (ii) in a case where the examination is not carried out by reason of any of the provisions of regulation 27G that he is to remove the vehicle from such custody.

(2) In this regulation references to an examination, in relation to a vehicle which, after the carrying out of an examination, remains in the custody of a proprietor, or the Licensing Authority in order that a further examination of that vehicle may be carried out, include references to that further examination.

**27L.** (1) A person to whom a notice of the refusal of a test certificate has been issued may appeal to the Licensing Authority and, save as may be otherwise permitted by the Licensing Authority any such appeal shall—

Appeal on refusal of a test certificate. [197/1999 34/2003].

- (a) be on a form approved by the Licensing Authority and contain the particulars required by that form; and
- (b) be sent to the office of the Licensing Authority within fourteen days from the date of the said notice.

(2) Within twenty-one days after the date on which the Licensing Authority receives a notice in accordance with subregulation (1) he shall send to the applicant, at his address given on the said notice, a notice stating—

- (a) the place at which the examination for the purposes of the appeal will occur; and
- (b) the time at which that examination will start.

(3) Save as may be otherwise permitted by the Licensing Authority, the examination mentioned in subregulation (2), shall not occur unless the applicant, or a person acting on his behalf—

- (a) submits the vehicle in respect of which the appeal is made to the place specified in the notice given by the Licensing Authority mentioned in subregulation (2), not later than the time specified in that notice as that at which the examination will start;

- (b) produces to the person appointed by the Licensing Authority to carry out the examination—
  - (i) the notice of the refusal of a test certificate issued as a result of the examination in connection with which the appeal is made; and
  - (ii) the registration document relating to the vehicle or other sufficient evidence of the date of its registration or date of manufacture; and
- (c) gives to that person such information as he may reasonably require in connection with the carrying out of the examination relating to any alteration made or repairs carried out or any accident or other event occurring, since the date of the said notice, which may have affected the vehicle or its equipment or accessories,

and the said officer shall not be required to carry out the examination unless such notice, registration document or other evidence is produced and such other information is given.

(4) When a person completes an examination under the provisions of this regulation he shall issue to the appellant—

- (a) either—
  - (i) a test certificate; or
  - (ii) a notice of the refusal of a test certificate stating the grounds thereof; and
- (b) an inspection checklist.

(5) Test certificates, notices of the refusal of a test certificate, and inspection checklists issued under this regulation—

- (a) shall, subject to such modifications as may be appropriate, be in the same form and contain the same particulars as are appropriate in the case of a test certificate, notice of the refusal of a test certificate and an inspection checklist issued under the provisions of these Regulations; and

(b) shall be signed on behalf of the Licensing Authority by the officer carrying out the examination for the purposes of the appeal.

(6) The provisions of this regulation do not apply where a notice of refusal of a test certificate has been issued following an examination for the purpose of an appeal.

**27M.** (1) Where arrangements are made for the carrying out at a vehicle testing station of a proprietor of an examination for the purposes of an appeal under regulation 27L an amount equal to one-half of the amount payable on that appeal shall be payable by the Licensing Authority to that proprietor in respect of the use of the station and apparatus thereat to be made available under the said arrangements.

Payment to proprietors at whose premises examinations on appeals are carried out. [197/1999 34/2003].

Except that the amount shall not be payable—

- (a) if the Licensing Authority gives the proprietor not less than one day's notice, whether in writing or otherwise, that the examination is not to take place in accordance with the said arrangements; or
- (b) if the proprietor does not make the testing station and the apparatus available to the Licensing Authority to his reasonable requirements.

(2) Where the Licensing Authority has issued a certificate after a successful appeal, the proprietor shall refund to the Authority the costs of such appeal.

**27N.** (1) The fee for an examination of a vehicle pursuant to an application made under regulation 27F is—

- (a) in the case of a motorcycle not having a side car attached to it, \$112.00; or
- (b) save as provided in paragraph (4) in the case of a privately owned light motor vehicle, \$300.00.

Fees for examination. [197/1999 34/2003 146/2017].

(2) Subject to the following provisions of this regulation, every fee prescribed by paragraph (1) shall be paid:

- (a) if the application is one to which item 1 in the Table to regulation 27F(1) applies, or is one, other

than an application for re-examination, to which item 2 in that Table applies, by a remittance accompanying the application;

- (b) if the application is one to which regulation 27F(2) applies or, in the case of an application for a re-examination, is one to which item 2 in the Table to regulation 27F(1) applies—
- (i) before the examination is carried out if the Licensing Authority or the proprietor by whom the examination is to be carried out so requires; and
  - (ii) after the examination is carried out in all other cases.

(3) Where, on an examination of a vehicle it is found that some or all of the prescribed statutory requirements are not complied with or where, in the circumstances mentioned in regulation 27J, a full examination of the braking system or systems of the vehicle is not carried out, then—

- (a) if the vehicle is left at the vehicle testing station at which the examination took place so that the defects which have been revealed can be repaired, no fee shall be payable in respect of any further examination carried out there on the completion of those repairs;
- (b) if the vehicle is removed from the vehicle testing station in consequence of a notice of refusal of a test certificate but within six weeks of the date of issue of the notice, it is brought to and left at that vehicle testing station for a second examination there shall be no fee payable in respect of that further examination; however—
- (i) if a vehicle is brought back to the same vehicle testing station for a third examination, a fee of \$200.00 shall be payable; and
  - (ii) if a vehicle is brought to another vehicle testing station the amount payable in subregulation (1) shall be payable.

(4) The fees prescribed by subregulations (1) and (3)(b), shall be payable notwithstanding that the vehicle is not submitted for examination in accordance with any such appointment or arrangement as is mentioned in regulation 27F:

Save that if the applicant for the examination has not less than one day before the time so appointed or arranged given the examining authority notice, whether in writing or otherwise, that the applicant does not propose to submit the vehicle for examination at the time so appointed or arranged, the application shall be treated for the purposes of this regulation as one in respect of which no fee is payable and any amount previously paid in respect of such a fee shall be repayable by the examining authority to the applicant unless another time is arranged for the carrying out of the examination.

(5) No fee shall be payable on an application for an examination of any vehicle in any case where in pursuance of any of the provisions of regulation 27G an authorised proprietor or the Licensing Authority does not carry out the examination, and any amount previously paid in any such case in respect of such a fee shall be repaid by the examining authority to the applicant.

(6) *(Deleted by LN 34/2003).*

**27O.** (1) The fees payable on an appeal made in accordance with regulation 27L are the same amount as the fees payable under regulation 27N.

Fees on  
appeals.  
[197/1999  
34/2003].

(2) Save as provided in paragraph (4), every fee prescribed by paragraph (1) as the fee payable on an appeal shall be paid at the same time as the appeal is made, and if that fee is not so paid the Licensing Authority shall not be obliged to deal with the appeal.

(3) After the completion of the examination for the purposes of the appeal the Licensing Authority may repay to the appellant, as he think fit, either the whole or a part of the fee paid on the appeal where it appears to him that there are substantial grounds for contesting the whole or part of the decision appealed against.

(4) A fee payable on an appeal in accordance with this section shall be payable notwithstanding that the vehicle is not submitted for examination in accordance with the provisions of regulation 27L:

Except that if the appellant has before the time fixed under regulation 27L for the carrying out of the examination given the Licensing Authority not less than two days' notice, whether in writing or otherwise, at the office of the traffic area at which his appeal was lodged or if he has been given such notice as is specified in regulation 27L(2), at the address specified in that notice as the address to which any communication relating to the appeal is to be sent, that the appellant does not propose to submit the vehicle for examination at that time, the appeal shall be treated for the purposes of this regulation as one in respect of which no fee is payable and any amount previously paid in respect of such a fee, shall be repaid by the Licensing Authority to the appellant unless another time is arranged for the carrying out of the examination.

Records to be kept and returns to be furnished by proprietors. [197/1999 34/2003].

**27P.** (1) Proprietors shall make, in duplicate, at each of their respective vehicle testing stations a record relating to all examinations carried out at that station, and that record shall be on a form supplied by the Licensing Authority and contain the particulars required by that form.

(2) On one of the first seven days of each month each authorised proprietor shall send to the Licensing Authority—

- (a) one copy of the record containing all the entries made therein relating to any examination as a result of which a test certificate or a notice of the refusal of a test certificate has been issued during the last preceding month; or
- (b) if no such certificate or notification has been issued, a notice to that effect.

(3) Subject to the following provisions of these Regulations, the other copy of the record shall be kept by the proprietor at the station at which the examinations to which it relates

are carried out for a period sufficient to ensure that upon the inspection at any time of that record the entries relating to any examination carried out within the last preceding eighteen months will be available for inspection.

**\*28.** (1) No person shall cause or permit a motor vehicle to be used on any public road, or shall drive or have charge of a motor vehicle when so used unless the conditions set out below are satisfied, namely—

Conditions of  
use of motor  
vehicles on  
public road.  
[197/1999  
8 of 2009].

(a) the motor vehicle, if it exceeds in weight unladen three hundred and sixty-five kilogrammes, shall be capable of being so worked that it may travel either forward or backwards;

Reversing.

(b) no motor vehicle or trailer shall exceed two and a half metres in overall width;

Width.

(c) (i) no motor vehicle constructed for the carriage of passengers only shall exceed ten metres in overall length, except trolley buses operated by the Port-of-Spain Corporation which may be of an overall length not exceeding ten metres. No other motor vehicle shall exceed nine metres in overall length;

Length.

(ii) no trailer other than a semi-trailer shall exceed seven metres in overall length;

(iii) no motor vehicle and semi-trailer attached shall exceed eleven metres in overall length;

(iv) no motor vehicle and trailer attached shall exceed fourteen metres in overall length:

Provided that the overall length of a motor vehicle and pole trailer carrying pipes may extend to fifteen and a half metres and of an agricultural tractor drawing two trailers to seventeen metres;

(d) except with the permission of the Licensing Authority, no motor vehicle or trailer shall have

Overhang.

\*See Note on Legal Notice No. 197/1999 on page 3.

a lateral overhang of more than one hundred and fifty-five millimetres or a longitudinal overhang which exceeds seven twenty-fourths ( $\frac{7}{24}$ ths) of the overall length of the vehicle, and when a trailer is connected to a motor vehicle by a bar or pipe, such bar or pipe shall not be allowed to project more than one metre beyond the rear of the trailer;

Distribution of weight.

- (e) (i) the total weight transmitted to the road surface by the wheels of any one axle of a motor vehicle or trailer shall not exceed ten tonnes;
- (ii) the combined gross weights of a motor vehicle and trailers shall not exceed the weight arrived at by the formula “eight thousand, one hundred and sixty-five kilogrammes + (L x 800)” where L equals the length in millimetres measured from the centre of the front wheels to the centre of the rearmost wheels of the vehicle or combination of vehicles;
- (iii) for the purposes of this paragraph two or more axles in line transversely and two or more axles the distance between the centre lines of which is less than one and three-tenths metres shall be deemed to be a single axle;

Brakes.

- (f) (i) every motor vehicle shall be equipped with an efficient braking system or efficient braking systems in either case having two means of operation so designed and constructed that one means of operation shall apply brakes to not less than all the wheels on each of two axles (or in the case of a motorcycle, one axle) of the motor vehicle and that

notwithstanding the failure of any part (other than a fixed member or a brake shoe anchor pin) through or by means of which the force necessary to apply the brakes is transmitted, there shall still be available for application by the driver to not less than half the number of the wheels of the vehicle (or in the case of a motorcycle or a motor vehicle having less than four wheels to not less than one wheel) brakes sufficient under the most adverse conditions to bring the vehicle to rest within a reasonable distance:

Provided that a motor vehicle manufactured prior to 1st January 1935, may be fitted with brakes capable of being applied to all the wheels of one axle but the braking system or systems of such motor vehicle shall have two independent means of operation as prescribed;

- (ii) all the brakes of a motor vehicle which are operated by one of the means of operation shall be capable of being applied by direct mechanical action without the intervention of any hydraulic, electric, pneumatic or any other device;
- (iii) one at least of the means of operation shall be capable of causing the brakes to be applied directly and not through the transmission gear to not less than half the number of the wheels of the vehicle;
- (iv) in the case of a steam driven vehicle which is not used as a public service vehicle for the conveyance of passengers for gain or hire, the engine of the vehicle shall be deemed to be an efficient braking system if the engine is capable of being reversed

and is incapable of being disconnected from any of the driving wheels except by the sustained effort of the driver;

- (v) every part of every braking system and of the means of operation thereof fitted to a motor vehicle or trailer, shall at all times, while the motor vehicle or trailer is used on a road, be maintained in good and efficient working order and shall be properly adjusted;

Trailers.

- (g) every trailer other than an agricultural trailer shall have an efficient braking system, approved by the Licensing Authority, the brakes of which are capable, when a trailer is being drawn, of being applied to at least two wheels. This paragraph shall not apply in the case of a pole trailer unladen or carrying an indivisible load;

Weight shown in certain cases.

- (h) every goods vehicle, motor omnibus or trailer shall have its tare and M.G.W. painted in white figures and letters not less than sixty-five millimetres in height upon a black ground on a conspicuous place on the right or off side of such vehicle to be specified by the Transport Officer. Such weights shall be expressed in kilogrammes;

Condition of vehicle.

- (i) the motor vehicle or trailer and all the fittings thereof shall be in such a condition as not to cause, or to be likely to cause, danger to any person on the motor vehicle or trailer or on any public road;

Silencers.

- (j) all motor vehicles shall be fitted with silencers to the satisfaction of the Licensing Authority. The use of cut-outs is forbidden throughout Trinidad and Tobago;

Cut-outs.

Unauthorised lights.

- (k) there shall not be affixed to the front of a motor vehicle any lighted lamp other than the headlights and side lights except with the approval in writing of the Licensing Authority, nor to the rear of a

motor vehicle or trailer any lighted lamp other than the red light prescribed by these Regulations except as permitted by paragraph (m)(iii) of this regulation;

- (l) there shall not be painted or otherwise affixed to the front or rear of a motor vehicle any combination of letters or figures resembling, or likely to obscure, or likely to be confused with, the letters and figures on the identification plate prescribed by these Regulations, and no letters or figures other than those on the identification plate shall be painted or affixed within five hundred millimetres of the identification plate;

Unauthorised  
letters and  
figures.

- (m) (i) every motor vehicle shall be equipped with a minimum of two lamps at the front of the vehicle, one on each side to the satisfaction of the Licensing Authority. When a motor vehicle is in motion on a road at night, the lamps at the front of the vehicle shall be lighted, and the rays from the lamps shall be of a type approved by the Licensing Authority and, if the vehicle is capable of proceeding at a speed greater than thirty kilometres per hour, of such intensity as to illuminate the road ahead for a distance of at least ninety-five metres or such greater distance as is sufficient to ensure the safety of the vehicle and the persons carried on the vehicle, and to indicate clearly the presence of the vehicle to approaching traffic. However, a motorcycle shall show one such lamp as aforesaid, but if a side-car is attached to the motorcycle, there shall be shown on that side of the side-car not adjacent to the motorcycle, an additional light of sufficient intensity to indicate the presence of the side-car from a reasonable distance to approaching traffic;

Lights.

- (ii) save as is contained in regulation 92, when stationary on a road at night every motor vehicle and every trailer not attached to a motor vehicle shall show two lights in front, one at each side, of sufficient intensity to indicate the presence of the motor vehicle or trailer from a reasonable distance to approaching traffic; but a motorcycle not attached to a side-car shall show one such light as aforesaid;
- (iii) save as provided elsewhere in these Regulations, every motor vehicle or trailer when on a road at night, whether in motion or stationary shall carry at least two lamps each showing a red light to the rear, of such intensity as to indicate clearly within a reasonable distance its presence on the road to traffic approaching from behind. There shall also be fitted lamps of such construction showing an uncoloured light of such intensity as to clearly illuminate the figures and numbers on the rear identification plate. Except as aforesaid, no other lamp shall be carried to the rear of the vehicle without the special written permission of the Licensing Authority. Where a trailer is attached to a tractor it will be sufficient if one such lamp as aforesaid is carried at the rear of the trailer only;
- (iv) no spot lights or other similar swivelling lamps shall be carried on any motor vehicle without the authority of the Licensing Authority, who may authorise such lights at his discretion and subject to such conditions as he may impose;
- (v) in addition to the foregoing provisions as to lamps to be carried, motor omnibuses shall also carry a lighted lamp on the

inside top of the hood showing a white light visible within a reasonable distance in all directions;

- (vi) in the case of motor omnibuses and goods vehicles, when either of the lamps referred to in subparagraph (i) hereof is placed in such a position that the distance of the centre of the lamp from the extreme outside point of the vehicle on its appropriate side exceeds three hundred millimetres, two additional lamps shall be fitted at the front of the said vehicle one on each side so that its centre shall not exceed the aforesaid distance of three hundred millimetres, and so as clearly to indicate the width of the vehicle to approaching traffic; the said lamps shall be focussed below the horizontal and shall exhibit a light of sufficient power only to indicate the width of the vehicle;

- (n) the exhaust pipe of a motor vehicle shall not be fixed in such a position that oil or any vaporisable or inflammable material is likely to be dropped upon it; the outlet thereof shall be placed far enough to the rear of the vehicle to prevent, as far as practicable, fumes from entering the vehicle.

(2) Notwithstanding subregulation (1)(m)(iv), the Licensing Authority shall not authorise an ambulance which is not registered under the Emergency Ambulance Services and Emergency Medical Personnel Act, to carry any spot lights, rotating lights, flashing lights or other similar swivelling lamps or lights.

Ch. 29:02.

(3) The Licensing Authority shall authorise in writing the carriage and use of any siren or warning instrument on any vehicle.

(4) Notwithstanding subregulation (3), the Licensing Authority shall not authorise an ambulance which is not registered under the Emergency Ambulance Services and Emergency Medical Personnel Act, to carry or use any siren or warning instrument.

Stationary  
motor  
vehicle.  
[197/1999  
6 of 2023].

**29.** Notwithstanding the provisions of regulation 28(m)(ii) and (iii), a motor vehicle when stationary at night within the boundaries of the City of Port-of-Spain, or the City of San Fernando, or the Boroughs of Arima, Chaguanas, Point Fortin, Diego Martin and Siparia need not show two lights in front and at least two lamps at the back if all the following conditions are complied with:

- (a) if such vehicle is drawn up as close as possible to its left or near side of the road;
- (b) if there is affixed or painted on the rear of the vehicle a reflective material or substance that is easily visible to approaching traffic.

Direction  
indicators.  
[197/1999].

**30.** (1) Every motor vehicle or trailer manufactured after 1960 shall be fitted with directional indicators on either side of the front and rear of such vehicle, and every indicator shall be so designed and fitted that—

- (a) it emits an amber light to the front and red or amber light to the rear;
- (b) it flashes at sixty to one hundred and twenty times a minute;
- (c) it shall not be more than one hundred and fifty-five millimetres measured horizontally from the outermost point of the side of the body immediately behind the driver's seat.

(2) Additional direction indicators may be fitted at the sides of the motor vehicle.

**31.** (1) *(Repealed by LN 197/1999).*

Left-hand  
driven  
vehicles.  
[197/1999].

(2) All motor vehicles with left-hand steering shall have a notice, affixed in a conspicuous position on the rear of the vehicle, bearing the words, in letters of not less than fifty millimetres in height, "Left-Hand Drive".

PART VI

INSPECTION OF VEHICLES OTHER  
THAN MOTOR VEHICLES

32. In this Part—

“carriage” includes any vehicle drawn by a horse or other animal and used or intended to be used for the conveyance of passengers;

“cart” means any hand cart, dray, van, wagon, truck, car, sledge, barrow or any other vehicle or machine howsoever drawn or propelled, and used or intended to be used for the carrying or conveyance of any goods, wares or other burden whatsoever, but does not include a motor vehicle.

Definition.  
[177/1956].

33. (1) Every cycle and every carriage on a road shall carry attached thereto a bell or other instrument approved by the Licensing Authority, capable of giving audible and sufficient warning of its approach or position.

Bells, etc.  
[177/1956  
39/1957].

(2) No person riding a cycle or driving a carriage on a road shall sound any bell or other instrument except for the purpose of giving reasonable and necessary warning of the approach or position of such cycle or carriage.

34. (1) At night—

(a) the person in charge of a carriage on a road shall carry attached thereto a lamp on each side of the carriage showing to the front a white light visible from a reasonable distance and a lamp on the right or off side of the carriage showing to the rear a red light visible from a reasonable distance;

(b) the person in charge of a cart on a road shall carry attached thereto on the right or off side and above the level thereof and of the load (if any) carried therein, a lamp showing a white light visible from a reasonable distance in all directions, and on the off rear end an unobscured and efficient reflector of a type approved by the Licensing Authority;

Lights on  
vehicles other  
than motor  
vehicles.  
[177/1956].

- (c) the person in charge of a cycle on a road shall carry attached thereto a lamp showing to the front a white light visible from a reasonable distance, and either—
- (i) a lighted lamp showing to the rear a red light, visible from a reasonable distance; or
  - (ii) an unobscured and efficient red reflector and in addition thereto an unobscured white surface which complies in all respects with the provisions of subregulation (2).

(2) Every white surface required to be exhibited under subregulation (1)(c) shall have an area of not less than five hundred and forty square millimetres, shall be kept clean and unobscured, and shall be so fixed that—

- (a) not less than half the area lies on the off-side of the centre line of the vehicle; and
- (b) not less than half the area is over two hundred and fifty-five millimetres above the ground.

For the purposes of this subregulation “white” includes the colour of polished aluminium or of chromium plating, or of a white reflective material.

Cycle brakes.  
[177/1956].

**35.** (1) No person shall ride, or cause, or permit any cycle to be ridden on any road unless he complies with the provisions of this regulation.

(2) Every cycle having any wheel of which the outside diameter (including any tyre when fully inflated) exceeds four hundred and fifty-five millimetres shall—

- (a) if it is so constructed that one or more of the wheels is incapable of rotating independently of the pedals, be equipped with a braking system operating on the front wheel or both front wheels, if it has two front wheels;

- (b) if it is not so constructed as aforesaid, be equipped with two independent braking systems, one of which operates on the front wheel, or both the front wheels, if it has two front wheels, and the other of which operates on the rear wheel, or one of the rear wheels, if it has two rear wheels:

Provided that in the case of a tricycle not constructed or adapted for the carriage of goods it shall be a sufficient compliance with this subregulation if the tricycle is equipped with two independent braking systems operating on the front wheel if it has two rear wheels, or on the rear wheel if it has two front wheels.

(3) Every cycle other than is specified in subregulation (2) shall be equipped with at least one braking system.

(4) All braking systems required by this regulation shall be efficient and shall be kept in proper working order.

(5) For the purposes of subregulation (4), a braking system shall be deemed not to be efficient if the brake operates directly on the tyre of any wheel.

**36.** Any constable in uniform is hereby empowered and shall be permitted by the owner or other person in charge of any cycle to test and inspect the brakes of the cycle, either on a road or on any premises where the cycle is. Such a test and inspection shall not be carried out on any premises where the cycle is, unless—

Constable may  
test cycle  
brakes.  
[177/1956].

- (a) the cycle has been involved in an accident;  
(b) the test and inspection are carried out within 48 hours of the accident; and  
(c) the owner of the premises consents thereto.

**37.** No parent, guardian or any other person having legal custody of a child or young person below the age of 16 years shall knowingly permit such child or young person to ride on a road a cycle which does not comply with any of the provisions of this Part.

Liability of  
parents and  
guardians.  
[177/1956].

PART VII

USE OF MOTOR VEHICLES

Rules to be observed by drivers. [177/1956 39/1957 197/1999 34/2003 6 of 2023]. Travelling backwards.

**38.** Every driver of a motor vehicle shall comply with the following rules:

Rule—

1. He shall not cause the motor vehicle to travel backwards for a greater distance or time than may be requisite for the safety or convenience of the occupants of the motor vehicle and of the passengers and other traffic on the road.

In the City of Port-of-Spain or the City of San Fernando or the Boroughs of Arima, Chaguanas, Point Fortin, Diego Martin and Siparia he shall not cause the motor vehicle to travel backwards at the junction of any roads or round a corner.

Full control and view to be maintained.

2. He shall not, when on the motor vehicle, be in such a position that he cannot have full control over the same, or that he cannot obtain a full view of the road and traffic ahead of the motor vehicle.

Brakes to be applied and engine stopped on quitting motor vehicle.

3. He shall before quitting the motor vehicle stop the engine and apply the brakes.

Restrictions as to sitting by driver.

4. In the case of goods vehicles and public service vehicles, not more than one person shall sit by the side of the driver unless such vehicle has been certified by a Transport Officer to have been constructed for the purpose of accommodating more than one person beside the driver.

No person shall sit on the right-hand side of the driver of any motor vehicle unless such motor vehicle has been constructed with a left-hand drive.

To keep to the left. [197/1999].

5. (1) He shall keep the motor vehicle on the left of the road unless prevented by some sufficient cause save where the

road is wide enough to accommodate three motor vehicles abreast and is marked off by the competent authority with a centre line, allowing vehicles occupying the centre to turn right.

(2) When meeting other vehicles he shall keep as close as possible to the left or near side of the road.

To keep on the left on meeting other traffic.

(3) When overtaking other vehicles he shall keep to the right or off side of such other vehicles.

Overtaking.

(4) When being overtaken by other vehicles he shall drive as close to the side of the road as possible so as to allow such other vehicles to pass, and in all cases he shall drive so as to give as much space as possible for the passing of other traffic and shall not speed abreast any vehicle when such vehicle is overtaking him.

Being overtaken.

(5) He shall not drive so as to overtake other traffic unless he has a clear and unobstructed view of the road ahead and he shall not overtake such other traffic unless he sees that the road ahead is clear for a sufficient distance to enable him to overtake and get back to his proper side before meeting any traffic coming from the opposite direction.

Cutting in.

(6) He shall not overtake other traffic when rounding a corner or when roads intersect or fork or where the road passes over the brow of a hill or over a humpbacked bridge or in any other circumstances where the driver cannot see sufficiently far ahead to overtake with safety.

Corners.

(7) He shall not cross a road or turn in a road or proceed from one road into another road, or drive from a place which is not a road into a road, or from a road into a place which is not a road unless he can do so without obstructing any other traffic on the road, and for this purpose he shall be held to be obstructing other traffic if he causes risk of accident thereto.

Crossings.

(8) When turning from one road into another road to the left he shall keep as close as possible to the left side of each road.

Turning to left.

Turning to right.

(9) When turning from one road into another road to the right he shall drive round the point of intersection of the two roads, and shall keep as close as possible to the left side of each road.

Stopping at corners.

(10) He shall not park his motor vehicle within a distance of nine metres from any corner or road intersection or nearer thereto than the distance indicated by the appropriate traffic sign, if any.

Drawing up alongside other motor vehicles.

(11) He shall not draw up the motor vehicle alongside any other motor vehicle nor shall he back the motor vehicle to the kerb stone of any foot-path or to the side of any road except for the purpose of turning.

Drawing up and standing alongside of fire hydrant.

(12) He shall not draw up his motor vehicle on any road or leave his motor vehicle standing on any road, within three metres of a fire hydrant.

(13) He shall not draw up his motor vehicle or permit it to remain on either side of any road, within three metres of the frontage of any Fire Brigade Station.

Obstruction.

6. He shall not negligently or wilfully prevent, hinder or interrupt the free passage of any vehicle, person or animal, and shall not allow such motor vehicle and any trailer drawn thereby to stand in such road so as to cause any unnecessary obstruction thereto.

Turnings and crossroads.

7. (1) He shall, when approaching turnings and crossroads or coming from any private road or place to any public road, slow down and make the appropriate traffic signal.

(2) He shall, when turning across traffic or turning to the right, slow down and make the appropriate traffic signal.

(3) He shall, when about to stop or slow down the vehicle on any public road, do so gradually and make the appropriate traffic signal.

(4) He shall, when quitting any place at which his vehicle has been stationary, make the appropriate signal.

8. He shall, when using a motor vehicle on any road, make the following traffic signals:

- (a) when about to slow down or stop, he shall extend the right arm and hand horizontally with the palm of the hand turned downwards and shall move the arm slowly and repeatedly downwards and upwards keeping it below the level of the shoulder;
- (b) when about to turn across traffic or to turn to the right he shall extend the right hand and arm horizontally, palm turned to the front or if the motor vehicle is fitted with direction indicators the driver shall signal with the indicators fitted on the offside of the vehicle;
- (c) when acknowledging a signal indicating that the driver of a vehicle proceeding in the same direction wishes to pass he shall extend the right arm and hand below the level of the shoulder and move them backwards and forwards;
- (d) when about to turn to the left he shall extend the right arm and rotate it from the shoulder in an anti-clockwise direction, or if the motor vehicle is fitted with direction indicators the driver shall signal with the indicator on the near side of the vehicle.

In no case shall the required traffic signal be given by the driver of a motor omnibus by means of a dummy arm unless the construction of the motor omnibus and the position of the driver's seat are such as to render it impossible for the driver to make such signal with his arm.

Further, in the case of a motor vehicle with left-hand steering, he shall, when using the vehicle on any road, make the following traffic signals:

- (i) when about to slow down or stop, he shall extend the left arm and hand

horizontally with the palm of the hand turned downwards and shall move the arm slowly and repeatedly downwards and upwards keeping it below the level of the shoulder;

- (ii) when about to turn across traffic or to turn to the right, he shall extend the left arm and rotate it from the shoulder in a clockwise direction or, if the motor vehicle is fitted with direction indicators, the driver shall signal with the indicator fitted to the offside of the vehicle;
- (iii) when about to turn to the left, he shall extend the left hand and arm horizontally, palm turned to the front, or if the motor vehicle is fitted with direction indicators, the driver shall signal with the indicator on the near side of the vehicle.

Traffic  
directions.  
[197/1999].

9. He shall conform to the rules of the road in regard to all kinds of traffic and shall comply with the lawful directions of any constable or Transport Officer charged with the regulation of traffic. He shall give the following signals for the purpose of indicating the direction in which he wishes to proceed:

- (a) when it is proposed to go straight ahead, raise the hand towards the shoulder, and move the forearm well forwards and then back in a vertical plane, making the movement sufficiently pronounced to be easily seen by the constable;
- (b) when about to turn to the left he shall extend the right arm and rotate it from the shoulder in an anti-clockwise direction;
- (c) when it is proposed to turn to the right, extend the right arm and hand with the palm turned to the front, and hold them rigid in a horizontal position straight out from the off side of the

vehicle. (This signal may be used in any circumstances when it may be necessary to convey the warning to traffic following behind that it is dangerous to overtake).

In the case of a motor vehicle with left-hand steering which is not fitted with direction indicators, he shall—

- (i) when about to turn to the left, extend the left arm and hand with the palm turned to the front and hold them rigid in a horizontal position straight out from the near side of the vehicle;
- (ii) when it is proposed to turn to the right, extend the left arm and rotate it from the shoulder in a clockwise direction.

10. Slow moving traffic shall keep as much to the left as possible at all times, and unladen vehicles shall give way to laden vehicles.

Slow moving traffic.

11. He shall, when about to stop the motor vehicle on any road, draw up as close as possible to the side of the road so as to allow a clear roadway for passing traffic; and shall remove the motor vehicle at the request of any constable when it is placed in such a position as to cause or be likely to cause obstruction on any road. He shall not draw up a vehicle or animal on a road in such manner as to obstruct a vehicular entrance to any premises. He shall not draw up the motor vehicle on a road in such a manner as to prevent or hinder the drivers of other vehicles complying with the directions of any traffic sign. He shall not leave the motor vehicle drawn up on any public road for an undue length of time having regard to all the circumstances of the case, including the amount of traffic which is at the time, or which might reasonably be expected to be, on the road.

Drawing up at side of road.

12. (1) He shall carry attached to the motor vehicle a horn or other instrument capable of giving audible and sufficient warning of its approach or position and he shall not himself sound or allow any other person to sound such

Horns, etc.

horn or other instrument except for the purpose of giving reasonable and necessary warning of the approach or position of the motor vehicle.

(2) He shall not himself sound or allow any other person to sound such horn or other instrument between the hours of 9.00 p.m. and 5.30 a.m. in any Municipal area, and also in any other area in Trinidad and Tobago in respect of which the Licensing Authority shall issue a prohibition notice to that effect in the *Gazette*.

(3) The Licensing Authority shall have power at any time to prohibit the use of any horn or instrument, the use of which for the purpose authorised in this regulation is likely to cause annoyance to the general public.

(4) Every horn or other instrument used for the purposes authorised shall either be of a kind which has been approved by the Licensing Authority generally as proper to be used on motor vehicles or which has been approved by him in a special case on the application of the owner of the motor vehicle.

(5) Any horn or other instrument which has been approved by the Licensing Authority for use on motor vehicles shall not be used on any other class of vehicles.

Sparks, smoke,  
vapour,  
lubricating oil.

13. He shall not permit sparks, smoke or visible vapour of any avoidable nature which would cause annoyance or danger to the public to come from any motor vehicle in his charge on or near any public road and shall take proper precautions to prevent the unnecessary discharge of lubricating oil on any road.

Stopping of  
motor vehicle  
at request of  
constable, or  
person in  
charge  
of horse.  
[197/1999].

14. He shall, on the request of any constable in uniform, or of any person having charge of a horse or any other animal, or if any such constable or Transport Officer or person shall put up his hand as a signal for that purpose, cause the motor vehicle to stop and to remain stationary so long as may be reasonably necessary.

15. He shall not carry on the motor vehicle or trailer, or being the owner of any motor vehicle or trailer shall not suffer or permit to be carried thereon, any tree, timber or iron beam or any lumber or other matter or thing projecting on either side of such motor vehicle or trailer more than three hundred millimetres beyond the plane of the wheels of such motor vehicle or trailer, or projecting more than one and a half metres in front or behind, or in such a manner as to obstruct, endanger or interfere with traffic, nor any load in such manner that the width of such load together with the overall width of the vehicle shall exceed two and a half metres. First Division Police Officers in charge of divisions may grant permits for the transport over any road, within stated hours, by a stated route and under stated conditions, of articles the transport of which would otherwise infringe the provisions of this regulation. Such permits shall be carried on the motor vehicle and shall be produced by the driver at the request of any Police Officer or Transport Officer. Any motor vehicle operating under the authority of any such permit shall carry by day a white flag and by night a red lamp affixed at the extreme rear end of the load.

Projections.  
[197/1999].

16. He shall not allow the motor vehicle to be overcrowded with persons.

Overcrowding.

17. He shall not allow any person to stand in or on a goods vehicle, agricultural trailer or trailer or on the tray or platform thereof whilst the vehicle is in motion, or to be carried in such a position that danger is caused or likely to be caused to such person or any other person, notwithstanding any permission granted by the Licensing Authority for the conveyance of persons.

Riding outside.  
[197/1999].

18. He shall not leave or permit to be left on any public road any motor vehicle which has broken down without taking the requisite steps to indicate its presence and position by lighting or otherwise to other persons using the road, and shall take immediate steps to have it removed as near to the left of the road as possible.

Motor vehicles  
unattended.

222      **Chap. 48:50**      *Motor Vehicles and Road Traffic*  
[Subsidiary]      *Motor Vehicles and Road Traffic Regulations*

Passage of Fire  
Brigade.  
[197/1999].

19. He shall on the approach of any engine or other apparatus of the Fire Services proceeding to and from a fire or suspected fire, or Police vehicles, Defence Force vehicles, Ambulances on emergency calls sounding their sirens or other warning instrument approved by the Licensing Authority, draw up close to the left-hand side of the road and stop, leaving the centre of the road for the passage of such vehicles, and he shall not stand abreast of any other vehicle.

Towing other  
vehicles.

20. He shall not, without the written permission of the Licensing Authority, tow anything except another motor vehicle in case of necessity, or a single registered trailer, except that in the case of an agricultural tractor he may tow not more than two trailers.

Length of tow  
rope.

21. No motor vehicle shall tow any other vehicle unless the tow rope, chain or draw bar be so adjusted that the distance separating the nearest two points of the two vehicles shall not, except in the case of a pole trailer, exceed five metres, and the tow rope, chain or draw bar is easily distinguishable by other users of the road.

Filling petrol  
into motor  
vehicles.  
[9 of 2017].

39. Any person who fills petrol into any receptacle on or adjacent to any motor vehicle or into the tank of a motor vehicle while the engine is running, or while any light, other than an electric light, is alight on the vehicle, and any person who smokes or lights a match or exposes a naked light in close proximity while petrol is being so filled is liable under these Regulations.

Reflecting  
mirror.  
[197/1999].

40. Every motor vehicle or trailer, other than a motorcycle, shall be equipped with the following:

- (a) a reflecting mirror, so constructed and fitted to the motor vehicle as to enable the driver of such motor vehicle to be or become aware of the presence in the rear thereof of any other vehicle, the driver of which is desirous of passing such motor vehicle;
- (b) a side mirror fitted on either side of the vehicle.

**41.** No part of the fittings, accessories or other equipment of any motor vehicle shall be so arranged or fixed as to be capable of being displaced by the motion of travel in a manner which causes the permitted dimensions of such vehicle to be exceeded.

Fittings and equipment to be properly adjusted.

**42.** In the case of goods vehicles the load shall be properly secured in such a manner as effectively to prevent the displacement of any portion thereof by the motion of travel. Any tarpaulin or other covering used for the protection of the load shall be adjusted so as to fit closely to the load or vehicle and shall be properly secured by ropes or other fastenings so as to prevent flapping or other displacement of such covering while the vehicle is in motion.

Load to be properly secured.

**43.** Any person driving or in charge of a motor vehicle which causes a loud noise to the annoyance or disturbance of any person is liable under these Regulations.

Noisy motor vehicles. [9 of 2017].

**44.** (1) All tyres of a motor vehicle or trailer shall at all times be maintained in such condition as to be free from any defect which might in any way cause damage to the surface of the road, or danger to persons in or on the vehicle or to any persons using the road. A person shall not be convicted under this regulation if he proves to the satisfaction of the Court that he could not by reasonable diligence have become aware of the defect.

Tyres.

(2) Any constable may require the driver of a motor vehicle, any of the tyres of which appears to the constable to be defective, to proceed to the nearest Police Station for examination and if the driver refuses to do so the motor vehicle may, at the expense and risk of the owner, be detained and taken to the said station or to a place for safe keeping until such request is complied with.

**45.** The glass windshield of any motor vehicle imported into Trinidad and Tobago after 31st December 1937 shall be made of safety glass.

Safety glass windshield.

**46.** An effective wiper shall be provided on the glass windshield of a motor vehicle.

Windshield wiper.

Traffic signal. **47.** No person, other than the driver, whilst travelling in a motor vehicle shall make any traffic signal.

Cyclists and pedestrians to comply with traffic control signal. [197/1999]. **48.** Whenever any constable or Transport Officer on point duty gives a traffic control signal to enable any vehicle to proceed in an indicated direction, no cyclist or pedestrian shall proceed across the current of traffic consequent upon such signal, or loiter in the roadway, or otherwise impede any vehicle from proceeding in the direction indicated.

Prohibition on playing of musical or noisy instruments in a motor vehicle. [9 of 2017]. **49.** A person who plays or operates any instrument, television, video, radio, tape deck, compact disc player, amplifier, equaliser, or speaker or other electrical or electronic equipment for the purpose of playing music or other electrically or electronically transmitted sounds, in a motor vehicle, to the annoyance of any resident or person in a street or of any person in a place to which the public is admitted or has access, without the written permission of the Licensing Authority, is liable under these Regulations and the driver of a motor vehicle who permits a person to contravene this regulation shall also be liable under these Regulations.

#### PART VIII

### USE OF VEHICLES OTHER THAN MOTOR VEHICLES AND OF ANIMALS

Application of certain provisions of Part VII to drivers and riders of vehicles other than motor vehicles, and of animals. [177/1956]. **50.** (1) The following provisions of Part VII of these Regulations shall apply in respect of the persons specified below in this regulation as they apply in respect of the drivers of motor vehicles, that is to say:

- (a) regulation 38 rule 5(1), (2), (5) to (9), and rules 6, 9, 11, 12, 15 and 20 shall apply in respect of any person driving, riding, drawing or propelling any vehicle other than a motor vehicle, and in respect of any person riding any animal on any road;
- (b) regulation 38 rule 1, rule 5(10) and (13), rule 17 and regulation 47 shall apply in respect of any

- person driving any vehicle drawn by an animal on any road;
- (c) regulation 38 rule 5(11) shall apply in respect of any person driving any vehicle drawn by an animal, in respect of any person drawing or propelling a cart, and in respect of any person riding an animal on any road;
  - (d) regulation 38 rule 2 and rule 7(1) to (4) shall apply in respect of any person driving any vehicle drawn by an animal, and in respect of any person riding a cycle or an animal on any road;
  - (e) regulation 38 rules 14 and 19, and regulations 42, 43 and 49 shall apply in respect of any person driving any vehicle drawn by an animal, and in respect of any person drawing or propelling a cart on any road;
  - (f) regulation 44 shall apply in respect of any person riding a cycle on any road,

and references in those provisions to motor vehicles, drivers and driving shall be construed accordingly.

(2) In this regulation “cart” means any hand cart, dray, van, wagon, truck, car, sledge, barrow and any other vehicle drawn or propelled by hand and used or intended to be used for the carrying of or conveyance of any goods, wares or other burden whatsoever, but does not include a motor vehicle.

**51.** The driver of any vehicle drawn by an animal and the rider of any cycle or animal on any road shall make the following traffic signals for the information of traffic or of any constable charged with the regulation of traffic:

Traffic signals.  
[177/1956].

- (a) when about to slow down or stop, he shall extend the right arm and hand horizontally with the palm of the hand turned downwards and shall move the arm slowly and repeatedly downwards and upwards keeping it below the level of the shoulder;

- (b) when about to turn across traffic or to turn to the right he shall extend the right hand and arm horizontally, palm turned to the front;
- (c) when acknowledging a signal indicating that the driver or rider of a vehicle or the rider of an animal proceeding in the same direction wishes to pass, he shall extend the right arm and hand below the level of the shoulder and move them backwards and forwards;
- (d) when about to turn to the left he shall extend the right arm and rotate it from the shoulder in an anti-clockwise direction;
- (e) when he proposes to go straight ahead, he shall raise the right hand towards the shoulder, and move the forearm well forwards and then back in a vertical plane, making the movement sufficiently pronounced to be easily seen.

Reckless driving.  
[177/1956  
39/1957].

**52.** No person shall drive, ride, draw or propel a vehicle other than a motor vehicle (in respect of which similar provision is made in section 71 of the Act) or ride any animal on any road recklessly, or at a speed or in a manner which is dangerous to the public, having regard to all the circumstances of the case, including the nature, condition and use of the road, and the amount of traffic which is actually at the time, or which might reasonably be expected to be on the road.

Careless driving.  
[177/1956  
39/1957].

**53.** No person shall drive, ride, draw or propel a vehicle other than a motor vehicle (in respect of which similar provision is made in section 71 of the Act) or ride any animal on any road without due care and attention or without reasonable consideration for other persons using the road.

Driving or riding while under influence of drink.  
[177/1956].

**54.** No person shall ride a cycle or drive a vehicle drawn by an animal on any road while he is under the influence of drink or a drug to such an extent as to be incapable of having proper control of the cycle or vehicle, as the case may be.

55. No person driving or in charge of any vehicle drawn by an animal on any road shall ride on any part of the vehicle or on the shafts thereof, or on the animal, without having and holding the reins, nor be at such distance from such vehicle as not to have complete control over the animal drawing the same.

Control of animal drawing vehicle.  
[177/1956].

56. (1) No person shall drive any cattle furiously on any road.

Control of cattle.  
[177/1956].

(2) No person shall load or unload or attempt to load or unload any cattle in or upon any road from any vehicle without sufficient assistance to prevent any of such cattle from breaking loose or from doing mischief.

(3) No person shall allow any cattle to break loose on any road.

(4) No person, not being a person employed by the owner thereof to drive the same, shall run after any animal on any road, or by shouting or making a noise or in any other manner frighten any cattle which may have broken loose on any road.

(5) No person shall by negligence or ill-usage in driving any cattle on any road cause injury to be done by such cattle.

(6) No person shall allow any cattle to wander, stray or be tethered on any road.

(7) In this regulation "cattle" includes sheep, goats and swine.

57. No person shall wilfully drive, ride, draw or propel a vehicle or ride an animal upon any footpath or pavement by the side of any road made or set apart for the use or accommodation of pedestrians.

Driving or riding on the footpath.  
[177/1956  
39/1957].

#### PART IX

### PUBLIC SERVICE VEHICLES— CONSTRUCTION AND MAINTENANCE

#### MOTOR OMNIBUSES

58. All bodies of motor omnibuses shall be of first-class workmanship and be securely bolted and braced. Where it is

Body and chassis.  
[197/1999].

necessary to extend the chassis frame the extension shall be inspected by a Transport Officer before the body is finally bolted and braced to the frame.

Curtains, screens, etc., to be properly fastened.

**59.** In the case of motor omnibuses, all curtains, or screens, or other devices for the protection of passengers from the weather shall be properly secured by straps or other fastenings so as to prevent flapping or other displacement of such curtains, or screens, or other devices while the vehicle is in motion.

Flooring. [197/1999].

**60.** Motor omnibuses shall be so constructed that the height of the main floor measured at a certain point shall not exceed seven hundred and sixty millimetres measured vertically from the surface of the road when the vehicle is fully loaded. The Inspecting Engineer shall be empowered to pass vehicles as motor omnibuses with a greater height of flooring (but not exceeding the floor height passed by the Ministry of Transport) if he is satisfied as to the stability and safety of the vehicle.

Fittings for motor omnibuses.

Every motor omnibus shall be fitted with—

- (a) a device by which a passenger may signal to the driver or conductor when required;
- (b) a speedometer;
- (c) a fire extinguisher.

All such fittings shall be subject to the approval of the Transport Officer, and shall be kept in working order.

Seats, corridor and safety exits.

**61. (1) Seats**—The width between the backs of seats when the seats are placed lengthwise shall be not less than one and a half metres. When the seats are placed behind each other, the space between the seats shall be unobstructed, and the distance between the backs of two seats so placed shall be not less than seven hundred millimetres, and when seats are placed crosswise facing each other the unimpeded space between them shall be not less than six hundred and fifty millimetres and the depth of each seat shall be not less than three hundred and fifty-five millimetres. At least four hundred millimetres of unimpeded

space shall be allowed for each passenger measured along each seat. The supports of all seats shall be firmly fixed in position.

(2) *Corridors*—Every motor omnibus registered after 31st December 1935, with seating accommodation for more than ten passengers, shall have an internal corridor of not less than four hundred millimetres in width, so arranged as to admit of easy access from within the vehicle to all seats; and no person shall stand on or move along the footboard outside any such vehicle whilst it is in motion.

(3) *Emergency Exit*—Every motor omnibus, the sides of which are enclosed, shall be fitted at the rear of the vehicle with an emergency door opening outwards, or other sufficient exit which shall be readily accessible from all seats; such door or exit shall be kept secured against use by any passenger, except in the case of an emergency.

**62.** No steps, footboard or running-board shall be allowed on the right or off side of any motor omnibus. Horizontal metal rails spaced not more than two hundred and thirty millimetres apart shall run from end to end and from floor level to six hundred millimetres above the level of the seats. Such rails shall not be moveable. Steps, etc.

**63.** Where running-boards, steps or footboards are fitted to the left or near side of the omnibus these must be fitted with a toeguard at least one hundred millimetres above the running-board, step or footboard and securely fastened to same. The length of this toeguard not to be less than one hundred and fifty millimetres longer than the outside diameter of the rear tyre and to be fitted equidistant from the centre of the rear wheel. Toeguards.

**64.** The driver's seat shall not be less than six hundred millimetres wide, and shall be so constructed that there is a space of at least three hundred millimetres on each side of the steering column, the space between the rear lower part of the steering wheel and the top of the driver's seat (inclusive of any cushion) Driver's seat.

shall not be less than one hundred and eighty millimetres. This seat shall slope backwards with a rake of one hundred and twenty-five millimetres per metre measured horizontally, the distance between the back part of the steering wheel and the back of the driver's seat shall not be less than three hundred and thirty millimetres. The driver's seat shall be divided off from that of the person sitting beside him on his left by a wooden partition not less than seven hundred and sixty millimetres high measured from the floor, and extending from the front of the front seat to the dashboard. In any case this partition is to have a clearance of not less than fifty millimetres to the left of the extreme left lever controlled by the driver.

Conductor's seat.

**65.** A fixed seat shall be provided for the conductor in every motor omnibus which shall not in any way interfere with the driver or passenger seating accommodation.

Motor omnibus to carry conductor.

**66.** Every motor omnibus with seating accommodation for more than ten passengers when in use on any road shall at all times carry a conductor in addition to a driver.

The owner and driver shall both be liable if the motor omnibus is used in contravention of this regulation.

Front protection.

**67.** Where passengers are carried on the left or near side of the driver's side, provision shall be made for a suitable guard, barrier or rail to be fitted so that, in the event of the omnibus stopping suddenly, the passenger or passengers cannot be thrown forward and out of the omnibus.

Internal height.

**68.** The internal height measured in the centre line of a motor omnibus from floor to lower edge of hoop sticks or other projections on the ceiling shall not be less than one and a half metres.

Driver's uniform and badge.

**69.** Every driver of a motor omnibus on a public road shall at all times—

- (a) wear his badge conspicuously and in such a manner that the whole of the writing thereon is distinctly legible;

- (b) be suitably attired and wear boots or shoes and a distinguishing cap and uniform to consist of a forage cap and a khaki or blue serge suit.

70. Every conductor of a motor omnibus on a public road shall comply with the following regulations:

Special regulations for motor bus conductors. [9 of 1997].

- (a) he shall not smoke after objection made by any passenger;
- (b) he shall not make use of any abusive language or insulting gestures;
- (c) he shall not call out to or otherwise importune any person to travel by any such omnibus;
- (d) he shall not ride otherwise than inside such omnibus except when collecting a fare;
- (e) he shall not permit more passengers than such omnibus is registered for to be carried in such omnibus. If there are passengers in excess, the conductor, or the driver when there is no conductor, shall at the request of any constable in uniform eject the passengers being carried in excess, and on his refusal so to do the constable may arrest the conductor or the driver, as the case may be, and take such steps as may be necessary to prevent the vehicle from proceeding on its journey with such excess passengers. Three children, if they are each under the age of fifteen years, shall be counted as two passengers for the purposes of this paragraph;
- (f) he shall not permit luggage other than personal luggage to be carried on such omnibus, "Personal Luggage" means wearing apparel and such other personal requisites as are usually carried by a traveller for his comfort and convenience, and includes the receptacle in which such articles are being conveyed;
- (g) he shall not be under the influence of drink or drugs during his employment;

- (h) he shall at all times wear his badge conspicuously in such a manner that the whole of the writing thereon is distinctly legible;
- (i) he shall at all times be suitably attired and wear boots or shoes and a distinguishing cap and uniform, to consist of a forage cap and a khaki or blue serge suit.

Motor bus to proceed direct to destination.

**71.** Every person driving a motor omnibus on a road shall after quitting any stand or garage with passengers proceed direct to the place or places included in the route of such omnibus, and shall not delay in so doing, and shall not return to the place of departure after leaving it, except on the return journey.

Entering or leaving bus.

**72.** The driver or conductor of a motor omnibus on any road shall not permit passengers to enter or leave such omnibus otherwise than by the rear or by the left or near side thereof.

Licensing Authority may delegate his powers.

**73.** All acts and things required by this Part to be done by the Licensing Authority may be done by any person or persons to whom he may from time to time delegate all or any of his powers.

Motor omnibuses registered prior to 1st January 1935.

**74.** The Licensing Authority in his discretion need not enforce any or all of these Regulations in respect of motor omnibuses that were registered as such prior to 1st January 1935.

Saving as to motor omnibus. [104/1982].

**75.** The Licensing Authority may in his discretion exempt motor omnibuses from any of the provisions of these Regulations having regard to—

- (a) the number of passengers or amount of load to be carried by such omnibuses;
- (b) the particular route on which or the type of service in which these omnibuses are to be used;
- (c) the safety and convenience of the public,

and in particular any such exemption may relate to the attendance of conductors.

**PUBLIC SERVICE VEHICLES**

**76.** The driver of a public service vehicle shall comply with the following regulations:

- (a) he shall not use a horn or other instrument for the purpose of calling passengers;
- (b) he shall not smoke after objection made by any passenger;
- (c) he shall not make use to any passenger of any abusive language or insulting gestures;
- (d) he shall not call out to or otherwise importune any person to travel by such public service vehicle;
- (e) he shall not loiter for the purpose of procuring passengers or otherwise;
- (f) he shall not, while waiting to pick up passengers, race his engine or make any loud or unnecessary noise with his engine;
- (g) he shall at the request of any passenger immediately stop in order to enable such passenger to alight; and when he is driving a motor omnibus in any area where stopping places are designated he shall not stop the motor omnibus to pick up or set down passengers elsewhere than at a stopping place marked as such by signboard or other device, nor shall he stop at any such stopping place unless passengers are waiting to be picked up or desire to alight; and when stopping to pick up or set down passengers he shall not cause any obstruction to the ordinary traffic on the road;
- (h) he shall not in the City of Port-of-Spain, the City of San Fernando and the Boroughs of Arima, Chaguanas, Point Fortin, Diego Martin, Siparia and in Princes Town draw up his omnibus on a road other than at a public stand appointed under the Act, except for the purpose of taking on or discharging passengers;

Special regulations for drivers of public service vehicles. [197/1999 6 of 2023].

- (i) he shall maintain the public service vehicle in a clean and sanitary condition;
- (j) he shall carry at least one spare inflated tyre fixed to the rim, spare wheel or other device, capable of being fitted to a wheel or axle.

Lost property.      **77.** The driver of a public service vehicle and the conductor of a motor omnibus wherein any property is left shall within twenty-four hours deposit such property, if not sooner claimed, at the police station nearest to his residence.

Touting.      **78.** No owner, driver or conductor of a public service vehicle plying for hire or any other person shall speak, make any noise or sound any instrument in order to attract the attention of the public or of a possible passenger; or by troublesome and frequent demands or by persistent following hold out the vehicle for hire to the public in such a manner as to constitute a nuisance, or act in any way so as to cause annoyance or inconvenience to any person.

Attire of taxi driver.      **79.** Every driver of a taxi on a public road shall be suitably attired.

Advertisement.      **80.** No owner or driver of a taxi shall place or suffer to be placed any printed, written or other matter by way of advertisement on any side window of the taxi.

Refusal to hire motor vehicle. [9 of 1997].      **81. (1)** The driver of a taxi shall not without reasonable excuse—

- (a) refuse to be hired when the taxi is standing on a public stand; or
- (b) refuse or neglect to drive the taxi to any accessible place indicated by the hirer: Provided that the whole journey, out and return, does not exceed thirty-five kilometres; or
- (c) refuse or neglect to carry such number of passengers, not exceeding the number specified in the motor vehicle registration, as he may be required to carry by the hirer; or

(d) refuse or neglect to accept with a hirer, a reasonable amount of luggage.

(2) Where a taxi is at the head of a rank at a public stand, the driver thereof shall, except for good and substantial cause, the proof whereof shall lie on him, remain standing by, or seated in, the taxi.

**82. (Repealed by LN 197/1999).**

**83. (Deleted by LN 34/2003).**

**84.** (1) The driver or conductor of any public service vehicle shall have the right to demand his fare of any person employing him or intending to travel in such vehicle, upon such person entering the vehicle or ordering him to wait or to drive further, and may refuse to convey any such person who does not comply with such demand, and may require any constable to remove from the vehicle any person so refusing to pay his fare.

Right to demand fare. [9 of 2017].

(2) Every driver or conductor of a public service vehicle who demands more than his legal fare, and every person who refuses or omits to pay his legal fare, and every person who resists or obstructs a constable in the performance of his duty under this regulation is liable to a fine not exceeding one hundred and fifty dollars.

#### PART X

#### \*RESTRICTIONS RELATING TO MOTOR OMNIBUSES

**85.** (1) A motor omnibus shall be permitted to ply for hire or reward only on the route or routes specified in the licence issued in respect thereof and shall not be permitted to ply for hire or reward on any route not specified therein without a special permit from a Transport Officer.

Omnibus routes. [197/1999 9 of 2017].

(2) If the driver of a motor omnibus uses any route other than that specified in the licence or permit for the purpose of plying for hire or reward, or of conveying any passenger, he is liable under these Regulations.

\*See Note on Application at page 4.

Routes to be specified on licence.

**86.** Every licence for a motor omnibus shall specify the route or routes and the limits thereof on or along which the vehicle is permitted to ply for hire or reward.

Special permits. [197/1999].

**87.** A Transport Officer may in his discretion issue occasional special permits to enable any motor omnibus to operate on special occasions on a route other than that for which the motor omnibus is licensed upon payment of a fee of twenty-five cents. Such permit shall be valid for the period therein stated but not exceeding seven days. The driver of the motor omnibus shall retain the permit in his possession and produce the same for inspection to any police officer on demand.

**88.** }  
to } *(Repealed by LN 197/1999).*  
**90.** }

Reconsideration of Licensing Authority's decision. [197/1999].

**91.** Any person aggrieved by any decision of the Licensing Authority or of a Transport Officer shall have the right to submit his application by way of appeal to the Trinidad Transport Board for further consideration.

#### PART XI

#### RULES FOR PARKING OF VEHICLES

No lighted lamps on motor vehicles required when in parking places and public stands. Third Schedule.

**92.** Any motor vehicle while waiting at the Parking Places specified in the Third Schedule shall be parked in the prescribed manner only, and at night when so parked shall not be required to carry any lighted lamps.

Rules for parking of taxis.

**93.** The taxis shall stand in line commencing five metres from the near kerb of any intersecting road unless otherwise provided and not less than one metre nor more than one and a half metres apart from each other; but where taxis are required or permitted to stand alongside each other they shall so stand not less than three hundred millimetres apart, and not less than one metre between the lines.

**94.** (1) Taxis standing for hire in stands shall leave such stands for the purpose of answering calls according to their priority of position in such stands and not otherwise.

Taxis leaving stands.

(2) On the departure of any taxi standing for hire in any such stands the taxi next in rear thereto shall move forward and occupy the vacant place, and in like manner other taxis in rear shall move forward in the line and occupy the vacant spaces immediately in front of them.

**95.** No vehicles other than taxis may park in Public Stands appointed for taxis.

Parking of taxis.

**96.** Motor omnibuses shall stand in line not less than one metre nor more than one and a half metres apart from each other.

Alignment of omnibuses.

**97.** On the departure of any motor omnibus standing for hire in any such stands the motor omnibus next in rear thereto shall move forward and occupy the vacant place and in like manner other motor omnibuses in rear shall move forward in line and occupy the vacant spaces immediately in front of them.

Omnibuses leaving stands.

**98.** (1) No vehicles other than motor omnibuses may park in Public Stands appointed for motor omnibuses.

Parking. [233/1951].

(2) No vehicle may park at any time on the Golden Grove Road, Arouca, within four hundred and sixty metres of any part of the Golden Grove Prison.

**99.** }  
**100.** } *(Repealed by LN 197/1999).*

## PART XII

### TRAFFIC LIGHT SIGNALS

**101.** The Minister may erect and maintain light signals for the control of vehicular traffic subject to the following provisions:

Licensing Authority to erect and maintain light signals. [83/1952 177/1956 197/1999].

(a) at least three lights shall be used facing the stream of traffic which the signal is intended to control, one red, one amber and one green;

- (b) the lamps showing the coloured lights aforesaid shall be arranged vertically, the lamp showing a red light being the uppermost and that showing a green light the lowermost;
- (c) each lamp shall be separately illuminated and the effective diameter of the lens thereof shall not be less than two hundred millimetres;
- (d) the height of the centre of the green lens from the carriageway shall be not less than one and a half metres;
- (e) the edges of the lenses shall not be more than three hundred and sixty millimetres apart;
- (f) }  
(g) } **(Deleted by LN 197/1999).**  
(h) }

Significance of  
light signals.  
[83/1952  
177/1956  
197/1999].

**102.** The significance of the light signals shall be as follows:

- (a) the red signal shall be taken as prohibiting vehicular traffic to proceed beyond the stop line on the carriageway provided in conjunction with the signals;
- (b) the amber signal in combination with the red signal shall be taken to denote an impending change in the indications given by the signal from red to green but shall not be taken to alter the prohibitory significance of the red signal;
- (c) the full green signal shall be taken to indicate that vehicular traffic may pass the signal and proceed with due regard to the safety of other users of the road and subject to the directions of any police constable or other duly authorised person who may be engaged in the regulation of traffic;
- (d) the full amber signal shown alone shall be taken as prohibiting vehicular traffic from proceeding beyond the stop line except in the case of any vehicle which when the signal first appears is so close to the said line that it cannot safely be stopped before passing the line;

- (e) the green arrow signal shall be taken to indicate that vehicular traffic may pass the signal and proceed with due regard to the safety of other users of the road in the direction indicated by the signal;
- (f) the combination of the red signal and the green arrow signal shall be taken to indicate that vehicular traffic is prohibited from proceeding beyond the stop sign on the carriageway provided in conjunction with the signal except in the case of the vehicles proceeding in the direction indicated by the green arrow signal;
- (g) the combination of the red signal and the amber arrow shall be taken to indicate that vehicular traffic is prohibited from proceeding beyond the stop sign on the carriageway provided in conjunction with the signals except when proceeding in the direction indicated by the arrow and that vehicles so proceeding shall give way to vehicles proceeding across their path;
- (h) the flashing red signal shall be taken to indicate that vehicular traffic may proceed with extreme caution beyond the stop line on the carriageway save that vehicles so proceeding shall give way to vehicles proceeding in pursuance of the flashing amber signal referred to in paragraph (i);
- (i) the flashing amber signal shall be taken to indicate that vehicular traffic may proceed with extreme caution beyond the stop line on the carriageway and such vehicles shall have the right of way over vehicular traffic proceeding in pursuance of the flashing red signal referred to at paragraph (h).

**103. (Repealed by LN 197/1999).**

**104. (1)** Light symbols may be used for the purpose of indicating to pedestrians the period during which it is desirable that they should or should not cross the carriageway.

“Cross” and  
“Don’t Cross”  
signals.  
[83/1952  
197/1999].

(2) Such light symbols shall be used in conjunction with those light symbols used for the control of vehicular traffic.

(3) Where such symbols are used in accordance with subregulations (1) and (2), they shall consist of—

- (a) a red standing man or red palm or the words “DON’T WALK” illuminated in red that shall be taken as indicating to pedestrians the period during which they should not cross the carriageway;
- (b) a flashing red standing man or the flashing words “DON’T WALK” illuminated in red that shall be taken as indicating to pedestrians that they should not begin to cross the carriageway;
- (c) a lunar and white walking man or the word “WALK” illuminated in lunar white that shall be taken to indicate to pedestrians the period during which they should cross the carriageway.

(4) *(Deleted by LN 197/1999).*

Inoperative traffic lights. [197/1999].

**104A.** Where traffic light signals under this Part are rendered inoperative or cease to function in the proper manner, motorists at any affected carriageway or intersection shall stop at the stop line and proceed only when safe to do so, exercising extreme caution at all times.

#### PART XIII

#### SPECIAL TRAFFIC DIRECTIONS

Traffic at dual carriageways. [39/1957 197/1999].

**105.** Wherever dual carriageways are provided along a public road all vehicles shall proceed along or keep to the left hand carriageway and shall keep to the left side of the left hand carriageway except when overtaking. Any vehicle entering such road from a side road or intersecting road will bear to the left and if desiring to cross the road or to pass on to the further carriageway it will keep to the left of the traffic island situated opposite to the junction from which it has emerged and forming part of the central strip dividing the dual carriageway.

**106.** At any place where a traffic roundabout has been constructed and where such roundabout is indicated by traffic signs all vehicles will proceed in a clockwise direction only.

Traffic at roundabouts. [39/1957].

**107.** Any person who is driving a motor vehicle or who is driving or is in control of any other vehicle shall slow down when coming from any private road or place to any public road or when approaching any crossroads or road junction, and if on his near side of the road along which he is proceeding there is erected a traffic sign bearing the legend “Stop at Major Road Ahead” or “Stop—Major Road Ahead”, he shall stop his vehicle before reaching, and as near as possible to, the stop line and shall not move his vehicle or cause his vehicle to move to the crossroads or road junction next ahead until he has satisfied himself that it is safe to do so and he shall then proceed slowly and give way to any traffic which may be on such crossroads or road junction.

Traffic at crossroads. [177/1956 39/1957].

**108. (Repealed by LN 197/1999).**

**109.** No person shall drive a lorry on High Street, in the City of San Fernando, between Quenca Street and the Library Corner except for the purpose of delivering or removing goods within that area.

Restricting lorries on part of High Street.

**110.** No cart or handcart shall be allowed to be backed into any pavement within the City of San Fernando. All such carts shall be drawn up parallel to the pavements for the purpose of loading or unloading any goods, articles or things, such loading to be done by means of skids. This regulation shall not apply to that part of High Street between Pointe-a-Pierre Road and Penitence Street.

Parking of vehicles in San Fernando. [26/1957].

**110A. (1)** In this regulation—  
“emergency response vehicle” means—

- (a) a Police Service vehicle;
- (b) a Fire Service vehicle; or
- (c) a vehicle authorised by law to use a siren and flashing roof lights to preempt the right of way of other vehicles based on the existence of an emergency situation;

Restriction on use of surveillance bays. [207/2011 9 of 2017].

“Minister” means the Minister to whom responsibility for transport is assigned;

“Police Service vehicle” includes any motor vehicle used by a police officer in the performance of his duties;

“surveillance bay” means that part of a road which is identified by a traffic sign as an area reserved for use by emergency response vehicles only.

(2) Subject to subregulation (3), no person shall stop, park or drive a motor vehicle on a surveillance bay.

(3) Subregulation (2) shall not apply to—

- (a) an emergency response vehicle;
- (b) a motor vehicle driven by a member of a protective service in the performance of his duties in an emergency situation;
- (c) a driver directed by a police officer in uniform where the use of the surveillance bay is necessary because of an emergency situation; or
- (d) such other motor vehicles as are authorised by the Minister.

(4) A person who contravenes subregulation (2) commits an offence and is liable to a fine of fifteen hundred dollars.

#### PART XIV

#### TAXIS

Taxi Drivers’  
licences.  
[4/1985  
197/1999].

Fourth  
Schedule.

**111.** (1) No person shall drive on any road a taxi registered as such unless he is the holder of a taxi driver’s licence issued to him by the Licensing Authority under these Regulations.

(2) Every application for a taxi driver’s licence shall be in the form set out in the Fourth Schedule and shall be signed by the applicant. Duplicate photographs of the applicant of passport size, a Police Certificate of Character and his driving permit issued under the Act shall accompany each application.

(3) The Licensing Authority may refuse a taxi driver’s licence to any applicant who fails to satisfy him that he is a fit

and proper person to hold such a licence. Before refusing a licence the Licensing Authority shall inform the applicant of the grounds for the proposed refusal and shall consider any representations made in writing in support of his application within seven days thereafter. If the applicant notifies the Licensing Authority that he wishes to make oral representations and/or adduce witnesses in support of his application the Licensing Authority shall hear such representations and/or witnesses or shall direct his Deputy or such other officer as he may appoint to hear and determine the matter in dispute. A taxi driver's licence may be refused notwithstanding that the applicant is the holder of a driving permit under the Act, but shall in no case be issued to an applicant who is not the holder of such a permit. The fee for a taxi driver's licence shall be ten dollars and shall be paid to the Licensing Authority before the licence is issued. The licence shall be in the form set out in the Fifth Schedule. A taxi driver's licence shall not be valid during any period in which the holder is not the holder of a driving permit under the Act, and is renewable every three years.

Fifth Schedule.

(4) On the grant of a taxi driver's licence there shall be issued to the holder thereof a badge on which is embossed the number of the licence and a photograph of the holder if the Licensing Authority provides such badge and/or photograph. Such badge shall be displayed therein at all times when any taxi of which such holder is the driver is standing, plying or being driven for hire, in such a manner as to be plainly and distinctly visible.

(5) An application for the grant or renewal of a taxi driver's licence and badge may be dealt with at any time within one month before the date on which the renewal of the taxi driver's licence and badge is to take effect.

**112.** If the holder of a taxi driver's licence shall satisfy the Licensing Authority that the licence issued to him has been lost, destroyed or defaced and that he has not wilfully effected or been a party to such loss, destruction or defacement, it shall be lawful for the Licensing Authority to issue a duplicate licence. If the former licence has been defaced it shall be surrendered to the Licensing Authority prior to the issue of a duplicate licence. The provisions

Duplicate  
licences.

of regulation 111(3) shall apply in relation to duplicate licences and every such duplicate licence shall be endorsed as such by the Licensing Authority. The Licensing Authority shall not refuse to issue a duplicate licence on the ground that the applicant is not a fit and proper person to hold a licence except on facts which have come to his knowledge since the original licence was issued.

Cancellation of  
Taxi Drivers'  
licences.

**113.** (1) The Licensing Authority may cancel any taxi driver's licence (which expression when hereinafter used shall include a duplicate licence) if the holder thereof is convicted of any offence against any of the regulations contained in this Part or if the Licensing Authority is satisfied that it was obtained by any false representation, or that the holder has ceased to be a fit and proper person to hold a taxi driver's licence. The Licensing Authority shall inform him of the substance of what is alleged against him and shall consider any explanations or representations made by him in writing in connection with such proposed cancellation within seven days thereafter. If the holder of the taxi driver's licence notifies the Licensing Authority that he wishes to make oral representation and/or adduce witnesses in connection with such proposed cancellation, the Licensing Authority shall hear such representations and/or witnesses or shall direct his Deputy or such other officer as he may appoint to hear and determine the matter in dispute. Cancellation of a taxi driver's licence may be effected by notice to the holder, and on such cancellation the holder shall forthwith surrender his licence and badge to the Licensing Authority. When the driving permit of any person has been cancelled under the Act it shall be in the discretion of the Licensing Authority to refuse any further taxi driver's licence to that person.

(2) The holder of a taxi driver's licence shall surrender such licence and the badge issued therewith forthwith to the Licensing Authority on ceasing to be the holder of a driving permit issued under the Act.

(3) Whenever a taxi driver's licence and badge are surrendered for any reason by the holder thereof, the Licensing Authority shall refund to such holder the sum of eighty cents.

**114.** It shall be the duty of the holder of a taxi driver's licence to notify the officer in charge of the police station nearest his residence of any change in the particulars set out in his licence and to produce such licence to such officer. If required to do so by the officer, he shall sign a statement containing full particulars of the information given and the officer shall forward the licence and the particulars to the Licensing Authority who may make any necessary correction on the licence and return the same to the holder.

Changes in particulars set out in taxi drivers' licences to be notified.

**115.** It shall be the duty of every taxi driver to take all proper steps to preserve his licence and badge against loss, destruction or defacement, and to produce the same on demand for inspection by any member of a police service or any Transport Officer constituted by law in Trinidad and Tobago or by any passenger in any taxi of which he may be the driver.

Production and inspection of taxi drivers' licences. [197/1999].

**116.** (1) Whenever any taxi is on a taxi stand, or is plying for hire or is under hire, no person (other than the driver) shall be in the taxi unless he is a bona fide passenger.

Only bona fide passengers to be in taxis plying for or on hire in taxi stands.

(2) In this regulation, the expression "bona fide passenger" means a person (hereinafter referred to as "the hirer") who, on his own account or jointly with others, has hired the taxi for reward and any other person who has entered the taxi with the permission of the hirer.

(3) If the preceding provisions of this regulation are contravened, the driver of the taxi and the persons who were in the taxi in contravention of those provisions shall be deemed to have contravened these Regulations; and in any prosecution for any such contravention any person (other than the driver) proved to have been in the taxi who cannot give a good account of himself shall be deemed not to be a bona fide passenger.

(4) If any person shall loiter on or about any taxi stand (whether in a vehicle or otherwise) and shall fail to give a good account of himself, he shall be deemed to have contravened these Regulations.

No person to loiter on or about a taxi stand.

Taxi not to be used for indecent or immoral purpose.

**117.** A driver of a taxi shall not himself use, or knowingly permit the taxi to be used by any other person for any indecent or immoral purpose.

**118.** *(Repealed by LN 197/1999).*

Exemption.

**119.** The provisions of regulation 111(1) and of regulation 116 shall not apply in relation to any taxi when it is on a road or is being driven on a road for the purpose of test by any garage keeper or any employee of any garage keeper and is not being used for hire or reward.

Rented cars not to be used as taxis.

**120.** No person shall cause or permit a rented car to ply for hire on any road.

#### PART XV

#### MISCELLANEOUS

Limitation of drivers' working hours.

**121.** (1) No person shall drive or cause or permit any person employed by him or subject to his orders to drive any hiring car or motor omnibus, or any goods vehicle, continuously for more than five-and-a-half hours without at least a half hour intervening during which the driver can obtain rest and refreshment, nor for an aggregate of more than ten hours in any twenty-four-hour period, nor for more than fifty-six hours in any one week, and provided that the driver shall have at least ten consecutive hours for rest during such twenty-four-hour period and shall not be employed in any capacity by his employer for more than eleven hours during such twenty-four-hour period.

(2) For the purposes of this regulation, a twenty-four-hour period shall be the period of time commencing from the hour at which the driver first took up work on any day to the corresponding hour on the following day.

Discretionary powers of Licensing Authority.

**122.** The Licensing Authority, in his discretion, need not enforce any or all of the provisions contained in regulations 58 to 65, 67 and 68 of these Regulations, and the provisions of regulation 70(e) and (f) of these Regulations shall have effect in

relation to any motor omnibus subject to any modification approved by the Licensing Authority and endorsed on the licence relating to such vehicle by such Authority or on his behalf.

**123.** (1) No person shall, except for the purpose of taking up or setting down passengers, allow a vehicle to remain stationary at any time between the hours of 7.30 a.m. and 9.00 a.m. or between the hours of 4.00 p.m. and 5.30 p.m. on any day at any place on the following sections of road:

Eastern Main  
Road  
Regulations.  
[200/1951  
9 of 2017].

- (a) that portion of South Quay and the Eastern Main Road which lies between Piccadilly Street in the City of Port-of-Spain and Bushe Street at San Juan; and
- (b) that portion of the Eastern Main Road which lies between St. John's Road and Freeling Street at Tunapuna.

(2) No goods shall be loaded or unloaded from any vehicle at any place on the aforesaid sections of road at any time between the aforesaid hours; and the driver or person in charge of any vehicle on or from which any goods are loaded or unloaded in contravention of this regulation and any person assisting in such loading or unloading shall each be liable under these regulations.

(3) No person shall drive an animal-drawn cart in an easterly direction along that section of the Eastern Main Road which lies between its junctions with the Old St. Joseph Road on the West and Leon Street on the East at any time between the aforesaid hours.

**124.** No person shall, except for the purpose of taking up or setting down passengers, allow a vehicle, other than a vehicle belonging to the Government of the United States, to remain stationary at any time at any place on the following sections of roads:

Eastern Main  
Road,  
Demerara  
Road, Aripo  
and Heights of  
Guanapo Roads.

- (a) that portion of the Eastern Main Road which lies between the thirty-kilometre and the thirty-five-kilometre marks;
- (b) the whole of Demerara Road;

- (c) that portion of the Aripo Road which lies between the zero and three-kilometre marks;
- (d) that portion of the Heights of Guanapo Road which lies between the zero and four-kilometre marks.

Western Main Road.

**125.** (1) Between the hours of 7.00 a.m. and 9.00 a.m. and 4.00 p.m. and 6.00 p.m. daily no vehicle shall be drawn up and parked on the north side of the Western Main Road between Mucurapo Road on the East and the Diego Martin Road on the West.

(2) Between the aforesaid hours waiting will be permitted on the south side of the Western Main Road only.

Chaguanas Road.  
[43/1958].

**126.** No person shall, except for the purpose of taking up or setting down passengers, allow a vehicle to remain stationary at any time on that portion of the Chaguanas Road, between Endeavour Road on the East and the Caroni-Savannah Road on the West.

Liability for contravention or failure to comply with Regulations.  
[177/1956].


**127.** Unless otherwise specifically provided, no person shall use or cause or permit to be used on any road a vehicle or trailer which does not comply with the Regulations—

- (a) applicable to the class or description of vehicles to which the vehicle belongs as to the construction, weight and equipment thereof; or
- (b) as to the use or maintenance of any such vehicle or trailer or part thereof in a specified condition.

\_\_\_\_\_

**FIRST SCHEDULE**  
REPUBLIC OF TRINIDAD AND TOBAGO  
**FORM 1**

[11 of 1963  
61/1979  
9 of 2017  
311/2020  
120/2022].  
Regulation 4.

  
Government of the Republic of Trinidad and Tobago  
**FORM OF PARTICULARS TO BE GIVEN BY APPLICANT  
FOR REGISTRATION OF MOTOR VEHICLE**  
Motor Vehicles and Road Traffic Act, Chap. 48:50

Form 1

Please print information in **BLOCK LETTERS**

**1. Applicant Name:** \_\_\_\_\_  
(Surname, First Name, Middle Name)

**Company Name:** \_\_\_\_\_ **Company/Business Reg. No.:** \_\_\_\_\_

**2. Date of Birth:** \_\_\_\_\_ **Nationality:** \_\_\_\_\_  
(DD/MM/YYYY)

**I.D.**  / **D.P.**  / **Passport**  **No.:** \_\_\_\_\_ **Sex:**  Male  Female

**3. Contact Information:**  
**Address (Street):** \_\_\_\_\_  
**Address (City):** \_\_\_\_\_  
**Mailing Address (if different from above) (Street):** \_\_\_\_\_  
**Address (City):** \_\_\_\_\_  
**Telephone:** ( ) \_\_\_\_\_ **Email:** \_\_\_\_\_

**4. Description of Motor Vehicle:**  
**(a) Chassis No./VIN:** \_\_\_\_\_  
**(b) Left Hand Drive?** Yes  No  **(c) Make:** \_\_\_\_\_ **(d) Model:** \_\_\_\_\_  
**(e) Colour:** \_\_\_\_\_ **(f) Year of manufacture:** \_\_\_\_\_  
**(g) Body Type:**  
 Sedan  Hatchback  SUV  Motorcycle  Pickup Truck  Truck  Tractor  
 Station Wagon  Goods Vehicle  Motor Omnibus  Panel Van  Glass Van  
 Freight Passenger Vehicle  Ambulance  Trailer  Tow Truck  
 Other: \_\_\_\_\_  
**(h) Country of Origin:** \_\_\_\_\_ **(i) Mileage:** \_\_\_\_\_  Km  Miles  
**(j) Maximum Seating:** \_\_\_\_\_ **(k) Seating to the left/right of driver:** \_\_\_\_\_ **(l) No. of Doors:** \_\_\_\_\_  
**(m) Weight (Tare):** \_\_\_\_\_ k.g. **(n) M.G.W.:** \_\_\_\_\_ k.g. **(o) Brakes:**  HYD  Air  Other  
**(p) Length x Width:** \_\_\_\_\_ **(q) No. of Wheels:** \_\_\_\_\_ **(r) No. Standing Persons (Buses Only):** \_\_\_\_\_  
**Additional information:** \_\_\_\_\_

**5. Engine and Transmission Details:**  
**Engine Number:** \_\_\_\_\_ **Engine size:** \_\_\_\_\_ cc  
**Number of Cylinders:** \_\_\_\_\_ **Horsepower:** \_\_\_\_\_  New  Used  Rebuilt  
**Transmission:**  Automatic  Manual  
**Fuel:**  Gas  Diesel  Hybrid  Electric  Other: \_\_\_\_\_

[1] [OVER]

250 **Chap. 48:50** *Motor Vehicles and Road Traffic*  
[Subsidiary] *Motor Vehicles and Road Traffic Regulations*

**FORM 1—Continued**

**6. Insurance Details:**  
Insurance Company Name: \_\_\_\_\_  
Certificate/Policy No.: \_\_\_\_\_ Date: \_\_\_\_\_  
(DD/MM/YYYY)  
Effective Date: \_\_\_\_\_ Expiry Date: \_\_\_\_\_  
(DD/MM/YYYY) (DD/MM/YYYY)

**7. Intended Use -**  
 (a) Private motor car  (b) Hiring car or Taxi  (c) Motor omnibus  (d) Motor lorry  
 (e) Goods vehicle  (f) Freight Passenger vehicle  (g) Motorcycle  (h) Trailer  
 (i) Tractor  (j) Other: \_\_\_\_\_

**8. Particulars as to the position on the car in which it is proposed to place the plates forming the identification mark:** \_\_\_\_\_

**Declaration of Applicant:**  
I, \_\_\_\_\_ declare that the information provided is true and correct and hereby apply for the registration of the vehicle specified above.  
\_\_\_\_\_  
Signature Date (DD/MM/YYYY)

N.B: (1) It is an offence under section 94 of the Motor Vehicles and Road Traffic Act, Chap. 48:50 to give any particulars which are false or incorrect and you will be liable to prosecution if you do so.  
(2) Application must be supported by documents as proof of address such as a recent Utility Bill or in the case of a rental, a copy of the Lease/Rental Agreement for the rental premises identified and bearing the name of the Applicant. If the utility bill or Lease/Rental Agreement is not in the Applicant's name, a letter from the owner confirming the Applicant's residence and copy of the owner's national identification (ID) MUST be submitted.  
(3) If Applicant is a Company, the application must be supported by Company validation documents such as a copy of the company/business registration certificates and/or Notice of Directors.

**For Official Use only:**

[2]

*Motor Vehicles and Road Traffic* **Chap. 48:50**  
*Motor Vehicles and Road Traffic Regulations*

251

[Subsidiary]

**FORM 4**

Regulation 18.  
[9 of 2017  
311/2020].

 Government of the Republic of Trinidad and Tobago <b>APPLICATION FOR DRIVING PERMIT(S)/ENDORSEMENT(S)</b> Motor Vehicles and Road Traffic Act, Chap. 48:50 Regulation 18			
FORM 4			
<b>Print information in BLOCK LETTERS</b>			
1. Type of permit(s)/endorsement(s) applied for—			
(i) Transaction:			
<input type="checkbox"/> First Issue	<input type="checkbox"/> Renewal	<input type="checkbox"/> Duplicate	<input type="checkbox"/> Provisional <input type="checkbox"/> Endorsement
(ii) Classification:			
<input type="checkbox"/> Motorcycle	<input type="checkbox"/> Light Motor Vehicle	<input type="checkbox"/> Heavy Motor Vehicle	<input type="checkbox"/> Extra Heavy Motor Vehicle
<input type="checkbox"/> Omnibus	<input type="checkbox"/> Tractor Wheel/Truck	<input type="checkbox"/> Other:	
(iii) Use:			
<input type="checkbox"/> Hiring Car/Taxi	<input type="checkbox"/> Commercial	<input type="checkbox"/> Private	
2. Name of Applicant:			3. Sex:
Surname	First Name	Middle Name	Maiden Name (if any)
			<input type="checkbox"/> Male <input type="checkbox"/> Female
4. Place of Birth:	5. Date of Birth:	6. Nationality:	
	(DD/MM/YYYY)		
7. Contact Information: Residential Address in Trinidad and Tobago:		8. Contact Information if different from (7): Residential Address:	
Street		Street	
City		City	
E-mail		E-mail	
Telephone ( ) -		Telephone ( ) -	
9. (i) Are you the holder of a driving permit issued in Trinidad and Tobago?		(ii) If "yes" to (i) or (ii) state number and date of Issue below:	
<input type="checkbox"/> Yes <input type="checkbox"/> No		Number	Date (DD/MM/YYYY)
(iii) Have you previously been the holder of a Driving Permit issued in Trinidad and Tobago?		(iv) Class of vehicle authorised to drive:	
<input type="checkbox"/> Yes <input type="checkbox"/> No			
10. Are you the holder of a driving permit/licence held elsewhere than in Trinidad and Tobago? <input type="checkbox"/> Yes <input type="checkbox"/> No			
11. Give particulars of any endorsement(s) on any driving permit/licence which you held or now hold. <input type="checkbox"/> Yes <input type="checkbox"/> No			
12. Have you at any time been disqualified from obtaining a driving permit? If "yes" give particulars: <input type="checkbox"/> Yes <input type="checkbox"/> No			
13. Are your vision, hearing and bodily and mental fitness such as to qualify you for issue of a driving permit? <input type="checkbox"/> Yes <input type="checkbox"/> No			
14. I, _____, declare that the information provided above is true and correct.			
_____ Signature of Applicant		Date: _____ (DD/MM/YYYY)	

**FORM 4—Continued**

15. DECLARATION IN RESPECT OF APPLICATION FOR DUPLICATE DRIVER'S PERMIT, TAXI DRIVER'S LICENCE/BADGE, MOTOR VEHICLE LICENCE, CONDUCTOR'S PERMIT

I, .....

of .....

in the Republic of Trinidad and Tobago do solemnly and sincerely declare as follows:

1. I am the holder of ..... No. ....  
which was issued/renewed for the year 20 .....

2. The said ..... No. ....  
was lost or stolen, on or about the ..... day of ..... 20 .....

and although I have made a diligent search for the said .....  
I have been unable to find same.

3. The said ..... No. ....  
was destroyed on or about the ..... day of ..... 20 .....

And I make this declaration conscientiously believing the same to be true and according to the **Statutory Declarations Act Chap. 7:04** and I am aware that if there is any statement in this declaration which is false in fact, which I know or believe to be false or do not believe to be true I am liable to fine and imprisonment.

Signature of Declarant: .....

Declared at .....  
this ..... day of ..... 20 .....

Before me,  
.....  
*Commissioner of Affidavits*

---

16. For Official Use

---

**INSTRUCTIONS TO APPLICANTS**

1. All applicants must complete questions 1-14.

2. Applicants applying for a "DUPLICATE" Permit must complete questions 1-15.

3. Tick boxes where applicable.


4. Question 1 (i) (a) "First Issue"—application for the first time for a permit for a particular class of vehicle.  
(b) "Provisional"—application for a permit to learn to drive a vehicle of a particular class. Such permit is valid for one year only.

(ii) (a) "Motor Vehicle/Light"—includes any motor vehicle (e.g., motor car, station wagon, pick-up van, etc.) whose tare weight does not exceed 2,270 kilogrammes or whose m.g.w. does not exceed 2,950 kilogrammes.  
(b) "Motor Vehicle/Heavy"—includes any motor vehicle whose m.g.w. exceeds 2,950 kilogrammes but does not exceed 15,240 kilogrammes.  
(c) "Motor Vehicle/Extra Heavy"—includes any motor vehicle whose m.g.w. exceeds 15,000 kilogrammes.  
(d) "Other"—includes application for a permit for a vehicle not listed at 1(ii) e.g., road roller, cranes, etc.

(iii) (a) "Private use"—includes use of a rented vehicle or use of any other vehicle for non-commercial purposes.  
(b) "Commercial use"—means use of a vehicle primarily for industrial or trade purposes.

5. It is an offence under section 94 of the **Motor Vehicles and Road Traffic Act, Chap. 48:50** to give any particulars which are not correct and you will be liable to prosecution if you do so.


6. Application must be supported by documents as proof of address such as a recent Utility Bill or in the case of a rental, a copy of the Lease/Rental Agreement for the rental premises identified and bearing the name of the Applicant. If the utility bill or Lease/Rental Agreement is not in the Applicant's name, a letter from the owner confirming the Applicant's residence and copy of the owner's national identification (ID) MUST be submitted.



**FORM 5A**

Regulation 19.

(Front)

<i>Photograph</i>	 REPUBLIC OF TRINIDAD AND TOBAGO <b>DRIVER'S PERMIT</b>		
	Name and Address		
	Issue Date	Expiry Date	TR
	Birth Date	Sex	Class
	Permit Number		Date of Payment
<i>Signature of Holder</i>		<i>Signature of Licensing Officer</i>	

(Back)

*Reminder Notice*

This permit is valid for three years only from the date of First Issue or Anniversary Date of Renewal.

*Restriction*

Nil

*Class*

- (1) Motorcycles
- (2) Wheel tractors
- (3) Light motor vehicles
- (4) Heavy motor vehicles
- (5) Extra heavy motor vehicles
- (6) Omnibuses
- (7) Others

*Transaction Code*

- A.—First Issue
- B.—Renewal
- C.—Duplicate
- D.—Endorsement.

**FORM 5A—Continued**  
(Back)

*Reminder Notice*

This permit is valid for three years only from the date of First Issue or Anniversary Date of Renewal.

*Restriction*

Holder must wear corrective lenses Yes  No   
Valid to drive automatic transmission only Yes  No

*Class*

- (1) Motorcycles
- (2) Wheel tractors
- (3) Light motor vehicles
- (4) Heavy motor vehicles
- (5) Extra heavy motor vehicles
- (6) Omnibuses
- (7) Others

*Transaction Code*

- A.—First Issue
- B.—Renewal
- C.—Duplicate
- D.—Endorsement.

(Back)

*Reminder Notice*

This permit is valid for one year only from the date of First Issue or Anniversary Date of Renewal.

*Restriction*

Holder must wear corrective lenses Yes  No   
Valid to drive automatic transmission only Yes  No

*Class*

- (1) Motorcycles
- (2) Wheel tractors
- (3) Light motor vehicles
- (4) Heavy motor vehicles
- (5) Extra heavy motor vehicles
- (6) Omnibuses
- (7) Others

*Transaction Code*

- A.—First Issue
- B.—Renewal
- C.—Duplicate
- D.—Endorsement.

(Back)

*Reminder Notice*

This permit is valid for one year only from the date of First Issue or Anniversary Date of Renewal.

*Restriction*

Invalid or disabled driver valid while driving private motor car Registration No. .... only.

*Class*

- (1) Motorcycles
- (2) Wheel tractors
- (3) Light motor vehicles
- (4) Heavy motor vehicles
- (5) Extra heavy motor vehicles
- (6) Omnibuses
- (7) Others


*Transaction Code*

- A.—First Issue
- B.—Renewal
- C.—Duplicate
- D.—Endorsement.

**FORM 5AA**

[120/2022].

(Front)

REPUBLIC OF TRINIDAD AND TOBAGO DRIVER'S LICENCE			
Photograph	Name Address		Class
	Licence Number		
	Birth Date	Expiry Date	
	Issue Date	Date of Payment	TR
Signature of Holder	Signature of Transport Commissioner		

(Back)

*Reminder Notice*

This licence is valid for five years only from the date of First Issue or Anniversary Date of Renewal.

*Restriction*

Nil

Class	Transaction Code
(1) Motorcycles	A.—First Issue
(2) Wheel tractors	B.—Renewal
(3) Light motor vehicles	C.—Duplicate
(4) Heavy motor vehicles	D.—Endorsement.
(5) Extra heavy motor vehicles	
(6) Omnibuses	
(7) Others	

(Back)

*Reminder Notice*

This licence is valid for five years only from the date of First Issue or Anniversary Date of Renewal.

*Restriction*

Holder must wear corrective lenses Yes  No   
Valid to drive automatic transmission only Yes  No

**FORM 5AA—Continued**

Class	Transaction Code
(1) Motorcycles	A.—First Issue
(2) Wheel tractors	B.—Renewal
(3) Light motor vehicles	C.—Duplicate
(4) Heavy motor vehicles	D.—Endorsement.
(5) Extra heavy motor vehicles	
(6) Omnibuses	
(7) Others	

(Back)

*Reminder Notice*

This licence is valid for one year only from the date of First Issue or Anniversary Date of Renewal.

*Restriction*

Invalid or disabled driver valid while driving private motor car Registration No.... only.

Class	Transaction Code
(1) Motorcycles	A.—First Issue
(2) Wheel tractors	B.—Renewal
(3) Light motor vehicles	C.—Duplicate
(4) Heavy motor vehicles	D.—Endorsement.
(5) Extra heavy motor vehicles	
(6) Omnibuses	
(7) Others	

(Back)

*Reminder Notice*

This licence is valid for one year only from the date of First Issue or Anniversary Date of Renewal.

*Restriction*


Holder must wear corrective lenses      Yes       No   
Valid to drive automatic transmission only      Yes       No

Class	Transaction Code
(1) Motorcycles	A.—First Issue
(2) Wheel tractors	B.—Renewal
(3) Light motor vehicles	C.—Duplicate
(4) Heavy motor vehicles	D.—Endorsement.
(5) Extra heavy motor vehicles	
(6) Omnibuses	
(7) Others	

**FORM 5B**

Regulation 19.

(Front)

<i>Photograph</i>	 REPUBLIC OF TRINIDAD AND TOBAGO PROVISIONAL PERMIT			
	Name and Address			
	Issue Date		Expiry Date	
	Birth Date	Sex	Class	TR
	Permit Number		Date of Payment	
<i>Signature of Holder</i>		<i>Signature of Licensing Officer</i>		

(Back)

*Reminder Notice*

This permit is valid for one year only from the date of First Issue.

*Restriction*

A learner shall drive on such roads between the hours and days stipulated by the Commissioner of Transport.

*Class*

- (1) Motorcycles
- (2) Wheel tractors
- (3) Light motor vehicles
- (4) Heavy motor vehicles
- (5) Extra heavy motor vehicles
- (6) Omnibuses
- (7) Others

*Transaction Code*

- A.—First Issue
- B.—Renewal
- C.—Duplicate
- D.—Endorsement.

258 **Chap. 48:50** *Motor Vehicles and Road Traffic*  
[Subsidiary] *Motor Vehicles and Road Traffic Regulations*

Regulation  
21(2).

**FORM 6**

**PARTICULARS TO BE GIVEN BY APPLICANT FOR  
CONDUCTOR'S PERMIT**

*Motor Vehicles and Road Traffic Act, Chap. 48:50*

1. Full Name of Applicant ... ..	
2. Postal Address of Residence of Applicant ...	
3. State Date of Birth of Applicant ... ..	
4. Are you the holder of a Conductor's Permit, or have you at any time previously been the holder of a Conductor's Permit, if so, state number and date of issue ... ..	
5. State particulars of any endorsement on any Conductor's or Driver's Permit which you hold or have previously held ... ..	
6. Have you at any time been disqualified from obtaining a Conductor's or Driver's Permit. If so, give particulars as to the Court by whom, the date on which and the period for which the disqualification was imposed ... ..	

Signature of Applicant .....

Date of Application .....

\_\_\_\_\_

FORM 7

Regulation 27.

**MOTOR VEHICLES INSPECTOR'S CERTIFICATE**

*Motor Vehicles and Road Traffic Act, Chap. 48:50*

No.

I hereby certify that:

(1) I have personally made a thorough examination of, and have driven and tested the—

Hiring Car or Taxi No. H. ....	Lorry No. T .....
Omnibus No. H. ....	Van No. T .....
Light Omnibus No. H. ....	Trailer No. T .....
Freight Passenger Vehicle No. H. ....	Goods Vehicle using fuel other than Petrol No. T .....
One of the above Vehicles using fuel other than Petrol No. H. ....	

Owned by .....

of .....  
which is described below—

- (a) Chassis manufactured by .....
- (b) Model ..... W.B for G-V or M.O .....
- (c) Year manufactured .....
- (d) Engine No. .... No. of Cylinders .....
- (e) Make ..... Fuel .....
- (f) Factory number of chassis .....
- (g) Maker's maximum gross weight in kilogrammes when new .....
- (h) Type of body .....
- (i) Tare in kilogrammes .....

and found the condition of its several parts to be—

Chassis .....  
Engine .....  
Body .....  
Tyres .....  
Brakes .....  
Mechanism .....

and have allowed a—

Longitudinal Overhang of .....  
Lateral Overhang of ..... R Wheels Dual or Single Tyres .....

(2) The said vehicle ..... conforms to the Regulations for the time being in force under the Motor Vehicles and Road Traffic Act, Chap. 48:50 and is in good and proper condition to carry ..... passengers. Be licensed for a Maximum Gross Weight of ..... kilogrammes. Licence duty to be paid \$ .....

260 **Chap. 48:50** *Motor Vehicles and Road Traffic*  
[Subsidiary] *Motor Vehicles and Road Traffic Regulations*

- (3) That not more than ..... persons may sit on the left/right of the driver.
- (4) Inspection Receipt bearing No. .... dated ..... 20 ....., for the Inspection Fee has been produced and seen by me.
- (5) And that the said ..... may be duly licensed for the year .....

.....  
*Motor Vehicles Inspector*

Date of certificate ....., 20 .....

UNOFFICIAL

Regulation 27(3).

**FORM 8**

**REGISTER TO BE KEPT BY MOTOR VEHICLES INSPECTORS**


1	2	3	4	5	6	7	8	9	10	11
Number of Certificate issued	Date of first inspection	Date of Certificate issued	Registered Number of Vehicle	Name of Owner	Address of Owner	Type of Vehicle	Number of Passengers to be carried	Tare in kilogrammes	M.G.W. in kilogrammes	Remarks

262 **Chap. 48:50** *Motor Vehicles and Road Traffic*  
[Subsidiary] *Motor Vehicles and Road Traffic Regulations*

Section 34.  
[311/2020].

**FORM 9**

Form 9

  
Government of the Republic of Trinidad and Tobago

**APPLICATION FOR DEALER'S GENERAL LICENCE**  
Motor Vehicles and Road Traffic Act, Chap. 48:50  
SECTIONS 34 - 40 and Regulation 11

**Please print information in BLOCK LETTERS**

1. Applicant Name: \_\_\_\_\_  
(Surname, First Name, Middle Name)

Company Name: \_\_\_\_\_ Company/Business Registration No. \_\_\_\_\_

2. Applicant I.D.  / D.P.  / Passport  No.: \_\_\_\_\_ Telephone: (\_\_\_\_) \_\_\_\_\_

3. Address (Street): \_\_\_\_\_

Address (City): \_\_\_\_\_

4. Email Address: \_\_\_\_\_

5. Nature of business: \_\_\_\_\_  
(Dealer, Manufacturer or Repairer)

Business Address (Street): \_\_\_\_\_

Address (City): \_\_\_\_\_

6. Number of general identification marks required: \_\_\_\_\_

7. Insurance Details -

(a) Name of Insurance Company: \_\_\_\_\_

(b) Terms of Insurance Certificate/Policy: \_\_\_\_\_

(c) Insurance Certificate/Policy No.: \_\_\_\_\_


(c) Expiration date of Insurance Certificate/Policy: \_\_\_\_\_  
(DD/MM/YYYY)

**Declaration of Applicant:**  
I \_\_\_\_\_, declare that the information provided above is true and correct and hereby apply for a Dealer's General Licence.

Signature: \_\_\_\_\_ Date: \_\_\_\_\_  
(DD/MM/YYYY)

N.B: (1) It is an offence under section 94 of the Motor Vehicles and Road Traffic Act, Chap. 48:50 to give any particulars which are not correct and you will be liable to prosecution if you do so.  
(2) All applications must be supported by Company validation documents such as a copy of the company/business registration certificates and/or Notice of Directors.

For Official Use only: \_\_\_\_\_



**FORM 10**

Section 35.

Licence No. ....

**FORM OF DEALER'S GENERAL LICENCE**

*Motor Vehicles and Road Traffic Act, Chap. 48:50*

1. A dealer's general licence is hereby granted to ..... of ..... under section 35 of the Act as a dealer/manufacturer/repairer of motor vehicles, subject to the provisions of the Act and Regulations.

2. The following general identification marks are assigned under this licence .....

3. This licence expires on 31st December .....

Date .....

..... Licensing Authority.

N.B.—Motor vehicles used under the authority of this licence must be the property of the licence holder and may only be used for the purposes defined in section 35 of the Act and subject to the provisions of regulation 11.

**FORM 11**

Section 36.

**FORM OF REGISTER OF DEALERS' GENERAL LICENCES TO BE KEPT BY THE TRANSPORT OFFICER**

*Motor Vehicles and Road Traffic Act, Chap. 48:50*


No. of licence issued and date of issue	Name of licensee and place of business	Whether licensed as dealer, manufacturer or repairer	Insurance Company, terms of policy. No. of policy	Date of expiration of policy	Numbers of identification marks assigned

L.R.O.

264 **Chap. 48:50** *Motor Vehicles and Road Traffic*  
[Subsidiary] *Motor Vehicles and Road Traffic Regulations*

Regulation 26.  
[9 of 2017  
311/2020].

**FORM 12**

 Government of the Republic of Trinidad and Tobago		Form 12
MEDICAL TEST FOR DRIVING PERMIT <b>FORM OF MEDICAL CERTIFICATE FOR AN APPLICANT FOR                  A PERMIT TO DRIVE MOTOR VEHICLES</b> Motor Vehicles and Road Traffic Act, Chap. 48:50		
(1) This form is to be completed by REGISTERED MEDICAL PRACTITIONER (2) Please print information in BLOCK LETTERS		
Applicant Name: _____ <small>(Surname, First Name, Middle Name)</small>		
Applicant I.D. <input type="checkbox"/> / D.P. <input type="checkbox"/> / PASSPORT <input type="checkbox"/> No. _____		
In the case of suspected medical unfitness it is important that the Licensing Authority be satisfied on the following points before the grant of a driving permit:		
1. Is the applicant, to the best of your judgment, subject to epilepsy, vertigo or any mental ailment likely to affect his efficiency?	Reply to be inserted in this column	
2. Does the applicant suffer from any heart or lung disorder which might interfere with the performance of his duties as a driver?		
3. What is the Blood pressure reading? <small>(Both systolic and diastolic readings should be given)</small>		
4. (a) Is there any defect of vision? <small>(See Note I).</small>	(a)	
(b) If a defect of vision is revealed on examination, give acuity of vision by Snellen's Test.	(b) R.E.            L.E            without glasses. R.E.            L.E            with glasses.	
(c) Do you consider that the applicant should wear glasses when driving?	(c)	
(d) Is there any defect of hearing?	(d)	
5. Has the applicant any deformity or loss of members? If so, would it interfere with the efficient performance of his duties as a driver? <small>(See Note II)</small>		
6. Is the applicant sufficiently active for the performance of his duties as a driver?		
7. Does the applicant show any evidence of being addicted to the excessive use of alcohol, tobacco or drugs?		
8. Is the applicant, in your opinion, generally fit as regards:	(a)	
(a) bodily health and	(b)	
(b) temperament for the performance of his duties of as a driver?		
Notes: I - Special attention should be directed to distant vision. II - Special attention is directed to the condition of the arms, hands, legs and joints of the upper and lower extremities		
		[OVER]
[1]		

FORM 12

The applicant is responsible for the payment of any fee in connection with the examination and the fee is NOT a charge on Public funds.

The Certificate is for the confidential use of the Licensing Authority and its contents are not divulged to anyone other than the applicant.

It is an offence under section 94 of the Motor Vehicles and Road Traffic Act, Chap. 48:50, for any person to "make any statement which to his knowledge is false, or in any material respect misleading", and the penalty on conviction is two thousand dollars.

It is suggested that the applicant might be so warned before the examination is made by the Registered Medical Practitioner.

\_\_\_\_\_

**TO: THE LICENSING AUTHORITY**

I certify that I have examined the applicant, Mr/Mrs/Miss \_\_\_\_\_  
(Surname) (Other Names)

\_\_\_\_\_ on \_\_\_\_\_  
(DD/MM/YYYY)

I consider this patient fit  / unfit  for the performance of his duties as a driver of motor vehicles.

Medical Practitioner Name : \_\_\_\_\_

Qualification and  
Registration Number of Medical Practitioner : \_\_\_\_\_

Office Address (Street) : \_\_\_\_\_

Address (City) : \_\_\_\_\_


Telephone : (\_\_\_\_) \_\_\_\_\_ Email: \_\_\_\_\_

I declare that to the best of my knowledge and belief the information given by me is true and correct. I am aware that if there is any statement in this declaration which is false in fact or which I know or believe to be false or do not believe to be true, I am liable on summary conviction to a fine of two thousand dollars in accordance with section 94 of the Motor Vehicles and Road Traffic Act, Chap. 48:50.

\_\_\_\_\_  
Signature of Medical Practitioner

\_\_\_\_\_  
Date: (DD/MM/YYYY)

\_\_\_\_\_  
Medical Practitioner's Stamp



[2]

266 **Chap. 48:50** *Motor Vehicles and Road Traffic*  
[Subsidiary] *Motor Vehicles and Road Traffic Regulations*

Regulation 7.

## SECOND SCHEDULE

### Alternative Diagram No. 1



### Alternative Diagram No. 2

8. Particulars as to the position on the car in which it is proposed to place the plates forming the identification mark: \_\_\_\_\_

---

**Declaration of Applicant:**

I, \_\_\_\_\_ declare that the information provided is true and correct and hereby apply for the registration of the vehicle specified above.

Signature \_\_\_\_\_ Date (dd/mm/yyyy): \_\_\_\_\_

N.B. (1) It is an offence under section 64 of the Motor Vehicles and Road Traffic Act, Chap. 48:50 to give any particulars which are false or incorrect and are well known to be so by the person giving them.  
(2) Applications made to the Registrar in accordance with these regulations shall be treated as being made in the name of a holder of a valid copy of the Leasehold Agreement for the land upon which the vehicle is to be registered. If the vehicle is not a Leasehold Agreement as set out in the regulations, a letter from the owner authorizing the Registrar to receive and copy of the owner's national identification (NIC) must be submitted.  
(3) If applicant is a Company, the application must be supported by Company's solicitor's certificate as a copy of the company's business registration certificate and/or letter of Director.

The alternative diagrams above are specimen plates drawn approximately to a scale of one-third. The actual size of the plate will, however, differ according to the number of letters and figures required.

**\*THIRD SCHEDULE**

Regulation 92.

**PARKING PLACES**

PORT-OF-SPAIN

1. *DeLuxe Theatre and Victoria Institute*.—Keate Street, North side, facing East between Frederick Street and Chancery Lane.

2. *Vistarama Theatre*—

- (i) St. Vincent Street, facing South, between Park and Gordon Streets;
- (ii) Oxford Street, South side facing West, between St. Vincent and Abercromby Streets and between Abercromby and Pembroke Streets; and North side, facing West, between St. Vincent and Edward Streets.

3. *Globe Theatre*—

- (i) Park Street, North side, facing West between St. Vincent and Edward Streets;
- (ii) Edward Street, facing North, between Park Street and Tragarete Road;
- (iii) Edward Street, facing North, between Park and Duke Streets.

4. *Astor Theatre*—French Street, between Ariapita Avenue and the Eastern entrance to the Theatre.

5. *Olympic Theatre*—Pelham Street, between Erthig Road and Jerningham Avenue.

6. *Roxy Theatre*—Damian Street, South of the Road Sign on the road surface.

7. *Royal Theatre*—Charlotte Street, between Oxford Street and Observatory Street at a point seventy metres North of Park Street.

8. *Clydesdale Club*—Stanmore Avenue, East side facing South, between Queen's Park West and Albion Street.

\*This Schedule was amended by the following GNs: 148/1958; 32/1964; 73/1966; 206/1979, 207/1979, 208/1979 and 211/1979.

9. *Cosmos Club*—New Street, North side, facing East, between St. Vincent and Edward Streets.

10. *Portuguese Association*—Richmond Street, facing South between Duke and Park Streets.

11. *Portuguese Club, Shamrock Club and the Overseas Forces Club*—Queen's Park East, West side, facing North, between Park Avenue and Belmont Circular Road.

12. *Casuals Club*—Queen's Park West, North side facing East, between Picton Street and a point three metres West of the Club entrance.

13. *Union Club*—Independence Square South, both sides; facing West, between Chacon and Abercromby Streets.

14. *Queen's Park Cricket Club*—Elizabeth Street, West side, facing North, between St. Clair Avenue and Tragarete Road.

15. *Queen's Park Hotel*—
- (i) Queen's Park West, North side, facing East, between Cipriani Boulevard and a point three metres West of the central entrance to the Hotel;
  - (ii) Victoria Avenue, East side, facing South, between Tragarete Road and Queen's Park West.

16. *Botanic Gardens*—Circular Road, South side, facing West, between Lady Chancellor Road and a point eight metres West of the main Entrance to President's House.

17. *Town Hall and Public Library*—Knox Street, South side, facing East between Frederick and Pembroke Streets.

18. *Trinidad Dairies*—Phillips Street, West side, facing North, between Tragarete Road and Kew Place.

19. *Masonic Temple*—Alexandra Street, East side, facing North, between Tragarete Road and Sweet Briar Road.

20. *St. Ann's Hall*—Oxford Street, South side facing West, from Charlotte Street to Observatory Street.

**PARKING PLACES—Continued**

21. *Independence Square Tennis Club*—George Street, facing North from Independence Square South to South Quay.

22. *India Club*—Cipriani Boulevard between Queen's Park West and Tranquillity Street, East side facing South.

23. *Hankow Restaurant*—Charlotte Street between Queen Street and Independence Square North.

Regulation 111.

**FOURTH SCHEDULE**

REPUBLIC OF TRINIDAD AND TOBAGO

**FORM OF APPLICATION FOR TAXI DRIVER'S LICENCE**

1. Full name of applicant (Surname first, in block letters) .....
  2. Postal address of residence of applicant .....
  3. State number of Driver's Permit (Motor Vehicles and Road Traffic Act) and date of issue .....
  4. State date and place of birth .....
- Signature of Applicant .....
- Date of Application .....

Regulation 111.

**FIFTH SCHEDULE**

REPUBLIC OF TRINIDAD AND TOBAGO

**TAXI DRIVER'S LICENCE**

Photograph of Holder	Licence No. ....	To Drive a Taxi Driver's Permit No. ....
----------------------	------------------	--

..... of ..... is hereby licensed to drive a taxi.

Dated this ..... day of ....., 20.....

Signature of holder .....

.....  
*Licensing Authority*

FEE \$10.00

\_\_\_\_\_

**SIXTH SCHEDULE**

197/1999.  
[34/2003  
146/2017].

**RESPONSIBILITIES OF A VEHICLE TESTING STATION  
PROPRIETOR/EXAMINER**

1. This document outlines the responsibilities of the Proprietor of premises at which road safety inspection checks are to be performed as well as those of the Examiner, the person who actually performs the inspection checks.

2. For the purposes of this document the following terms would have the meaning defined:

“Act” means the Motor Vehicles and Road Traffic Act (Chap. 48:50);

“Authority” means the Licensing Authority;

“Examiner” means a person certified by the Authority as possessing the standard of qualifications, skills and experience to perform the inspection checks necessary for determining the road worthiness of private motor vehicles and motorcycles. It also means that the person has also attended the Authority’s training/orientation programme and has met the standards determined for certification. A Proprietor may be certified as a Tester if he possesses the necessary combination of qualifications, experience and training;

“Proprietor” means individual partnership or company whose premises has met the standards determined by the Authority upon application for the performance of road safety inspection checks on private cars and motorcycles;

“Vehicle Testing Station” refers to premises approved by the Authority in accordance with section 26 of the Act.

**GUIDELINES FOR PROPRIETORS**

3. The Proprietor shall be issued with a Designation (Appendix I) duly signed and dated by the Authority authorising and identifying the premises to be used as a Vehicle Testing Station.

4. (1) The Proprietor shall—

- (a) submit the name(s) of any of his employees possessing appropriate technical qualifications, skills and experience as an auto mechanic for assessment by the Authority for selection. Such persons are to attend an approved training/orientation course developed for persons wishing to perform the duties of an examiner. Persons not possessing the full qualifications, but who have submitted evidence of a

suitable working experience of at least five (5) years as an auto mechanic shall be subjected to an examination prepared by the Authority for determining their suitability for certification to perform the duties as examiners;

- (b) **(Deleted by LN 34/2003);**
- (c) notify the Authority of any change in their Testing Staff, clearly stating the reason(s) for such change;
- (d) ensure that—
  - (i) suitable accommodation for customers and staff is provided, kept in a tidy condition and a good state of repair (*See Appendix II for details of accommodation*);
  - (ii) customers are able to witness the inspection check from a safe and comfortable position;
- (e) have available in good working order all equipment and facilities as listed in Appendix II;
- (f) ensure that an adequate supply of the various documents to be used in the inspection process is always available. Documents shall include such other form(s) that the Authority may prescribe from time to time. Requisitions for these documents shall be made on the form provided at Appendix XI;
- (g) ensure that all stamps, seals and documents are kept in a safe place and under the control of the Proprietor;
- (h) ensure that a monthly return is made to the Authority on the prescribed form of all vehicles that have undergone an inspection check at the Testing Station within seven (7) days from the end of each month;
- (i) retain a copy of Monthly Returns, Inspection Checklists, and Certificate of Inspection for at least twenty-four (24) months so that Duplicate Inspection Certificates/Stickers can be prepared as needed;
- (j) deliver to the Authority all official documents on request by the Authority on suspension/cessation of Vehicle Testing Station operations;
- (k) ensure that a notice indicating opening and closing hours should be on display in a conspicuous place outside the premises;
- (l) display in a conspicuous place on his premises the prescribed “Vehicle Testing Station” sign clearly showing the V.T.S. No. assigned;
- (m) display in the waiting room of the premises in a conspicuous manner the certificate of authorisation for the operations of the Vehicle Testing Station as in Appendix III and the certification of the Tester(s) as in Appendix IV;

- (n) display in a conspicuous place a notice that informs customers of the right to lodge complaint(s) on the appropriate form to the Authority about any grievance in relation to the inspection proceedings or otherwise;
- (o) make the premises and records available for examination by officers authorised by the Authority;
- (p) inform the Authority of any changes affecting the ownership, control, layout and operations of the Testing Station;
- (q) ensure that the Testing Station complies with any guidelines set out by the Town and Country Planning Division, Local Health Authority, Fire Services and other Regulatory Agencies;
- (r) ensure that the premises are covered by adequate liability insurance for any injury, loss or damage that may occur on the premises and for which it is liable;
- (s) ensure that the day-to-day operations of the Testing Station are organised so as to avoid undue congestion on the premises;
- (t) ensure that vehicles registered in the name of the Proprietor are not inspected at the Testing Station belonging to the Proprietor;
- (u) allow facilities to be used by authorised personnel from the Authority to carry out tests on vehicles of applicants who have appealed decisions made at their respective Testing Stations.

(2) A person who fails to submit a return in accordance with subparagraph (1)(h) is required to pay a fine of one thousand dollars.

### **GUIDELINES FOR EXAMINERS**

5. Having completed the approved training/orientation course issued by the Authority and on application of the examiner (Appendix V) a certificate shall be issued duly signed and dated by the Authority authorising the examiner to perform inspection checks on privately registered motor vehicles (not exceeding 2 270 kg) and motorcycles.

6. The examiner shall ensure that—

- (a) tests are carried out and completed as far as possible without interruption;
- (b) inspections of vehicles are carried out in accordance with the Act and these Guidelines as well as any instructions or supplementary directives that may be issued from time to time by the Authority;
- (c) that all documents are signed and dated accurately;

- (d) when the inspection check has been completed but the vehicle has failed to meet the statutory requirements, the original copy of the Inspection Checklist, signed and dated by the examiner and detailing all defects discovered, must be issued to the person who brought in the vehicle;
- (e) when the inspection check is completed and the vehicle is found to meet statutory requirements, a certificate of inspection (Appendix VII) signed and dated by the Tester is then issued in the name of the registered owner of the vehicle;
- (f) an official sticker (Appendix VIII) supplied by the Authority is then affixed to the lower left-hand corner of the front windshield of the vehicle. In the case of a motorcycle the sticker should be affixed to a conspicuous place at the front;
- (g) where it is the opinion of the Examiner that there has been tampering with the chassis/engine number an immediate report should be lodged with the nearest office of the Authority. The make, model, number of the vehicle, together with the name and address of the registered owner should be noted and forwarded. The examiner has no power to impound the vehicle;
- (h) while on duty the examiner is required to wear an official Examiner's Identification showing that he/she is a certified Examiner working at the Testing Station (Appendix IX).

#### GENERAL

7. The various fees and charges in respect of the Testing Station operations may be reviewed annually, but for the time being consist of the following:

*Fees—*

- (a) testing stations shall be subjected to the payment of a Registration Fee of \$1,000.00 payable to the Authority;
- (b) an annual renewal fee of \$500.00 shall be paid to the Authority;
- (c) an Examiner is liable to a certification fee of \$300.00 payable to the Authority for a period to two (2) years. Certification would be renewable at the same cost from the date of issue on a biannual basis;

\*(d) (i) Proprietors are to purchase the inspection documents from the Authority;

(ii) the inspection fee payable for the time being shall be made up as follows:

Inspection	\$ 200.00
Vat	\$ 25.00
Reimbursement for inspection documents	\$ 75.00

\*Paragraph (d)(i) and (ii) were deleted and replaced by LN No. 146/2017.

*Authorised Testing Stations must be VAT registered—*

- (e) a vehicle that has failed the road safety inspection check is entitled to a free inspection if it is brought back to the same Testing Station at any time for inspection within six (6) weeks of the date of the first inspection;
- (f) a vehicle that is inspected after six (6) weeks of the date of the first inspection would be subjected to a complete inspection for which an additional inspection fee of two hundred dollars (\$200.00) would be paid by the vehicle's owner.

*Registers—*

- (g) the Authority shall keep a register of all premises authorised to function as Testing Stations;
- (h) the Authority shall keep a register of all persons certified as Examiners and the respective Testing Stations at which they are to function.

**FORMS**

8. The official forms which are used in connection with the Vehicle Testing Programme are listed below together with notes on their use—

- (a) Designation Instrument (Appendix I);
- (b) Accommodation, Equipment and Inspection Pit (Appendix II);
- (c) Testing Station Authorisation (Appendix III);
- (d) Examiner Certificate (Appendix IV);
- (e) Application Form Certification for a Vehicle Examiner (Appendix V);
- (f) Inspector Checklist (Appendix VI);
- (g) Inspector/Test Certificate (Appendix VII);
- (h) Inspector Sticker (Appendix VIII);
- (i) Examiner's Identification (Appendix IX);
- (j) Application for premises to be used as a Vehicle Testing Station compound (Appendix X);

*Any false statement may put the application or any authorisation resulting from it, at risk. The form must be signed by the Proprietor, or by a partner in the case of a partnership. In the case of a company, it should be signed by a director or any other authorised by the director.*

- (k) Application for inspection documents (Appendix XI);
- (l) Monthly returns (Appendix XII);

*An authorised Proprietor is required to record in this Return particulars of all tests carried out at the Testing Station. The record must indicate whether the vehicle satisfies the*

*requirement of an inspector, or otherwise. The register must be kept at the Testing Station for at least twenty-four (24) months and a copy of the register must be forwarded to the Licensing Authority within seven (7) days after the end of the month to which it refers. It must be accompanied with the duplicate copies of certificates of inspection for the period.*

(m) Complaint/Grievance Notice (Appendix XIII);

*This form is to be used by anyone who wishes to record a complaint or grievance, and must be sent to the Licensing Authority within seven (7) days of the incident. The forms must be held at the Testing Station and a poster (Appendix XIV) detailing the appeal procedure must be displayed where it can be read by members of the public.*

*Certificates of Inspection*

9. (a) Certificates of Inspection Book(s) shall be issued only on receipt of a requisition together with the appropriate fee.

(b) A certificate of inspection must be completed in triplicate on the same day of the test. The certificate must always be signed by the person who carried out the test **and embossed with the Testing Station Seal**. The duplicate copy must accompany the Monthly Return.

(c) The month of issue and expiry must always be stated first followed by the day and year. No space must be left in which figures can be inserted. The last two figures of the year must also be entered in words to prevent alteration.

**Example:** Date of issue June 24 1991 (ninety-one)

Date of expiry June 23 1992 (ninety-two).

(d) **The name and number of the issuing Testing Station must be embossed** in the space marked "Signature of Inspector/Tester". Rubber stamps are not acceptable.

(e) The "date of issue" will always be the date on which the certificate is completed. It is effective for twenty-four (24) months from the date of issue. However, if there is a current certificate of inspection for the vehicle, the date of expiry on the new certificate shall be twenty-four months from the date of expiry shown on the current certificate. Examiners must always enquire of the owner for a current certificate and if applicable, its serial number must be **recorded on the new certificate in the space provided**. The certificate shall not be altered if the current certificate is produced at a later date. This advice should also be given if the "date of expiry" entered by the tester is disputed.

**Example:**    **Date of issue of previous certificate 12th May 1991;**  
                  **Date of expiry of previous certificate 11th May 1993;**  
                  **Date of issue of new certificate 28th May 1993;**  
                  **Date of expiry to be entered on new certificate**  
                  **10th May 1995.**

(f) An inspection check cannot be performed more than one (1) month before the expiry date of the current certificate of inspection.

10. Official documents (Inspection Checklist, Certificates of Inspection and Monthly Return, etc.) must be completed in indelible ink or ballpoint pen and a clear carbon copy must be taken. Entries must be written clearly and firmly to ensure that any subsequent attempt to alter them will be obvious.

**APPENDIX I**

**REPUBLIC OF TRINIDAD AND TOBAGO**

**DESIGNATION AS AUTHORISED PREMISES  
AS A VEHICLE TESTING STATION**

The following premises, namely: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

as owned and operated by \_\_\_\_\_

\_\_\_\_\_, authorised Proprietor(s) is hereby designated as a Vehicle Testing Station for the purposes of the inspection of motor vehicles under the provisions of the Motor Vehicles and Road Traffic Act, (Chap. 48:50).

Dated this ..... day of ..... 20.....

.....  
*Transport Commissioner*

\_\_\_\_\_

## APPENDIX II

### SUITABLE ACCOMMODATION, EQUIPMENT AND INSPECTION PIT

#### 1. ACCOMMODATION

- a. Staff Office
- b. Public Waiting Room
- c. Brake Testing Area
- d. Parking Facilities
- e. Entry and Exit Point

#### 2. EQUIPMENT

- a. Hydraulic Jack (3-ton and 6-ton)
- b. Head Lamp Spot and Alignment Tester
- c. \*Brake Efficiency Tester
- d. Tyre Tread Depth Tester
- e. Cro-Bars
- f. \*Emission Tester
- g. \*Smoke Meter
- h. 1/4 lb Engineer's Hammer

#### 3. INSPECTION PIT

- a. Width 2' 7"
- b. Length 25' to 33'
- c. Depth 5' 6"
- d. Extension Light

and/or

#### 4. RAMP

and/or

#### 5. HOIST

**SPECIAL NOTE** \*Within one (1) year the intention is for all Testing Stations to be equipped with Brake Testing and Emission Control Machines. Proprietors are to note that this can be a precondition for the renewal of the Licence to operate a Testing Station.

**APPENDIX III**

**TRANSPORT DIVISION  
TESTING STATION AUTHORISATION**

I certify that of this ..... day of ..... 20.....

.....

has been approved as a **Vehicle Testing Station**. You are duly authorised to perform roadworthy checks on all Motorcycles and

Private Cars **not exceeding a Tare Weight of 2 270 kg.**

Valid until the ..... day of ..... 20.....

.....  
*Transport Commissioner*

.....  
*Date*

APPENDIX IV

TRANSPORT DIVISION

VEHICLE EXAMINER'S CERTIFICATE

This is to certify that of this ..... day of ..... 20.....

Mr./Ms. ....

has been duly certified as an authorised Examiner of all Motorcycles and Private Cars **not exceeding a Tare Weight of 2 270 kg.**

Testing Station # .....

Valid until the ..... day of ..... 20.....

.....  
*Date*

.....  
*Transport Commissioner*

\_\_\_\_\_

**APPENDIX V**

**MINISTRY OF WORKS AND TRANSPORT**

**APPLICATION FOR CERTIFICATION AS A VEHICLE  
EXAMINER**

NAME (Block Letters) .....

ADDRESS (Block Letters) .....

NAME OF TESTING STATION (Block Letters) .....  
(if Applicable)

VEHICLE TESTING STATION No. ....

PASSPORT/ID No. ....

DRIVER'S PERMIT No. ....

.....  
*Date*

.....  
*Signature*

---

**For Official Use**

**APPENDIX VI**

**TRANSPORT DIVISION**

For Official Use
------------------

**MOTOR VEHICLE INSPECTION CHECKLIST**

No. \_\_\_\_\_

Name/Address of Inspector/Testing Site ..... Testing Centre No. ....  
.....

Date ..... Inspection No. ....

Vehicle Registration No. .... Registered Owner .....

<b>1. Required Documentation:</b>		Good	Defective	<b>4. Electrical:</b>		Good Defective
(a) Inspection Receipt	<input type="checkbox"/>		<input type="checkbox"/>	(a) Head lamps including focus	<input type="checkbox"/>	<input type="checkbox"/>
(b) Certificate of Ownership	<input type="checkbox"/>		<input type="checkbox"/>	(b) Park lamps	<input type="checkbox"/>	<input type="checkbox"/>
(c) Vehicle/Trailer Insurance	<input type="checkbox"/>		<input type="checkbox"/>	(c) Tail Lamps	<input type="checkbox"/>	<input type="checkbox"/>
<b>2. Identification of Vehicle/trailer</b>				(d) Rear Registration Plate Light	<input type="checkbox"/>	<input type="checkbox"/>
Verify:		Good	Defective	(e) Indicators	<input type="checkbox"/>	<input type="checkbox"/>
(a) Vehicle painted according to law	<input type="checkbox"/>		<input type="checkbox"/>	(f) Horn (Note: It must be non-musical)	<input type="checkbox"/>	<input type="checkbox"/>
(b) VIN/Chassis No. ....				(g) Wipers	<input type="checkbox"/>	<input type="checkbox"/>
(c) Body number (if applicable) .....				(h) Passenger Stop Buzzer (Maxi-Taxi)	<input type="checkbox"/>	<input type="checkbox"/>
(d) Engine Number .....				(i) Taxi Sign Lamp (Maxi-Taxi)	<input type="checkbox"/>	<input type="checkbox"/>
(e) Weight .....				(j) Loose Wires, Switches, etc.	<input type="checkbox"/>	<input type="checkbox"/>
(f) Description of Vehicle:				<b>5. Body/door/fenders/panels/glasses/seats</b>		
(i) Colour .....				(a) Operation of:		Good Defective
(ii) Year manufactured .....				(i) Hinges, locks, winders, etc.	<input type="checkbox"/>	<input type="checkbox"/>
(iii) Model .....				(ii) Doors, Bonnet, Trunk in fair condition	<input type="checkbox"/>	<input type="checkbox"/>
(iv) Seating .....				(iii) Entrance/exit door (Maxi-Taxi)	<input type="checkbox"/>	<input type="checkbox"/>
(v) Type .....				(iv) Emergency door (Maxi-Taxi)	<input type="checkbox"/>	<input type="checkbox"/>
(vi) Horse Power .....				(b) Condition of Fender/ Panels (i.e., not excessively corroded)	<input type="checkbox"/>	<input type="checkbox"/>
(vii) Engine Size .....				(c) Seats secured	<input type="checkbox"/>	<input type="checkbox"/>
<b>3. Engine:</b>		Good	Defective	(d) Seat Belt	<input type="checkbox"/>	<input type="checkbox"/>
(a) Oil and Fuel Leaks	<input type="checkbox"/>		<input type="checkbox"/>	(e) Seat Upholstered	<input type="checkbox"/>	<input type="checkbox"/>
(b) Water/Coolant Leaks	<input type="checkbox"/>		<input type="checkbox"/>	(f) Glasses (Windscreens included)	<input type="checkbox"/>	<input type="checkbox"/>
(c) Operation of cut-off switch (Diesel Trucks)	<input type="checkbox"/>		<input type="checkbox"/>	(g) Tint of Glasses	<input type="checkbox"/>	<input type="checkbox"/>
(d) Starter Mechanism	<input type="checkbox"/>		<input type="checkbox"/>	(h) Outside mirror	<input type="checkbox"/>	<input type="checkbox"/>
(e) Engine properly washed	<input type="checkbox"/>		<input type="checkbox"/>	(i) Length, Width and overhangs	<input type="checkbox"/>	<input type="checkbox"/>
(f) Battery properly secured	<input type="checkbox"/>		<input type="checkbox"/>	(j) Bumpers secured	<input type="checkbox"/>	<input type="checkbox"/>
(g) Tuned properly	<input type="checkbox"/>		<input type="checkbox"/>			
(h) Visible Vapour/Sparks, etc.	<input type="checkbox"/>		<input type="checkbox"/>			

<p>6. Markings:</p> <table border="1"> <thead> <tr> <th></th> <th>Good</th> <th>Defective</th> </tr> </thead> <tbody> <tr> <td>(a) Letter (S) painted on all special Vehicles</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(b) M.G.W., Tare and Licence Weight clearly marked and are to Regulation's size and colour</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(c) "LEFT-HAND DRIVE" painted at the Rear of Left-Hand Drive Vehicles</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(d) Correct number of passengers' sign on all Taxis and Maxi-Taxis</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(e) Number Plates are of Regulation size and colour</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> </tbody> </table>		Good	Defective	(a) Letter (S) painted on all special Vehicles	<input type="checkbox"/>	<input type="checkbox"/>	(b) M.G.W., Tare and Licence Weight clearly marked and are to Regulation's size and colour	<input type="checkbox"/>	<input type="checkbox"/>	(c) "LEFT-HAND DRIVE" painted at the Rear of Left-Hand Drive Vehicles	<input type="checkbox"/>	<input type="checkbox"/>	(d) Correct number of passengers' sign on all Taxis and Maxi-Taxis	<input type="checkbox"/>	<input type="checkbox"/>	(e) Number Plates are of Regulation size and colour	<input type="checkbox"/>	<input type="checkbox"/>	<p>10. Under Carriage</p> <table border="1"> <thead> <tr> <th>Check for:</th> <th>Good</th> <th>Defective</th> </tr> </thead> <tbody> <tr> <td>(a) Washed under carriage</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(b) Exhaust System:</td> <td></td> <td></td> </tr> <tr> <td>    (i) Noise</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>    (ii) Corrosion</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>    (iii) Length</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(c) Drive Shaft, Universal Joint and Centre Bearing</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(d) Front and Rear spring "U" Clamps Bolts</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(e) For Loose Body to Chassis Frame Bolts</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> </tbody> </table>	Check for:	Good	Defective	(a) Washed under carriage	<input type="checkbox"/>	<input type="checkbox"/>	(b) Exhaust System:			(i) Noise	<input type="checkbox"/>	<input type="checkbox"/>	(ii) Corrosion	<input type="checkbox"/>	<input type="checkbox"/>	(iii) Length	<input type="checkbox"/>	<input type="checkbox"/>	(c) Drive Shaft, Universal Joint and Centre Bearing	<input type="checkbox"/>	<input type="checkbox"/>	(d) Front and Rear spring "U" Clamps Bolts	<input type="checkbox"/>	<input type="checkbox"/>	(e) For Loose Body to Chassis Frame Bolts	<input type="checkbox"/>	<input type="checkbox"/>
	Good	Defective																																												
(a) Letter (S) painted on all special Vehicles	<input type="checkbox"/>	<input type="checkbox"/>																																												
(b) M.G.W., Tare and Licence Weight clearly marked and are to Regulation's size and colour	<input type="checkbox"/>	<input type="checkbox"/>																																												
(c) "LEFT-HAND DRIVE" painted at the Rear of Left-Hand Drive Vehicles	<input type="checkbox"/>	<input type="checkbox"/>																																												
(d) Correct number of passengers' sign on all Taxis and Maxi-Taxis	<input type="checkbox"/>	<input type="checkbox"/>																																												
(e) Number Plates are of Regulation size and colour	<input type="checkbox"/>	<input type="checkbox"/>																																												
Check for:	Good	Defective																																												
(a) Washed under carriage	<input type="checkbox"/>	<input type="checkbox"/>																																												
(b) Exhaust System:																																														
(i) Noise	<input type="checkbox"/>	<input type="checkbox"/>																																												
(ii) Corrosion	<input type="checkbox"/>	<input type="checkbox"/>																																												
(iii) Length	<input type="checkbox"/>	<input type="checkbox"/>																																												
(c) Drive Shaft, Universal Joint and Centre Bearing	<input type="checkbox"/>	<input type="checkbox"/>																																												
(d) Front and Rear spring "U" Clamps Bolts	<input type="checkbox"/>	<input type="checkbox"/>																																												
(e) For Loose Body to Chassis Frame Bolts	<input type="checkbox"/>	<input type="checkbox"/>																																												
<p>7. Body/chassis frame</p> <table border="1"> <thead> <tr> <th>Check for:</th> <th>Good</th> <th>Defective</th> </tr> </thead> <tbody> <tr> <td>(a) Severe body/chassis frame damage including corrosion</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(b) Cut and Joined bodies and chassis</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> </tbody> </table>	Check for:	Good	Defective	(a) Severe body/chassis frame damage including corrosion	<input type="checkbox"/>	<input type="checkbox"/>	(b) Cut and Joined bodies and chassis	<input type="checkbox"/>	<input type="checkbox"/>	<p>11. Brakes</p> <table border="1"> <thead> <tr> <th>Condition of:</th> <th>Good</th> <th>Defective</th> </tr> </thead> <tbody> <tr> <td>(a) Brake Shoe Lining</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(b) Hub/Wheel Bearing Seals (Any oil leaks)</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(c) Fluid and Air Leaks</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(d) Brake hoses, Pipes, Joints, Cables and Linkages</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(e) Foot Brake Warning Device (Heavy Vehicles)</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(f) Spring Brake (Heavy Vehicles)</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(g) Foot Brakes (Pedal Pressure)</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(h) Hand Brakes (Test)</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> </tbody> </table>	Condition of:	Good	Defective	(a) Brake Shoe Lining	<input type="checkbox"/>	<input type="checkbox"/>	(b) Hub/Wheel Bearing Seals (Any oil leaks)	<input type="checkbox"/>	<input type="checkbox"/>	(c) Fluid and Air Leaks	<input type="checkbox"/>	<input type="checkbox"/>	(d) Brake hoses, Pipes, Joints, Cables and Linkages	<input type="checkbox"/>	<input type="checkbox"/>	(e) Foot Brake Warning Device (Heavy Vehicles)	<input type="checkbox"/>	<input type="checkbox"/>	(f) Spring Brake (Heavy Vehicles)	<input type="checkbox"/>	<input type="checkbox"/>	(g) Foot Brakes (Pedal Pressure)	<input type="checkbox"/>	<input type="checkbox"/>	(h) Hand Brakes (Test)	<input type="checkbox"/>	<input type="checkbox"/>									
Check for:	Good	Defective																																												
(a) Severe body/chassis frame damage including corrosion	<input type="checkbox"/>	<input type="checkbox"/>																																												
(b) Cut and Joined bodies and chassis	<input type="checkbox"/>	<input type="checkbox"/>																																												
Condition of:	Good	Defective																																												
(a) Brake Shoe Lining	<input type="checkbox"/>	<input type="checkbox"/>																																												
(b) Hub/Wheel Bearing Seals (Any oil leaks)	<input type="checkbox"/>	<input type="checkbox"/>																																												
(c) Fluid and Air Leaks	<input type="checkbox"/>	<input type="checkbox"/>																																												
(d) Brake hoses, Pipes, Joints, Cables and Linkages	<input type="checkbox"/>	<input type="checkbox"/>																																												
(e) Foot Brake Warning Device (Heavy Vehicles)	<input type="checkbox"/>	<input type="checkbox"/>																																												
(f) Spring Brake (Heavy Vehicles)	<input type="checkbox"/>	<input type="checkbox"/>																																												
(g) Foot Brakes (Pedal Pressure)	<input type="checkbox"/>	<input type="checkbox"/>																																												
(h) Hand Brakes (Test)	<input type="checkbox"/>	<input type="checkbox"/>																																												
<p>8. Tyres/wheels</p> <table border="1"> <thead> <tr> <th>Condition of:</th> <th>Good</th> <th>Defective</th> </tr> </thead> <tbody> <tr> <td>(a) Tyres</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(b) Rims</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(c) Wheel Studs and Nuts</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(d) Tyre Inflated Pressure</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(e) Tyre Application</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(f) Wheel Alignment</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> </tbody> </table>	Condition of:	Good	Defective	(a) Tyres	<input type="checkbox"/>	<input type="checkbox"/>	(b) Rims	<input type="checkbox"/>	<input type="checkbox"/>	(c) Wheel Studs and Nuts	<input type="checkbox"/>	<input type="checkbox"/>	(d) Tyre Inflated Pressure	<input type="checkbox"/>	<input type="checkbox"/>	(e) Tyre Application	<input type="checkbox"/>	<input type="checkbox"/>	(f) Wheel Alignment	<input type="checkbox"/>	<input type="checkbox"/>																									
Condition of:	Good	Defective																																												
(a) Tyres	<input type="checkbox"/>	<input type="checkbox"/>																																												
(b) Rims	<input type="checkbox"/>	<input type="checkbox"/>																																												
(c) Wheel Studs and Nuts	<input type="checkbox"/>	<input type="checkbox"/>																																												
(d) Tyre Inflated Pressure	<input type="checkbox"/>	<input type="checkbox"/>																																												
(e) Tyre Application	<input type="checkbox"/>	<input type="checkbox"/>																																												
(f) Wheel Alignment	<input type="checkbox"/>	<input type="checkbox"/>																																												
<p>9. Suspension/Steering</p> <table border="1"> <thead> <tr> <th>Condition of:</th> <th>Good</th> <th>Defective</th> </tr> </thead> <tbody> <tr> <td>(a) Steering Ends and Linkages</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(b) Steering Box/Rack</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(c) Fluid Leak from Steering Box/Rack Power Hoses, etc.</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(d) Shackle Pin and Bushings</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(e) Suspension Rubber and Bushings</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td>(f) Stabiliser/Torsion Bars</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> </tbody> </table>	Condition of:	Good	Defective	(a) Steering Ends and Linkages	<input type="checkbox"/>	<input type="checkbox"/>	(b) Steering Box/Rack	<input type="checkbox"/>	<input type="checkbox"/>	(c) Fluid Leak from Steering Box/Rack Power Hoses, etc.	<input type="checkbox"/>	<input type="checkbox"/>	(d) Shackle Pin and Bushings	<input type="checkbox"/>	<input type="checkbox"/>	(e) Suspension Rubber and Bushings	<input type="checkbox"/>	<input type="checkbox"/>	(f) Stabiliser/Torsion Bars	<input type="checkbox"/>	<input type="checkbox"/>																									
Condition of:	Good	Defective																																												
(a) Steering Ends and Linkages	<input type="checkbox"/>	<input type="checkbox"/>																																												
(b) Steering Box/Rack	<input type="checkbox"/>	<input type="checkbox"/>																																												
(c) Fluid Leak from Steering Box/Rack Power Hoses, etc.	<input type="checkbox"/>	<input type="checkbox"/>																																												
(d) Shackle Pin and Bushings	<input type="checkbox"/>	<input type="checkbox"/>																																												
(e) Suspension Rubber and Bushings	<input type="checkbox"/>	<input type="checkbox"/>																																												
(f) Stabiliser/Torsion Bars	<input type="checkbox"/>	<input type="checkbox"/>																																												

**APPENDIX VII**

ORIGINAL

**INSPECTOR'S TEST CERTIFICATE**

Testing Centre No. ....  
Name and Address of Inspector/Testing Site .....

Inspection No. ....

I HEREBY CERTIFY THAT—

- (1) **I have personally made a thorough examination of, and have driven and tested**  
Motor Vehicle Reg. No. .... categorised as ..... vehicle  
Owner's Name .....

Owner's Address .....

**Vehicle Particulars:**

- (a) Chassis manufactured by ..... Model .....
- (b) Make and year manufactured ..... VIN/Chassis No. ....
- (c) Engine No. .... No. of Cylinders .....
- (d) Fuel ..... Horse Power ..... Colour .....
- (e) Tare ..... kg M.G.W ..... kg Tyre Size .....

and found the condition of its several parts to be:

Chassis .....

Engine .....

Body .....

Tyres .....

Brakes .....

Mechanism .....

Fittings .....

and have allowed a:

Longitudinal overhang of .....

Lateral overhang of .....

Rear Axle: Dual  Dual Single

- (2) The said vehicle/trailer ..... conforms to the  
Regulations for the time being in force under the Motor Vehicle and Road  
Traffic Act, Chap. 48:50 and is in good and proper condition to carry  
..... passengers.

- (3) No more than ..... persons may sit on the left/right of the driver and the vehicle may carry a maximum of ..... passengers.
- (4) Inspection Receipt bearing No. .... dated ..... 20..... for the Inspection Fee paid at ..... has been produced and seen by me.
- (5) And that the said vehicle Registration No. .... may be operated on the public roadways of Trinidad and Tobago for the period ..... to .....

Date of Certificate ..... 20.....


.....  
*Signature of Officer/Examiner*

**APPENDIX VIII**  
**INSPECTION STICKER**

**INSPECTION PASSED**

MINISTRY OF WORKS AND TRANSPORT  
TRANSPORT DIVISION

Jan
Feb
Mar
Apr
May
Jun



Jul
Aug
Sep
Oct
Nov
Dec

**TRINIDAD & TOBAGO**

Registration No.

Inspected

**APPENDIX IX**

**EXAMINER'S ID**

**(FRONT)**

**TRANSPORT DIVISION**


Approved Motor Vehicle Examiner

Name:

Expiry Date:

Badge No.:

Certified by:



.....  
*Transport Commissioner*

**(BACK)**

**VEHICLE INSPECTION CLASSES:**

- CLASS 1 — Motorcycles  
CLASS 3 — Private Motor Vehicles  
(Not exceeding 2 270 kg)

This card is the property of the Transport Division, Ministry of Works and Transport. Duplication or modification of this card, or use by anyone rather than the Certified Examiner identified on this card, is a violation of the Motor Vehicle and Road Traffic Act, Chap. 48:50.

.....

**APPENDIX X**

**MINISTRY OF WORKS AND TRANSPORT  
(TRANSPORT DIVISION)**

**APPLICATION FOR PREMISES TO BE USED AS A  
VEHICLE TESTING OR INSPECTION COMPOUND**

(In Accordance with the Motor Vehicles and Road Traffic Act, Chap. 48:50 of  
the Laws of Trinidad and Tobago)

**INSTRUCTIONS:**

- (a) Complete form accurately in capital letters or bold type.
- (b) Tick appropriate boxes to indicate area(s) of Interest.
- (c) Only persons owning twelve (12) vehicles and over would be considered as Fleet Owners.
- (d) Applications for Vehicle Testing Centres must be accompanied by a police certificate of character.
- (e) Persons wishing to offer their premises for use as a Testing Centre/Compound are required to carefully read the attached document "RESPONSIBILITIES OF AN AUTHORISED TESTER".
- (f) Approved premises for Testing would be subject to an annual fee.
- (g) Operators/Owners of approved Testing Centre/Compound would not be allowed to test their own vehicles at their Compound.

**A. TYPE OF APPLICATION:**  Fleet Owner Compound Inspection  
 Vehicle Testing  Private Car  Motorcycle

**B. BUSINESS PARTICULARS:**

- (a) Title/Name \_\_\_\_\_
- (b) Company Registration No. (c) VAT Registration No. (d)(i) Telephone No. \_\_\_\_\_  
\_\_\_\_\_ (ii) Fax No. \_\_\_\_\_
- (e) Business Address \_\_\_\_\_
- (f) Compound Address \_\_\_\_\_  
[If different from (a) above] \_\_\_\_\_

**C. FLEET OWNERS ONLY**—(Inspection would be conducted by Transport Division's Personnel)

- (a) No. of Vehicles \_\_\_\_\_
- (b) Registration Class:
  - (i) No. Motorcycle \_\_\_\_\_ (v) No. Extra Heavy Motor Vehicle \_\_\_\_\_  
(M.G.W. over 15 240 kg)
  - (ii) No. Wheel Tractor \_\_\_\_\_ (vi) No. Omnibus \_\_\_\_\_
  - (iii) No. Light Motor Vehicle \_\_\_\_\_ (vii) No. Trailer:  
(M.G.W. 2 940 kg and over) \_\_\_\_\_
  - (iv) No. Heavy Motor Vehicle \_\_\_\_\_ (viii) No. of Other Vehicle \_\_\_\_\_
- Agriculture \_\_\_\_\_ Industrial \_\_\_\_\_

*Motor Vehicles and Road Traffic*

**Chap. 48:50**

289

*Motor Vehicles and Road Traffic Regulations*

[Subsidiary]

- (c) Have you applied for Fleet Owner Compound Inspection previously?  
 Yes  No
- (d) Have you been granted Fleet Owner Compound Inspection approval previously?  
 Yes  No
- (e) If answer to (d) is "Yes" state period(s)

**D. VEHICLE TESTING ONLY**—(Testing to be conducted by Private Garage Personnel on Private Cars and Motorcycles)

(a) List all work/functions presently performed at Testing Compound \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

(b) State Mechanical Qualifications/Training/Experience of Owner Tester(s)  
\_\_\_\_\_  
\_\_\_\_\_

**E. COMPOUND FACILITIES**

- (a) Accommodation: (i) Staff  Yes  No (iii) Parking  Yes  No  
(ii) Brake Test Area  Yes  No (iv) Wash Room  Yes  No

(b) Equipment \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

(c) Inspection Pit: Dimension (i) Width \_\_\_\_\_ (iii) Depth \_\_\_\_\_  
(ii) Length \_\_\_\_\_ (iv) Height \_\_\_\_\_

(d) Ramp/Other \_\_\_\_\_

**F. SIGNATURE** \_\_\_\_\_ **DATE** \_\_\_\_\_

**FOR OFFICIAL USE**

Date Received \_\_\_\_\_ Date Referred To Assessment Committee \_\_\_\_\_

Committee's Recommendation:  Approved  Not Approved Date Referred to Transport Commissioner \_\_\_\_\_

TRANSPORT COMMISSIONER'S DECISION  APPROVED  NOT APPROVED

\_\_\_\_\_  
*Signature of Transport Commissioner*

\_\_\_\_\_  
*Date*

**APPENDIX XI**

**APPLICATION FOR INSPECTION DOCUMENTS**

1. NAME OF VEHICLE TESTING STATION: .....
  2. ADDRESS: .....
  3. NAME OF OWNER: .....
  4. ADDRESS (IF DIFFERENT FROM ABOVE): .....
  5. VEHICLE TESTING STATION NO.: .....
- |                            |       |         |
|----------------------------|-------|---------|
| Inspection Checklist       | ..... | book(s) |
| Certificate of Inspection  | ..... | book(s) |
| Inspection Sticker         | ..... | roll(s) |
| Monthly Return             | ..... | book(s) |
| Grievance/Complaint Notice | ..... | form    |

**I hereby apply for the issue of the above Inspection documents for use at the Vehicle Testing Station named above.**

\_\_\_\_\_  
*Signature of Owner/Proprietor*

\_\_\_\_\_  
*Date*

***For Official Use Only***

Cashier,

Please accept the sum of ..... for the purchase of .....

Document details:

Inspection Checklist Nos. ....	to .....	
Certificate of Inspection Nos. ....	to .....	
Inspection Sticker Nos. ....	to .....	
Monthly Return Nos. ....	to .....	

\_\_\_\_\_  
*For Transport Commissioner*



**APPENDIX XIII**

**MINISTRY OF WORKS AND TRANSPORT**

**COMPLAINT/GRIEVANCE NOTICE**

NAME .....

ADDRESS .....

.....

Phone No. ....

Complaint/Grievance (Give outline and essential facts below)

.....

.....

.....


.....

.....

Date .....

Signature .....

\_\_\_\_\_



**SEVENTH SCHEDULE**

Regulation 27C.

**PART I**

**PRIVATE GARAGE SIGN:**

**“MINISTRY OF WORKS AND TRANSPORT**

**TRANSPORT DIVISION**

**APPROVED MOTOR VEHICLE TESTING STATION**

NO. ....”.

The sign shall be 48" x 52"; the colour shall be white lettering on a black background: and the material shall be Scotch Lite Reflecting Sheeting. The sign shall be mounted on a round steel post.

**PART II**

**CONDITIONS AS TO ERECTION OF PRIVATE GARAGE SIGN**

1. The sign shall be securely fixed against a wall of the vehicle testing station.
2. The sign shall be so exhibited that no part thereof is above the fascia level of the vehicle testing station or above fifteen feet from the ground, whichever is the lower.
3. Not more than one sign shall be displayed on each road frontage.

137/1978.

### SAFETY HELMETS NOTIFICATION

*made under section 43(3)*

The Minister hereby prescribes [as helmets capable of affording the head of the wearer protection from injury in the event of an accident, within the meaning of section 43(3) of the Act] safety helmets which, in design, construction and other quality, comply and carry the appropriate mark of compliance with any of the following standards:

American National Standard	... 290.1-1971	Specifications for protective headgear for vehicle users.
Australian Standard	... AS 1698-1974	Protective Helmets for vehicle users.
British Standard	... BS 2001	Protective Helmets for motor cyclists.
British Standard	... BS 2495-1977	Protective Helmets for vehicle users (high protection).
British Standard	... BS 5361-1976	Protective Helmets for vehicle users.
Canadian Standard	... CSA D230-1970	Safety Helmets for motorcycle riders.
Emergency Indian Standard	... IS:4151E-1968	Safety Helmets for road users.
International Standards Organisation	ISO/R1511-1970	Protective Helmets for road users.
Swedish Standard	... SIS 88 24 11-1976	Protective Helmets for road users. Requirements.

**SPECIAL SPEED LIMITS ORDER**

\*[210/1979.  
265/2013].

*made under section 62(2)*

1. This Order may be cited as the Special Speed Limits Order. Citation.

2. The special speed limits specified in the fourth column of the Schedule are hereby imposed with respect to the roads specified in the first column of the said Schedule in relation to the classes or descriptions of motor vehicles specified in the second column and during the periods specified in the third column of the said Schedule. Speed limits.

**SCHEDULE**

	Road	Class or Description of Motor Vehicle	Time	Special Speed Limit kilometres per hour
1	The Priority Bus Route	All classes of authorised vehicles	at all times	65
2	<i>Lady Young Road</i> in the County of St. George from a point of intersection with the Eastern Main Road to the 3-kilometre post, <i>Lady Young Road</i> from the 6-kilometre post to the junction of the St. Ann's Road	All motor vehicles except a tractor, and in this provision tractor does not include a goods vehicle or private motor car with or without trailer	at all times	50
3	That part of the Eastern Main Road situated in the County of St. George West which starts from a point 45 metres West of Sixth Avenue and continuing to a point 45 metres East of the said avenue	All motor vehicles except a tractor, and in this provision tractor does not include a goods vehicle or private motor car with or without trailer	from 6.00 a.m. to 6.00 p.m. daily	25
4	That part of the Paria Main Road situated in the County of St. George, which passes through Maracas Bay, commencing with the 130-kilometre mark and running in a more or less westerly direction for a distance of 755 metres to the junction of the said road with the North Coast Road	Motor vehicles generally	at all times	25

\*For further amendments to this Order, See LN 153/2017; LN 16/2018, LN 54/2018, LN 139/2018; 398/2019 and 94/2024.

296      **Chap. 48:50**      *Motor Vehicles and Road Traffic*

**[Subsidiary]**      *Special Speed Limits Order*

	Road	Class or Description of Motor Vehicle	Time	Special Speed Limit kilometres per hour
5	That part of the Manzanilla-Mayaro Road situated in the Ward of Turure in the County of St. Andrew, which passes through the Cocal Estate Compound, commencing with the 70-kilometre mark and running in a more or less southerly direction for a distance of 400 metres to the 70-kilometre mark on the said road	(a) Tractor (except a goods vehicle <i>or private motor car</i> with or without a trailer)	at all times	15
		(b) Any other motor vehicle	at all times	25
6	Mayaro Beach in the County of Mayaro and Manzanilla Beach in the Counties of St. Andrew and St. David	Motor vehicles generally	at all times	25
7	That part of the Uriah Butler Highway in the vicinity of Grand Bazaar Mall situated in the County of St. George commencing at the southern end of Grand Bazaar Limited and continuing to the intersection with the Eastern Main Road	(a) All motor vehicles except a tractor  (b) Tractor does not include a goods vehicle or private motor car with or without a trailer	at all times	60

**SPEED LIMITS (BUILT-UP AREAS) ORDER**

\*[209/1979.  
166/2013].

*made under section 62(2)*

1. This Order may be cited as the Speed Limits (Built-up Areas) Order. Citation.

2. The roads or portions of roads specified in the Schedule are hereby declared to be built-up areas for the purposes of section 62 of the Act. Built-up areas.

**SCHEDULE**

1. All roads in that area bounded as follows:
  - (a) North—by a line running due East and West of the two-kilometre post on the Saddle Road;
  - (b) South—by the Churchill-Roosevelt Highway from its intersection with the Eastern Main Road and thence by its northern boundary eastward;
  - (c) East—by the Mausica Road;
  - (d) West—by the western boundary of the City of Port-of-Spain.
2. All roads in that area bounded as follows:
  - (a) North—from the Bridge on the Maraval River at the north-eastern end of Jamaica Boulevard thence in a westerly direction to a drain running along the southern boundary of Ellerslie Park and continuing due West along the said drain through lands leased to the entrance to Civil Service Association Club;
  - (b) South—thence in an easterly direction along the said drain to Jamaica Boulevard and running South along the western side of Jamaica Boulevard to the Maraval River;
  - (c) East—continuing in a northerly direction along the Maraval River to the point of commencement;
  - (d) West—continuing in a southerly direction along Long Circular Road to Barbados Road and eastwards along the southern side of Barbados Road to and along a drain running along the eastern boundary of the St. James Barracks to another drain at the north-western boundary of St. Mary's College Grounds.

3. Western Main Road from the junction of the Diego Martin Main Road, Cocorite to the western end of Scotland Bay.

\*For further amendments to this Order, See LN 152/2017.

4. Long Circular Road.
5. Saddle Road.
6. Diego Martin Main Road.
7. Beetham Highway from its intersection with Wrightson Road to the flyover in the vicinity of the Central Market (also commonly known as the “NP Flyover”).
8. St. Ann’s Road—from its intersection with the Lady Young Road to the Simon Valley Road.
9. Coblenz Avenue—from its intersection with St. Ann’s Road to its intersection with Cascade Road.
10. Cascade Road—from its intersection with St. Ann’s Road to Knightsbridge.
11. Eastern Main Road—from its intersection with the boundary of the City of Port-of-Spain to the thirty-kilometre post on the Eastern Main Road.
12. North Coast Road.
13. Morne Coco Road.
14. All roads in St. Joseph bounded as follows:
  - North and East—by the St. Joseph River.
  - South—by the Eastern Main Road.
  - West—by a straight line running from the culvert on the Eastern Main Road near the entrance to the old Railway Station in a northerly direction to the ford of the St. Joseph River on the road to Maracas nearest to the Town of St. Joseph.
15. All roads in Tunapuna bounded as follows:
  - North—Northern boundary of Chinab’s land and a line running due East and West from that line.
  - South—Railway line.
  - East—Back Street (East) and a line running due North and South from that street.
  - West—The boundary of the area formerly known as St. Joseph’s Ward.
16. Arima-Blanchisseuse Road.
17. The Eastern Main Road from Guaico to Sangre Grande (i.e., from the forty-five-kilometre mark to the fifty-kilometre mark).

18. All roads in Sangre Grande bounded as follows:

North—A line drawn from the north-eastern boundary of block of six hectares of land, the property of the heirs of C. F. Sellier, crossing the Warner or Cuare Road and running in a westerly direction along the northern boundary of the said block and the northern boundary of lands of Rampersad, Jeebodh and Sookaie to the Picton Trace.

South—The Cunapo River.

East—A line drawn from the Cunapo River along the eastern boundary of a four hectares block of land formerly the property of A. Brooks, now of the heirs of C. F. Sellier crossing the Sangre Grande-Oropouche Road and along the eastern boundary of a two and a half hectares block of land formerly the property of P. Ojoe, now of the heirs of C. F. Sellier and thence in a northerly direction to the northern boundary of the lands of J. Ojoe now F. Cumberbatch, thence in a westerly direction to the south-eastern corner of a one and a half hectares block of land the property of the heirs of C. F. Sellier, thence running North along the eastern boundary of the said one and a half hectares block of land and lands of M. Warner now of Philip Acham and lands of heirs of C. F. Sellier (six hectares) to the north-eastern boundary of the said block of land.

West—A line drawn along the Picton Trace to the Eastern Main Road, and thence in a straight line running South to the Cunapo River.

19. The portion of the Paria Main Road between Toco and Matelot.

20. The portion of the Toco Main Road, in the County of St. David commencing at the four-kilometre post and ending at the six-kilometre post.

21. Manzanilla Beach Road.

22. Manzanilla-Mayaro Road from the Eastern Main Road to the southern side of the Nariva Bridge.

23. That portion of the Manzanilla-Mayaro Road commencing at the eighty-five-kilometre mark and ending at the eighty-five-kilometre mark on the said Manzanilla-Mayaro Road.

24. Cunapo Southern Road—

- (a) in the County of St. Andrew, between the four-kilometre mark and the ten-kilometre mark; and
- (b) in the County of Nariva, between the twenty-five-kilometre mark and the thirty-five-kilometre mark.

25. Caroni South Bank Road, Kelly Village, County of Caroni between the two-kilometre mark and St. Helena Junction.

26. Caroni Savannah Road from Chaguanas to its junction with the South Trunk Road, Charlieville.

27. All roads lying within the radius of two kilometres of the Magistrate's Court, Chaguanas.

28. Southern Main Road, County of Caroni, between the nine-kilometre mark and the fifteen-kilometre mark.

29. Chaguanas Main Road in the County of Caroni.

30. Cacandee Road, Chaguanas in the County of Caroni.

31. Southern Main Road, one hundred and eighty-five metres East of Calcutta Road No. 3 (Deonarine Junction) in the County of Caroni.

32. Southern Main Road, four hundred and seventy-five metres West of Calcutta Road No. 3 (Deonarine Junction) in the County of Caroni.

33. Southern Main Road, one hundred and eighty-five metres East of St. Mary's Junction, Freeport in the County of Caroni.

34. Southern Main Road, one hundred and eighty-five metres West of St. Mary's Junction, Freeport in the County of Caroni.

35. Southern Main Road—from the thirty-five-kilometre mark to the forty-kilometre mark (i.e., that portion of the Southern Main Road which passes through California Village).

36. Southern Main Road—

- (a) from its junction with the Churchill-Roosevelt Highway to the ten-kilometre post or mark;
- (b) from its junction with the Princess Margaret Highway to the twenty-five-kilometre post or mark;
- (c) from the forty-five-kilometre post or mark to the boundary of the Borough of San Fernando.

37. Couva bounded as follows:

North—By a line parallel to the Couva Main Road running from the Waterloo Road to the north-western corner of the Anglican Church Lands, then running along the northern boundary of the Anglican Church Lands to the north-eastern corner of the said lands, thence in a straight line to the north-western corner of the Glebe Lands, three hectares, thence in an easterly direction along the northern boundary of the Glebe Lands crossing Carlos Street to a point

on the eastern boundary of an estate trace; thence in a northerly direction along the eastern boundary of the said trace to a point at its intersection with the southern boundary of the so-called Perseverance Exchange Road, thence easterly along the southern boundary of the said road to the junction of Exchange Road, thence in a general southerly direction along the western boundary of the said road to the north-eastern corner of the parcel of land now or formerly owned by H. L. Jobity, thence in a due East direction crossing the Exchange Road and the Trinidad Government Railway line to a point on the western boundary of the Southern Main Road.

South—By a due West line running from the southern extremity of the eastern boundary on the Couva River to a point lying due South of the junction of the Couva River and Waterloo Roads.

East—By the Southern Main Road, Isaac Street and a due South line from the southern end of Isaac Street to the Couva River.

West—By the Waterloo Road and by a line running due South from the junction of this road with the Couva River Road to the western end of the southern boundary.

38. That portion of the Southern Main Road, commencing at its intersection with the boundary of the City of San Fernando on its southern side, and thence running in a southerly direction and ending at the sixty-kilometre mark.

39. The San Fernando-Siparia-Erin Road at its intersection with Ramsamooj Trace, and thence running in a southerly direction and ending at the Mohess Road Junction.

40. That portion of the San Fernando-Siparia-Erin Road between the five-kilometre mark in the County of Victoria and the forty-kilometre mark in the County of St. Patrick.

41. Guaracara-Tabaquite Road from the junction with the Southern Main Road, Marabella, to a point one hundred and fifty-five metres east of the Harmony Hall Road.

42. From the intersection of Bonne Aventure Road and Charles Street to a point East adjacent to the four-kilometre post on Bonne Aventure Road.

43. The entire length of Harmony Hall Road from the intersection of the Guaracara-Tabaquite Road to the Bonne Aventure Road.

44. Princes Town bounded as follows:

North—by the southern boundary of the Malgretoute Estate from the point where it leaves the eastern boundary of the Cedar Hill Estate to the old Ciperó Tramline, thence along the old Ciperó Tramline to the Glenroy Estate

boundary on the Naparima-Mayaro Road, thence along the southern boundary of the Glenroy Estate to the north-western corner of the Birken Hill Estate which now forms part of Buen Intento Estate.

South—by the northern boundary of the Lothians Estate from the south-eastern corner of the Navette public burial ground to the south-eastern corner of the Cedar Hill Estate.

East—by the western boundary of the said Birken Hill Estate to the north-western corner of the Knolly's Recreation Ground, thence along the northern and eastern boundaries of Knolly's Recreation Ground and the southern boundary of the said Birken Hill Estate to the western boundary of the Craignish Estate and along the western boundary of the said Craignish Estate to the Naparima-Mayaro Road and along that road in a south-westerly direction to the western boundary of the Brömmage Estate and along that boundary to where it meets the eastern boundary of the Lothians Estate, thence in a straight line running in a more or less south-westerly direction to the south-eastern corner of the Navette public burial ground.

West—by the eastern boundary of the Cedar Hill Estate from its south-eastern corner to the point where it meets the southern boundary of the Malgretoute Estate.

45. Manahambre Road commencing at the three-kilometre mark of the Naparima-Mayaro Road and thence running in a south-easterly direction for a distance of four kilometres to the junction with St. Charles Road and thence continuing in a north-easterly direction ending at its junction at the twelve-kilometre mark of the Naparima-Mayaro Road in the County of Victoria.

46. Naparima-Mayaro Road from the twenty-five-kilometre post or mark to the thirty-kilometre post or mark.

47. All roads lying within a radius of two kilometres of the Police Station, Oropouche.

48. All roads lying within a radius of three kilometres of the junction of the Fyzabad Road with the Fyzabad-Guapo Road.

49. Clarke Road in the County of St. Patrick and all roads lying within a radius of five kilometres of the Penal Police Station.

50. All roads lying within a radius of three kilometres of the Magistrate's Court, Siparia.

51. That portion of the Southern Main Road in the Vessigny Area commencing at the eighty-kilometre post and ending at the ninety-kilometre post.

52. Southern Main Road, Rousillac Village, La Brea, between the seventy and the seventy-five-kilometre marks, in the County of St. Patrick.

53. All roads lying within a radius of three kilometres of the Police Station, Point Fortin.

54. All roads lying within a radius of two kilometres from the Rest House at Cedros.

55. That portion of Fullerton Road, Icacos, which lies between Columbia Road on the West and Fullerton Beach on the East.

56. Southern Main Road, Fullerton—from a point approximately one hundred and eighty-five metres West of the one hundred and twenty kilometre-mark and continuing in a westerly direction to a point one hundred and eighty-five metres West of the one hundred and twenty-kilometre mark.

57. The entire Fullerton Beach Road from the Southern Main Road to the Beach.

58. Mayaro-Guayaguayare Road—from nought to the seven-kilometre mark and from the fifteen-kilometre mark to the twenty-kilometre mark.

59. All roads in the Island Ward of Tobago.

[Subsidiary]

46/1957.

**SPECIAL SPEED LIMITS (BRIDGES) ORDER**

*made under section 62(3)*

Citation and commencement.

**1.** (1) This Order may be cited as the Special Speed Limits (Bridges) Order.

(2) This Order shall come into operation on the date of commencement of the Motor Vehicles and Road Traffic (Amendment) Ordinance, 1956.

Speed limits.

**2.** The special speed limits specified in the second column of the Schedule are hereby imposed in respect of the bridges over which roads pass, which bridges and roads are specified in the first column of the said Schedule, in relation to motor vehicles generally.

---

**SCHEDULE**

<i>Bridges and Roads</i>	<i>Special Speed Limit (kilometres per hour)</i>
<b>1. COUNTY OF ST. GEORGE</b>	
(a) B1/2—Saddle Road ... ..	15
(b) B1/5—Maracas Royal Road ... ..	15
<b>2. COUNTY OF CARONI</b>	
B1/14 over Honda River—Southern Main Road	15
<b>3. COUNTY OF ST. ANDREW</b>	
(a) B1/37—Eastern Main Road ... ..	15
(b) Nariva Bridge—75-kilometre mark Manzanilla-Mayaro Road ... ..	10
<b>4. COUNTY OF VICTORIA</b>	
(a) B1/1—Harmony Hall Road ... ..	15
(b) B3/6—San Fernando-Siparia-Erin Road ... ..	10
(c) B1/41—Godineau Bridge—Southern Main Road	15
<b>5. COUNTY OF NARIVA-MAYARO</b>	
B3/2—Rio Claro-Guayaguayare Road ... ..	15

---

**ROAD TRAFFIC (PROHIBITED PARKING) ORDER**

\*206/1979.

*made under section 65*

1. This Order may be cited as the Road Traffic (Prohibited Parking) Order. Citation.

2. (1) No person shall cause or permit any vehicle to be or to remain parked on any of the roads specified in the First Schedule. Parking of vehicle.

(2) No person shall cause or permit any vehicle to be or to remain parked on a road described in the first column of the Second Schedule on the days and, where applicable, during the hours specified in the second column of the said Schedule.

3. Any person who contravenes the provisions of clause 2 is liable on summary conviction to a fine of five hundred dollars or to imprisonment for three months. Offence. [47 of 1980].

---

**FIRST SCHEDULE**

**PART A**

**COUNTY OF CARONI**

1. Chaguanas Main Road between the Southern Main Road Junction and the South-bound Overpass on the Solomon Hochoy Highway.

2. The surfaced portion of the Princess Margaret Highway from the Caroni River Bridge to the Chaguanas Overpass.

**PART B**

**COUNTY OF MAYARO**

**ROAD**

1. Naparima-Mayaro Road from its junction with Pierreville Village Street and extending in an easterly direction to a point 45 metres East of its junction with Manzanilla-Mayaro Road.

---

\*This Order has been amended by the following: LN 220/1980; LN 148/1983; LN 117/1984; LN 75/1985, LN 114/1985; LN 138/1986, LN 184/1986; LN 69/2013, LN 176/2013, LN 268/2013; LN 56/2016; Act No. 9 of 2017 and LN 143/2017.

2. Manzanilla-Mayaro Road from its junction with Naparima-Mayaro Road and extending in a northerly direction for a distance of 45 metres.

3. Peter Hill Trace from its junction with Naparima-Mayaro Road and extending in a northerly direction for a distance of 50 metres.

4. Guayaguayare Road from its junction with Naparima-Mayaro Road and extending in a southerly direction to a point 10 metres South of the Mayaro Post Office.

**PART C**

**COUNTY OF NARIVA**

**ROAD**

Rio Claro-Tabaquite Road from its junction with Naparima-Mayaro Road and extending in a northerly direction for a distance of one hundred metres.

**PART D**

**COUNTY OF ST. ANDREW**

**ROAD**

1. Eastern Main Road from its junction with Toco Road at the Roundabout and extending in a southerly direction for a distance of 185 metres.

2. Eastern Main Road from its junction with Ojoe Road at the Roundabout and extending in a westerly direction to the junction of Picton Road.

3. Andre Street between Cunapo Southern Road and Eastern Main Road.

4. Cunapo Southern Road between Eastern Main Road and Mary Street.

5. Mary Street between Cunapo Southern Road and George Street.

6. George Street between Eastern Main Road and Mary Street.

7. Toco Road from its junction with Eastern Main Road at the Roundabout and extending in an easterly direction to the junction of Henderson Street.

8. Brierley Street between Riverside Extension Road and Foster Local Road, between 6.00 a.m. and 6.00 p.m. daily, Sundays and Public Holidays not included.

9. Old Railway Road West, from its junction with Eastern Main Road and Riverside Extension Road.

**PART E**

**COUNTY OF ST. DAVID**

NIL

**PART F**

**COUNTY OF ST. GEORGE EAST**

**ROAD**

1. Golden Grove Road from the intersection of the Churchill-Roosevelt Highway to a point sixty metres East of the exit gate of the Piarco International Airport.
2. Southern Main Road, Curepe, from its junction South of the Churchill-Roosevelt Highway to a point four hundred and sixty metres in a southerly direction.
3. Southern portion of Broadway in the Borough of Arima from a point twenty-five metres East of Queen Street.
4. Cocorite Street in the Borough of Arima between Broadway and Green Street.
5. Queen Street in the Borough of Arima from Broadway to a point sixty metres South.
- 5A. Queen Street, eastern side between Farfan Street and Devenish Street.
6. The surfaced portion of the Churchill-Roosevelt Highway.
7. The surfaced portion of the Princess Margaret Highway from its junction with the Churchill-Roosevelt Highway to the Caroni River Bridge.

**PART G**

**COUNTY OF ST. GEORGE WEST**

**ROAD**

1. Lady Chancellor Road in the Ward of St. Ann's between the eight hundred-metre post from its junction with Circular Road to the three-kilometre post.
2. Cascade Road, St. Ann's between Spring Bank Avenue and Walker Avenue.

3. Nook Avenue, situate at St. Ann's.
4. La Fantasie Road in the Ward of St. Ann's.
5. Reid Lane, Belmont, in the City of Port-of-Spain between Belmont Circular Road and Norfolk Street.
6. Albion Street between Dundonald Street and Stanmore Avenue in the City of Port-of-Spain.
7. Melville Lane in the City of Port-of-Spain.
8. Gordon Street between Pembroke Street and Frederick Street in the City of Port-of-Spain.
9. Fitzgerald Lane in the City of Port-of-Spain.
10. Darbain Lane in the City of Port-of-Spain.
11. New Street between Frederick Street and Pembroke Street in the City of Port-of-Spain.
12. Frederick Street between New Street and Gordon Street in the City of Port-of-Spain.
13. Pembroke Street between Gordon Street and New Street in the City of Port-of-Spain.
14. Park Street between Piccadilly Street and Charlotte Street in the City of Port-of-Spain.
15. Charlotte Street between Observatory Street and Park Street in the City of Port-of-Spain.
16. Edward Street from a point ninety metres South of the intersection of Sackville and Edward Streets extending further South to a point one hundred metres South of the said intersection in the City of Port-of-Spain.
17. Edward Street, Port-of-Spain, from a point commencing five metres South of vehicle entrance of "Trinidad House" and continuing to a point five metres North of the said entrance.
18. Edward Street, Port-of-Spain, between Independence Square North and Independence Square South.

19. Richmond Street between Fraser Street and Park Street in the City of Port-of-Spain.

20. Queen Street in the City of Port-of-Spain between Frederick Street and Chacon Street.

21. Harvey Street in the City of Port-of-Spain.

22. The surfaced portion of the Beetham Highway situated in the Ward of St. Ann's not including that portion appearing under Part "G" of the First Schedule to the Miscellaneous Roads (Unilateral Parking) Order.

23. Wrightson Road between Edward and St. Vincent Streets in the City of Port-of-Spain.

24. Long Circular Road in the Ward of St. Ann's between Patna Street and Dibe Road.

25. Long Circular Road, Maraval, in the City of Port-of-Spain at the entrance of Camp Ogden, from points ten metres North and South of the said entrance.

26. Tragarete Road in the City of Port-of-Spain between Damian Street and the western end of Serpentine Road.

27. Lucknow Street between Hyderabad Street and Panka Street in the City of Port-of-Spain.

28. Panka Street between Lucknow Street and Gaston-Johnston Street in the City of Port-of-Spain.

29. Delhi and Kathleen Streets, St. James.

30. Morne Coco Road ninety metres North and South of the Crystal Stream Avenue in the Ward of Diego Martin.

31. Western Main Road commencing at the twelve-kilometre post or mark and ending a distance of one and a half kilometres, measured along the said Road, West of that post or mark in Carenage.

32. Quarry-Prizgar Road between Old St. Joseph Road and a point two hundred and seventy-five metres North of Old St. Joseph Road through Prizgar Lands.

33. Jogie Road in the Ward of St. Ann's between Fifth Street, Barataria and the Eastern Main Road.

34. First Street, San Juan, in the Ward of St. Ann's between Second Street and a point one hundred and forty metres North of Second Street.

35. Second Street, San Juan, in the Ward of St. Ann's between Saddle Road and First Avenue, not including those portions appointed as Taxi Stands.

36. Real Street, San Juan, in the Ward of St. Ann's between Saddle Road and San Juan Street.

37. Saddle Road, San Juan, in the Ward of St. Ann's between Eastern Main Road and Mission Road.

38. Saddle Road, North of the fifteen-kilometre post for a distance of one hundred and sixty-five metres in the Ward of St. Ann's.

38A. Mission Road, San Juan in the Ward of St. Ann's between Saddle Road and Rosemin Drive.

39. Mount Lambert Circular Road in the Ward of St. Ann's between the Priority Bus Route and First Avenue.

40. The surfaced portion of the Churchill-Roosevelt Highway.

41. Duke Street between Melbourne Street and Richmond Street, in the City of Port-of-Spain.

42. Production Avenue, Sea Lots, Port-of-Spain.

42A. Hayes Street, St. Clair—southern side between Elizabeth Street and Alexandra Street.

43. Sierra Leone Road between the Diego Martin Main Road and St. Lucien Road.

44. St. Lucien Road between Sierra Leone Road and Majuba Cross Road.

**PART H**

**COUNTY OF ST. PATRICK**

**ROAD**

Oropouche Road situated between the junction of the said road with the Delhi Settlement Road and the Fyzabad Road.

**PART I**

**TOBAGO**

**ROAD**

1. Carrington Street from the junction of Burnett Street to Crooks River Bridge, Scarborough.

2. Bacolet Street from the junction of Main Street to the southern end of the New County Hall, Scarborough.

3. Bacolet Street, Tobago, from a point ninety metres East of the entrance to the Temporary Court House and Police Station extending in a westerly direction for a distance of one hundred and eighty-five metres, Scarborough.

4. North Side Road from Crooks River Bridge to the southern side of the Botanic Station, Scarborough.

5. Wilson Road between Milford and Darrel Spring Roads, Scarborough.

**PART J**

**COUNTY OF VICTORIA**

**ROAD**

1. Court Street between Lewis Street and Harris Street, San Fernando.

2. *(Deleted by LN 152/1981).*

3. Circular Road, from a point ninety metres East of London Street to a point ninety metres West of London Street, San Fernando.

4. Penitence Street between High Street and San Fernando Street, San Fernando.

5. Penitence Street between Court Street and Harris Promenade (North), San Fernando.

6. Lord Street between Coffee Street and Mucurapo Street, San Fernando.

7. Mon Chagrin Street between High Street and St. James Street, San Fernando.

8. Hollis Street, San Fernando.

9. Paradise Street, San Fernando.

10. Hubert Rance Street between Vistabella Road and a point one hundred and eighty-five metres North of Boodoosingh Street, San Fernando.

11. St. James Street between Penitence Street and High Street, San Fernando.

12. Ciperio Street between Coffee Street and a point thirty-five metres South of Coffee Street, San Fernando.

13. Coffee Street between Library Corner and a point forty-five metres East of Johnstone Street, San Fernando.

14. Keate Street between Prince Alfred Street and Gransaul Street, San Fernando.

15. Chancery Lane, San Fernando.

16. Mucurapo Street between Lord Street and Library Corner, San Fernando.

17. Quenca Street between San Fernando Street and High Street, San Fernando.

18. Pointe-a-Pierre Road between High Street and Short Street, San Fernando.

19. Pointe-a-Pierre Road between a point thirty metres North of Mount Moriah Road and a point thirty metres North of Chacon Street, San Fernando.

20. Scott Street between Ciperio Street and Villain Street, San Fernando.

21. La Pique Road, San Fernando.

22. Cemetery Street in the Borough of San Fernando between Harris Promenade and Lord Street.

23. Independence Avenue, San Fernando between Keate Street and Harris Promenade.

24. Southern Main Road from Cross Crossing to the Union Roundabout, San Fernando.

25. Guaracara-Tabaquite Road between Southern Main Road and a point forty-five metres eastwards, San Fernando.

26. San Fernando Bye-Pass, in the Ward of Naparima, which commences at the fifty-kilometre mark, Southern Road (the Marabella Roundabout) and ends at the fifty-five-kilometre mark on the said Southern Road (the Union Hall Roundabout), San Fernando.

**SECOND SCHEDULE**

COUNTY OF ST. GEORGE WEST

1. St. Joseph Road in the City of Port-of-Spain  
Monday to Friday  
between 6.00 a.m. and 9.00 a.m.
2. Independence Square South in the City of Port-of-Spain  
Monday to Friday  
between 6.00 a.m. and 9.00 a.m.
3. Church Street, St. James, between Brunton Road and  
Bournes Road  
Monday to Friday  
between 6.00 a.m. and 6.00 p.m.

TOBAGO

1. Piggott Street between Bacolet and Jerningham Streets,  
Scarborough  
between 6.00 a.m. and 6.00 p.m.
2. Burnett Street South of Main Street, Scarborough  
between 6.00 a.m. and 6.00 p.m.
3. Burnett Street from the junction of Carrington Street to  
Main Street, Scarborough  
between 6.00 a.m. and 6.00 p.m.
4. Castries Street from the junction of Carrington Street to  
Main Street, Scarborough  
between 6.00 a.m. and 6.00 p.m.
5. Mount Marie Road, Scarborough  
between 6.00 a.m. and 9.00 p.m.  
and  
between 3.00 p.m. and 6.00 p.m.

[Subsidiary]

207/1979.  
[220/1980  
75/1985  
69/2013  
176/2013  
182/2013  
268/2013  
56/2016  
9 of 2017  
143/2017].

Citation.

Parking of  
vehicle.

Offence.  
[69/2013  
9 of 2017].

**MISCELLANEOUS ROADS  
(UNILATERAL PARKING) ORDER**

*made under section 65*

1. This Order may be cited as Miscellaneous Roads (Unilateral Parking) Order.

2. No person shall cause or permit a vehicle to be or to remain parked on any road described in the first column of the Schedule on the side of such road and, where applicable, on the days or at the times mentioned in the second column of the said Schedule.

3. Any person who contravenes any of the provisions of clause 2 is liable on summary conviction to a fine of five hundred dollars.

**SCHEDULE**

**PART A**

**COUNTY OF CARONI**

Nil

**PART B**

**COUNTY OF MAYARO**

Nil

**PART C**

**COUNTY OF NARIVA**

<i>Road</i>	<i>Side of Road</i>
1. Naparima-Mayaro Road from its junction with Rio Claro-Tabaquite Road and extending for a distance of 75 metres	Southern
2. Naparima-Mayaro Road from its junction with Rio Claro-Tabaquite Road and extending for a distance of 20 metres	Northern
3. Rio Claro-Tabaquite Road from a point 100 metres from its junction with Naparima-Mayaro Road and extending in a northerly direction for a distance of 150 metres.	Eastern

**PART D**

**COUNTY OF ST. ANDREW**

<i>Road</i>	<i>Side of Road</i>
1. Ojoe Road from its junction with the Main Road at the Roundabout and extending in a northerly direction for a distance of 40 metres	Eastern
2. Cunapo Southern Road from its junction with Andre Street and extending in a northerly direction for a distance of 70 metres	Western
3. Foster Local Road from its junction with Toco Road and extending in a northerly direction for a distance of 75 metres	Western
4. Old Railway Station Road East (Exit).	Western

**PART E**

**COUNTY OF ST. DAVID**

Nil

**PART F**

**COUNTY OF ST. GEORGE EAST**

<i>Road</i>	<i>Side of Road</i>
1. Riverside Road between the Eastern Main Road and Gordon Street	Eastern
2. Eastern Main Road between Orange Grove Road and Dinsley Junction	Southern
3. Hollis Avenue between John Shaw Avenue and King Street, Arima	Northern
4. Belle Smythe Street, between Agostini Street and Bushe Street	Eastern Monday to Friday between 6.00 a.m. and 4.00 p.m. Public holidays not included
5. Freeling Street, between Wells Street and Sheriff Street.	Western

**PART G**

**COUNTY OF ST. GEORGE WEST**

<i>Road</i>	<i>Side of Road</i>
1. St. Ann's Road between Lady Young Road and Simon Valley Road, St. Ann's	Eastern
2. Norfolk Street, Belmont in the City of Port-of-Spain between Jerningham Avenue and Erthig Road	Eastern
3. Queen's Park East, Port-of-Spain from St. Ann's Roundabout to the northern end of Charlotte Street	Eastern
4. Park Avenue, Queen's Park East in the City of Port-of-Spain	Southern
5. Queen's Park West between Queen's Park East and Frederick Street, Port-of-Spain	Southern
6. Queen's Park West from a point on that side of the road opposite to and central of Chancery Lane and continuing in a westerly direction for a distance of 30 metres in the City of Port-of-Spain	Northern
7. Keate Street between Queen's Park East and Frederick Street in the City of Port-of-Spain	Northern
8. <i>Deleted by LN 143/2017</i>	
9. <i>Deleted by LN 143/2017</i>	
10. Duke Street between Charlotte Street and George Street in the City of Port-of-Spain	Northern
10A. Duke Street between St.Vincent Street and Edward Street from a point nine metres west of St.Vincent Street and extending to a point forty-nine metres westwards, except for persons driving official motor vehicles of the Maritime Services Division, Ministry of Works and Transport	Southern Monday to Friday Northern
11. Knox Street in the City of Port-of-Spain from Frederick Street for a distance of 20 metres	Southern
12. Prince Street between Nelson Street and Duncan Street, Port-of-Spain	Southern
13. London Street in the City of Port-of-Spain	Southern
13A. Independence Square between Wrightson Road and Edward Street	

**COUNTY OF ST. GEORGE WEST—Continued**

<i>Road</i>	<i>Side of Road</i>
14. Independence Square North between St. Vincent Street and Frederick Street in the City of Port-of-Spain	Northern
15. Independence Square North between Henry Street and George Street in the City of Port-of-Spain	Northern
16. Piccadilly Street between Prince Street and Park Street in the City of Port-of-Spain	Western
17. Nelson Street between Independence Square North and South Quay in the City of Port-of-Spain	Western
18. Charlotte Street, Port-of-Spain from the junction of Queen's Park East to the junction of New Street	Eastern
19. Frederick Street between Queen's Park West and Keate Street, Port-of-Spain	Eastern
20. Chacon Street between Independence Square South and South Quay, Port-of-Spain	Western
21. St. Vincent Street, from Electric Pole No. 23 extending South for a distance of 20 metres in the City of Port-of-Spain	Western
22. St. Vincent Street, from the exit of the Red House Driveway (Southern Exit) South to Hart Street	Eastern
23. St. Vincent Street between Treasury Street and Independence Square North in the City of Port-of-Spain	Western
24. Edward Street between Park Street and Tragarete Road in the City of Port-of-Spain	Eastern
25. Edward Street, Port-of-Spain, between Independence Square South and Wrightson Road	Western
26. Tragarete Road between Edward Street and St. Vincent Street, Port-of-Spain	Northern
27. Flament Street, Port-of-Spain, between Park Street and Wrightson Road	Western
28. Beetham Highway Southern Carriageway between the Dry River and St. Vincent Street in the City of Port-of-Spain	Southern between 6.00 a.m. and 6.00 p.m.
29. Wrightson Road between signs on the Southern Carriageway from a point 10 metres East of the Entrance to the Flour Mill in the City of Port-of-Spain	Southern

<i>Road</i>	<i>Side of Road</i>
30. Maraval Road between Prada Street and St. Clair Avenue	Western
31. Mucurapo Road, Port-of-Spain, between Warren and Ethel Streets	Southern
31A. Rust Street	Southern
31B. Alcazar Street	Southern
31C. Marli Street	Southern
32. Gaston Johnson Street in the City of Port-of-Spain	Eastern
33. Panka Street, St. James between Nizam Street and Ethel Street	Southern
34. First Avenue, San Juan, in the Ward of St. Ann's between the Eastern Main Road and Second Street	Western
35. Colda Tinda Avenue, San Juan	Western Monday to Friday
36. First Street, San Juan, in the Ward of St. Ann's between Saddle Road and First Avenue	Southern
37. First Street, San Juan, in the Ward of St. Ann's from a point 140 metres North of Second Street to Saddle Road	Southern
38. Maracas Bay in the Ward of St. Ann's	Northern
39. Keate Street between Frederick Street and Pembroke Street, in the City of Port-of-Spain	Southern
40. Fitz Blackman Drive, in the City of Port-of-Spain.	Western
41. Benares Street, St. James	Western
42. Clarence Street, St. James	Western
43. Flood Street, St. Clair from Elizabeth Street to a point 60 metres west	Northern
44. Elizabeth Street, St. Clair from Flood Street to a point 30 metres north	Eastern
45. Tranquillity Street, in the City of Port-of-Spain	Southern
46. Murray Street, between Tragrete Road and Robert Street	Western Monday to Saturday
47. Rosalino Street	Western

**PART H**

**COUNTY OF ST. PATRICK**

<i>Road</i>	<i>Side of Road</i>
1. Penal Rock Road opposite the Taxi and Omnibus Stands for a distance of 35 metres in Penal	Eastern
2. Clarke Road, Penal, between Siparia Road and Penal Rock Road	Eastern
3. School Road, Point Fortin between Mainsfield Road and Guapo-Cap-de-Ville Road.	Southern

**PART I**

**TOBAGO**

<i>Road</i>	<i>Side of Road</i>
1. Milford Road from its junction with Wilson Road to a point 115 metres West, Scarborough	Southern between 6.00 a.m. and 6.00 p.m.
2. Milford Road from the western end of the Licensing Office to Government Farm Road, Scarborough	Northern
3. Milford Road from the junction of Orange Hill Road to Wilson Road, Scarborough	Northern
4. Ross Street from Piggott Street to Jerningham Street, Scarborough	Southern
5. Main Street from Fort Street to Castries Street, Scarborough	Southern
6. Piggott Street from Burnett Street to Jerningham Street, Scarborough	Northern
7. Piggott Street between Robinson and Bacolet Streets, Scarborough	Northern
8. Carrington Street between Castries and Exit Streets from Customs Area, Scarborough	Southern
9. Carrington Street from Wilson Road to a point 5 metres from the Truck Stand, Scarborough	Southern
10. Carrington Street from its junction with Castries Street and extending in a westerly direction to the Bailey Bridge, Scarborough	Northern
11. Jerningham Street from Ross Street to Piggott Street, Scarborough	Eastern
12. Entry Street to Customs Area, Scarborough.	Eastern

**PART J**

**COUNTY OF VICTORIA**

<i>Road</i>	<i>Side of Road</i>
1. King's Wharf (Eastern side of bus terminus) from a point 10 metres South of St. Vincent Street to Queen Street, San Fernando	Eastern
2. Queen Street, San Fernando	Northern
3. Harris Promenade North, San Fernando	Northern
4. Harris Promenade South, San Fernando	Southern
5. Library Street, San Fernando	Southern
6. Court Street from Harris Street to Lewis Street, San Fernando	Northern
7. Mucurapo Street from Cemetery Street to Lord Street, San Fernando	Eastern
8. Prince Alfred Street from Cemetery Street to Keate Street, San Fernando	Eastern
9. Ciperio Street from Ciperio Bridge to Scott Street, San Fernando	Western
10. Park Street from Ciperio Street to Todd Street, San Fernando	Northern
11. Buen Intento Road from the northern end of the Taxi Stand to Water Lane, Princes Town	Eastern
12. Railway Road, Princes Town	Eastern
13. Tramline Street, Princes Town	Northern
14. Naparima-Mayaro Road between King Street and Aldana Street, Princes Town	Western
15. Naparima-Mayaro Road from Railway Road to Buen Intento Road, Princes Town	Northern
16. Naparima-Mayaro Road between Railway Road and Lothians Road, Princes Town.	Southern

**MISCELLANEOUS ROADS (UNILATERAL  
ALTERNATE PARKING) ORDER**

[\*208/1979.  
220/1980  
75/1985].

*made under section 65*

1. This Order may be cited as the Miscellaneous Roads (Unilateral Alternate Parking) Order. Citation.

2. No person shall cause or permit a vehicle to be or to remain parked on any road described in the first column of the Schedule on the side of the road mentioned in the second column of the said Schedule on the days of the week and where applicable at the times mentioned in the third column of the said Schedule. Parking of vehicle.

3. No person shall cause or permit any bicycle to be or to remain parked on any of the roads mentioned in the Schedule, otherwise than the opposite side of the road to that on which other vehicles are required by the provisions of this Order, and when so parked shall be in line and not less than one metre the one from the other. Parking of bicycle.

4. Any person who contravenes any of the provisions of this Order is liable on summary conviction to a fine of five hundred dollars or to imprisonment for three months. Offence.

**SCHEDULE**

**PART A**

**COUNTY OF CARONI**

<i>Road</i>	<i>Side of Road</i>	<i>Day of Week and Time where Applicable</i>
1. Southern Main Road, Chaguanas between Longdenville Junction and Chaguanas Flyover	Northern	Tuesday, Thursday, Saturday
	Southern	Monday, Wednesday, Friday
2. That portion of Southern Main Road, Couva which lies between Isaac Junction and Carli Bay Road	Northern	Tuesday, Thursday, Saturday
	Southern	Sunday, Monday, Wednesday, Friday

\*See Legal Notices LN 69/2013, LN 176/2013, LN 268/2013; LN 25/2015; LN 56/2016; LN 48/2017, LN 143/2017 and Act No. 9 of 2017, for further amendments to this Order.

322 **Chap. 48:50** *Motor Vehicles and Road Traffic*  
 [Subsidiary] *Miscellaneous Roads (Unilateral Alternate Parking) Order*

<i>Road</i>	<i>Side of Road</i>	<i>Day of Week and Time where Applicable</i>
3. That portion of the Southern Main Road, Couva which lies between the 35-kilometre post and Isaac Junction	Eastern	Tuesday, Thursday, Saturday
4. That portion of the Southern Main Road, Couva which lies between the Carli Bay Road and Railway Station Road, California	Western	Sunday, Monday, Wednesday, Friday

**PART B**

**COUNTY OF MAYARO**

Nil

**PART C**

**COUNTY OF NARIVA**

Nil

**PART D**

**COUNTY OF ST. ANDREW**

<i>Road</i>	<i>Side of Road</i>	<i>Day of Week and Time where Applicable</i>
1. Eastern Main Road, Sangre Grande, not including—		
(i) that portion of the Eastern Main Road from its junction with Toco Road at the Roundabout and extending in a southerly direction for a distance of 185 metres	Northern	Sunday, Tuesday, Thursday, Saturday
(ii) that portion of the Eastern Main Road from its junction with Ojoe Road at the Roundabout and extending in a westerly direction to the junction of Picton Road	Southern	Monday, Wednesday, Friday
2. Toco Road, Sangre Grande, not including the Western portion between Henderson Street and the Eastern Main Road		

**PART E**

**COUNTY OF ST. DAVID**

Nil

**PART F**

**COUNTY OF ST. GEORGE EAST**

<i>Road</i>	<i>Side of Road</i>	<i>Day of Week and Time where Applicable</i>
1. That portion of Abercromby Street, St. Joseph in the County of St. George which lies between the Eastern Main Road and Riverside Road	Eastern	Tuesday, Thursday, Saturday
	Western	Sunday, Monday, Wednesday, Friday
2. Southern Main Road, Curepe in the Ward of St. Ann's	Eastern	Tuesday, Thursday, Saturday
	Western	Monday, Wednesday, Friday
3. Tunapuna Road, Tunapuna	Eastern	Tuesday, Thursday, Saturday
	Western	Sunday, Monday, Wednesday, Friday
4. That portion of Sorzano Street in the Borough of Arima which lies between Prince Street and St. Joseph Street		
5. That portion of Broadway in the Borough of Arima which lies between Queen Street and Prince Street	Northern	Monday, Wednesday, Friday
	Southern	Tuesday, Thursday, Saturday
6. That portion of Guanapo Street in the Borough of Arima which lies between Prince Street and Temple Street		
7. That portion of Green Street in the Borough of Arima which lies between Cocorite Street and St. Joseph Street		
8. That portion of Farfan Street in the Borough of Arima which lies between Cocorite Street and St. Joseph Street		
9. That portion of Hollis Avenue between King Street and Pro Queen Street	Northern	Monday, Wednesday, Friday
10. That portion of Devenish Street in the Borough of Arima which lies between Cocorite Street and Green Street	Southern	Tuesday, Thursday, Saturday
11. That portion of John Shaw Avenue in the Borough of Arima which lies between Providence Circular Road and Queen Mary Avenue		

324      **Chap. 48:50**      *Motor Vehicles and Road Traffic*  
[Subsidiary]      *Miscellaneous Roads (Unilateral Alternate Parking) Order*

<i>Road</i>	<i>Side of Road</i>	<i>Day of Week and Time where Applicable</i>
12. That portion of St. Joseph Street in the Borough of Arima which lies between Hollis Avenue and Sanchez Street		
13. That portion of Woodford Street in the Borough of Arima which lies between Hollis Avenue and Sorzano Street		
14. That portion of Prince Street in the Borough of Arima which lies between Broadway and Longden Street		
15. That portion of Queen Street in the Borough of Arima which lies between Sanchez Street and Hollis Avenue		
16. That portion of Pro Queen Street in the Borough of Arima which lies between Hollis Avenue and Railway Road	Eastern	Monday, Wednesday, Friday
17. That portion of Cocorite Street in the Borough of Arima which lies between Green Street and Devenish Street	Western	Tuesday, Thursday, Saturday
18. That portion of Railway Road in the Borough of Arima which lies between Robinson Circular Road and Pro-Queen Street		
19. That portion of O'Meara Road in the Borough of Arima which lies between Trinidad Government Railway Crossing and Churchill-Roosevelt Highway		
20. That portion of Industry Lane in the Borough of Arima which lies between Hollis Avenue and Rawle Circular		
21. That portion of King Street in the Borough of Arima which lies between Hollis Avenue and Sanchez Street		

**PART G**

**COUNTY OF ST. GEORGE WEST**

<i>Road</i>	<i>Side of Road</i>	<i>Day of Week and Time where Applicable</i>
1. Cascade Road situated in the Ward of St. Ann's which commences at the intersection of the St. Ann's Road with the Cascade Road and continues in a north-easterly direction to a point where the said Cascade Road meets Coblentz Avenue	Northern	Tuesday, Thursday and Saturday, between 8.00 a.m. and 8.00 p.m. Public Holidays not included
	Southern	Monday, Wednesday and Friday, between 8.00 a.m. and 8.00 p.m. Public Holidays not included
2. Cascade Road, from its intersection with Coblentz Avenue to Spring Bank Avenue	Northern	Tuesday, Thursday, Saturday
	Southern	Monday, Wednesday, Friday
3. Cascade Road, from Walker Avenue to Knightsbridge	Northern	Tuesday, Thursday, Saturday
4. Coblentz Avenue between St. Ann's Road and Cascade Road	Southern	Monday, Wednesday, Friday
5. Saddle Road in the Ward of St. Ann's between the St. Clair Roundabout and its junction with Long Circular Road, Port-of-Spain	Eastern	Tuesday, Thursday and Saturday
	Western	Sunday, Monday, Wednesday and Friday
6. Prada Street, St. Clair	Northern	Tuesday, Thursday and Saturday
7. <i>(Deleted by LN 75/1985)</i>		
8. Pelham Street, Belmont	Eastern	Sunday, Monday, Wednesday and Friday
	Western	Tuesday, Thursday and Saturday
9. Braithwaite Lane, Belmont	Eastern	Tuesday, Thursday and Saturday
	Western	Sunday, Monday, Wednesday and Friday
10. Willis Street, Belmont	Northern	Tuesday, Thursday and Saturday
	Southern	Sunday, Monday, Wednesday and Friday

**COUNTY OF ST. GEORGE WEST—Continued**

<i>Road</i>	<i>Side of Road</i>	<i>Day of Week and Time where Applicable</i>
11. Winton Lane, Belmont	Eastern	Tuesday, Thursday and Saturday
	Western	Sunday, Monday, Wednesday and Friday
12. Agard Lane, Belmont	} Northern	Tuesday, Thursday and Saturday
13. Altorf Street, Belmont		
14. St. Francois Valley Road, Belmont between Belmont Valley Road and Belmont Circular Road		
	} Southern	Sunday, Monday, Wednesday and Friday
15. Erthig Road between Norfolk Street and Belmont Circular Road	Northern	Tuesday, Thursday, Saturday
	Southern	Monday, Wednesday, Friday
16. Jerningham Avenue between Queen's Park East and Belmont Circular Road	Northern	Tuesday, Thursday, Saturday
	Southern	Monday, Wednesday, Friday
17. Norfolk Street commencing at the western intersection with Belmont Circular Road and ending at its northern intersection with the said Belmont Circular Road	} Eastern	Sunday, Tuesday, Thursday, Saturday
18. Belmont Circular Road between Belle Eau Road and Belmont Valley Road		
19. Belmont Circular Road between McShine Terrace and Norfolk Street		
20. Belmont Circular Road between Norfolk Street and Belle Eau Road	} Northern	Tuesday, Thursday, Saturday
21. Belmont Circular Road between Belmont Valley Road and Queen's Park East		
	} Southern	Monday, Wednesday, Friday
22. Belmont Circular Road between Charlotte Street and McShine Terrace		
23. McShine Terrace, Belmont	Northern	Tuesday, Thursday, Saturday
	Southern	Sunday, Monday, Wednesday, Friday
24. Observatory Street between Charlotte Street and Belmont Circular Road	Eastern	Sunday, Tuesday, Thursday, Saturday
	Western	Monday, Wednesday, Friday

*Motor Vehicles and Road Traffic*      **Chap. 48:50**

327

*Miscellaneous Roads (Unilateral Alternate Parking) Order*

**[Subsidiary]**

<i>Road</i>	<i>Side of Road</i>	<i>Day of Week and Time where Applicable</i>
25. Chancery Lane between Keate Street and Gordon Street	Eastern	Monday, Wednesday, Friday
	Western	Tuesday, Thursday, Saturday
26. Gordon Street between Charlotte and Frederick Streets	Northern	Sunday, Monday, Wednesday, Friday,
27. Gordon Street between Pembroke Street and Dundonald Street	Southern	Tuesday, Thursday, Saturday
28. New Street, Port-of-Spain between Dundonald Street and Victoria Avenue	Northern	Monday, Wednesday, Friday
	Southern	Tuesday, Thursday, Saturday
29. Park Street, Port-of-Spain between St. Vincent and Charlotte Streets	Northern	Tuesday, Thursday, Saturday
	Southern	Monday, Wednesday, Friday
30. Duke Street between George Street and Piccadilly Street	Northern	Tuesday, Thursday, Saturday
31. Duke Street, Port-of-Spain— (i) between Charlotte Street and Richmond Street;		
(ii) between Melbourne Street and Wrightson Road.		
32. Prince Street between Frederick Street and Nelson Street	Southern	Monday, Wednesday, Friday
33. Prince Street between Duncan Street and Piccadilly Street, Port-of-Spain	Northern	Tuesday, Thursday, Saturday
34. Sackville Street between St. Vincent Street and Wrightson Road		
35. Queen Street between Richmond Street and Chacon Street		
36. Queen Street between Frederick Street and Piccadilly Street	Southern	Monday, Wednesday, Friday
37. St. Joseph Road between the Eastern Main Road and Piccadilly Street	Northern	Tuesday, Thursday, Saturday
	Southern	Sunday, Monday, Wednesday, Friday
38. Old St. Joseph Road	Northern	Sunday, Monday, Wednesday, Friday
	Southern	Tuesday, Thursday, Saturday

**COUNTY OF ST. GEORGE WEST—Continued**

<i>Road</i>	<i>Side of Road</i>	<i>Day of Week and Time where Applicable</i>
39. Piccadilly Street in the City of Port-of-Spain between South Quay and St. Joseph Road	Eastern	Tuesday, Thursday, Saturday
	Western	Sunday, Monday, Wednesday, Friday
40. Duncan Street between Prince Street and South Quay	Eastern	Sunday, Tuesday, Thursday, Saturday
41. Nelson Street between Duke Street and South Quay		
42. George Street between Duke Street and South Quay		
43. Charlotte Street between Gordon Street and Observatory Street		
44. Charlotte Street between Park Street and South Quay		
45. Henry Street between Gordon Street and South Quay	Western	Monday, Wednesday, Friday
46. Frederick Street between Keate Street and Gordon Street	Eastern	Sunday, Tuesday, Thursday, Saturday
47. Frederick Street between New Street and Independence Square North		
48. Chacon Street between Queen Street and Independence Square South		
49. Pembroke Street between Keate Street and Gordon Street		
50. Pembroke Street between New Street and Knox Street		
51. Abercromby Street between Keate Street and South Quay	Western	Monday, Wednesday, Friday
52. St. Vincent Street between Gordon Street and Treasury Street, Port-of-Spain, but not including those portions of St. Vincent Street appearing under Head G of the First Schedule to the Miscellaneous Roads (Unilateral Parking) Order		
53. St. Vincent Street between Independence Square North and Independence Square South, Port-of-Spain		

*Motor Vehicles and Road Traffic* **Chap. 48:50**

329

*Miscellaneous Roads (Unilateral Alternate Parking) Order*

[Subsidiary]

<i>Road</i>	<i>Side of Road</i>	<i>Day of Week and Time where Applicable</i>
54. Edward Street in the City of Port-of-Spain between Tragarete Road and Gordon Street	Eastern	Tuesday, Thursday, Saturday
	Western	Sunday, Monday, Wednesday, Friday
55. Edward Street between Park Street and Independence Square North but not including those portions of Edward Street appearing under Head G of the First Schedule to the Road Traffic (Prohibited Parking) Order	Eastern	Sunday, Tuesday, Thursday, Saturday
	Western	Monday, Wednesday, Friday
56. Dundonald Street	Eastern	Tuesday, Thursday, Saturday
	Western	Sunday, Monday, Wednesday, Friday
57. Richmond Street between Tragarete Road and Fraser Street	Eastern	Monday, Wednesday, Friday
58. Richmond Street between Park Street and Independence Square South		
59. Francis Street between Sackville Street and Charles Street	Western	Sunday, Tuesday, Thursday, Saturday
60. Melbourne Street, Port-of-Spain	Eastern	Tuesday, Thursday, Saturday
	Western	Monday, Wednesday, Friday
61. Charles Street, Port-of-Spain	Northern	Tuesday, Thursday, Saturday
	Southern	Sunday, Monday, Wednesday, Friday
62. Borde Street between Tragarete Road and New Street	Eastern	Tuesday, Thursday, Saturday
63. Colville Street, from Wrightson Road to Tragarete Road	Western	Sunday, Monday, Wednesday, Friday
64. Methuen Street	Northern	Tuesday, Thursday, Saturday
65. McDonald Street	Southern	Monday, Wednesday, Friday

**COUNTY OF ST. GEORGE WEST—Continued**

<i>Road</i>	<i>Side of Road</i>	<i>Day of Week and Time where Applicable</i>
66. French Street between Tragarete Road and Ariapita Avenue	} Eastern	Tuesday, Thursday, Saturday
67. French Street, from Wrightson Road to Ariapita Avenue		
68. Maraval Road between Tragarete Road and Queen's Park West		
69. Cornelio Street, from Wrightson Road to Tragarete Road	} Western	Sunday, Monday, Wednesday, Friday
70. Tragarete Road between Damian Street and Edward Street	Northern	Monday, Wednesday, Friday
	Southern	Sunday, Tuesday, Thursday, Saturday
71. Luis Street between Roberts Street and Ariapita Avenue	Eastern	Tuesday, Thursday, Saturday
	Western	Sunday, Monday, Wednesday, Friday
72. Pole Carew Street, Woodbrook, between Warren Street and Tragarete Road	Eastern	Monday, Wednesday, Friday
	Western	Sunday, Tuesday, Thursday, Saturday
73. That portion of Warren Street in the City of Port-of-Spain which lies between Rosalino Street and Belle-Smythe Street	Northern	Tuesday, Thursday, Saturday
	Southern	Sunday, Monday, Wednesday, Friday
74. Warner Street between Cipriani Boulevard and Maraval Road		
75. Picton Street between Tragarete Road and Queen's Park West	Eastern	Tuesday, Thursday, Saturday
	Western	Sunday, Monday, Wednesday, Friday
76. Ana Street between Warren Street and Wrightson Road	Eastern	Sunday, Tuesday, Thursday, Saturday
	Western	Monday, Wednesday, Friday
77. Petra Street between Warren Street and Wrightson Road	Eastern	Sunday, Tuesday, Thursday, Saturday
	Western	Monday, Wednesday, Friday
78. Damian Street in the City of Port-of-Spain between Tragarete Road and Warren Street	Eastern	Tuesday, Thursday, Saturday
	Western	Sunday, Monday, Wednesday, Friday

*Motor Vehicles and Road Traffic*      **Chap. 48:50**

331

*Miscellaneous Roads (Unilateral Alternate Parking) Order*

**[Subsidiary]**

<i>Road</i>	<i>Side of Road</i>	<i>Day of Week and Time where Applicable</i>
79. Mucurapo Road between Ethel Street and Western Main Road	Northern	Sunday, Tuesday, Thursday, Saturday
	Southern	Monday, Wednesday, Friday
80. Lucknow Street between Hyderabad Street and Western Main Road in the City of Port-of-Spain	Northern	Tuesday, Thursday, Saturday
	Southern	Monday, Wednesday, Friday
81. Long Circular Road in the City of Port-of-Spain between Saddle Road and Dibe Road, Port-of-Spain	Northern	Tuesday, Thursday, Saturday
	Southern	Sunday, Monday, Wednesday, Friday
82. Bengal Street, St. James between the Western Main Road and Delhi Street	Eastern	Sunday, Tuesday, Thursday, Saturday between 6.00 a.m. and 6.00 p.m.
	Western	Monday, Wednesday, Friday, between 6.00 a.m. and 6.00 p.m.
82A. Woodford Street, between Tragarete Road and Queen's Park West	Eastern	Tuesday, Thursday, Saturday
82B. Agra Street, St. James, between Western Main Road and Patna Street	Western	Sunday, Monday, Wednesday, Friday
83. Henry Pierre Street in the City of Port-of-Spain	Eastern	Tuesday, Thursday, Saturday
84. Nizam Street, St. James in the City of Port-of-Spain	Western	Sunday, Monday, Wednesday, Friday
85. Ethel Street, St. James		
86. Pujadas Street, St. James	Northern	Tuesday, Thursday, Saturday
	Southern	Sunday, Monday, Wednesday, Friday
87. Luckput Street	Eastern	Tuesday, Thursday, Saturday
88. Coronation Street	Western	Sunday, Monday, Wednesday, Friday
89. Western Main Road, St. James in the City of Port-of-Spain	Northern	Monday, Wednesday, Friday
	Southern	Sunday, Tuesday, Thursday, Saturday

**COUNTY OF ST. GEORGE WEST—Continued**

<i>Road</i>	<i>Side of Road</i>	<i>Day of Week and Time where Applicable</i>
90. Western Main Road, Carenage between Jellicoe Street and Haig Street	Northern	Tuesday, Thursday, Saturday
	Southern	Sunday, Monday, Wednesday, Friday
91. First Street, San Juan between the Eastern Main Road and Second Street	} Northern	Sunday, Tuesday, Thursday, Saturday
92. First Street, San Juan between First Avenue and Seventh Avenue		
93. Second Street, San Juan between First Street and Saddle Road		
94. Second Street, San Juan between First Avenue and Seventh Avenue	} Southern	Monday, Wednesday, Friday
95. Saddle Road, San Juan between Mission Road and the 4-kilometre post	Eastern	Tuesday, Thursday, Saturday
	Western	Sunday, Monday, Wednesday, Friday
96. Back Chain Street	Northern	Tuesday, Thursday, Saturday
	Southern	Monday, Wednesday, Friday
97. El Socorro Road from Back Chain Street to Churchill-Roosevelt Highway	Eastern	Sunday, Tuesday, Thursday, Saturday
	Western	Monday, Wednesday, Friday

**PART H**

**COUNTY OF ST. PATRICK**

<i>Road</i>	<i>Side of Road</i>	<i>Day of Week and Time where Applicable</i>
1. That portion of Coora Road, Siparia, in the County of St. Patrick which lies between High Street and Mary Street	Eastern	Tuesday, Thursday, Saturday
	Western	Sunday, Monday, Wednesday, Friday
2. That portion of High Street, Siparia, in the County of St. Patrick which lies between Allies and La Pastora Streets	Northern	Tuesday, Thursday, Saturday
	Southern	Sunday, Monday, Wednesday, Friday
3. That portion of the Fyzabad-Guapo Road in the County of St. Patrick commencing at the junction of the said Fyzabad-Guapo Road and Oropouche Road continuing in a southerly direction and ending at the 4-kilometre mark on the said Fyzabad-Guapo Road	Eastern	Sunday, Tuesday, Thursday, Saturday
	Western	Monday, Wednesday, Friday
4. Point Fortin Main Road, between the A.B.C. Roundabout and Shell Trinidad Limited Main gate	Northern	Sunday, Tuesday, Thursday, Saturday
	Southern	Monday, Wednesday, Friday
5. That portion of the Point Fortin Main Road which lies between Frisco Junction and the A.B.C. Junction	Eastern	Tuesday, Thursday, Saturday
6. That portion of Guapo-Cap-de-Ville Road in the County of St. Patrick which lies between the A.B.C. Junction and the Point Ligoure Junction	Western	Sunday, Monday, Wednesday, Friday
7. Techier Road, Point Fortin	Northern	Monday, Wednesday, Friday
	Southern	Tuesday, Thursday, Saturday

**PART I**

**TOBAGO**

Nil

**PART J**

**COUNTY OF VICTORIA**

<i>Road</i>	<i>Side of Road</i>	<i>Day of Week and Time where Applicable</i>
1. Guaracara-Tabaquite Road from a point 45 metres East of the Southern Main Road to Battoo Avenue	Northern	Sunday, Tuesday, Thursday, Saturday
	Southern	Monday, Wednesday, Friday
2. Southern Main Road, Marabella between the Guaracara River and the Marabella Roundabout	Eastern	Sunday, Tuesday, Thursday, Saturday
	Western	Monday, Wednesday, Friday
3. Royal Road	Eastern	Sunday, Tuesday, Thursday, Saturday
	Western	Monday, Wednesday, Friday
4. Coffee Street from a point 45 metres East of Johnstone Street to Navet Road	Northern	Sunday, Tuesday, Thursday, Saturday
	Southern	Monday, Wednesday, Friday
5. Naparima-Mayaro Road from Circular Road to the Mon Repos Roundabout	Northern	Sunday, Tuesday, Thursday, Saturday
	Southern	Monday, Wednesday, Friday
6. Ciperio Street from Park Street to 34 metres South of Coffee Street	Eastern	Sunday, Tuesday, Thursday, Saturday
	Western	Monday, Wednesday, Friday
7. Rushworth Street from Independence Avenue to Bertrand Street	Northern	Sunday, Tuesday, Thursday, Saturday
	Southern	Monday, Wednesday, Friday
8. Prince Alfred Street from Keate Street to Rushworth Street	Eastern	Sunday, Tuesday, Thursday, Saturday
	Western	Monday, Wednesday, Friday
9. High Street, San Fernando but not including that portion appearing under Part "J" of the Schedule to the Public Stands (Taxis) Parking Order	Northern	Sunday, Tuesday, Thursday, Saturday
	Southern	Monday, Wednesday, Friday
10. Prince of Wales Street from Coffee Street to Rushworth Street	Eastern	Sunday, Tuesday, Thursday, Saturday
	Western	Monday, Wednesday, Friday

**COUNTY OF VICTORIA—Continued**

<i>Road</i>	<i>Side of Road</i>	<i>Day of Week and Time where Applicable</i>
11. Chacon Street	Northern Southern	Sunday, Tuesday, Thursday, Saturday Monday, Wednesday, Friday
12. Carib Street from La Coulee Street to Coffee Street		
13. Johnstone Street		
14. San Fernando Street	Northern	Tuesday, Thursday, Saturday
	Southern	Sunday, Monday, Wednesday, Friday
15. St. Vincent Street	Northern Southern	Sunday, Tuesday, Thursday, Saturday Monday, Wednesday, Friday
16. Keate Street from Prince Alfred Street to Prince of Wales Street and from Gransaul Street to Independence Avenue		
17. Circular Road from Pointe-a-Pierre Road to a point 90 metres West of London Street		
18. Penitence Street from Harris Promenade (North) to High Street	Eastern	Sunday, Tuesday, Thursday, Saturday
	Western	Monday, Wednesday, Friday
19. Pointe-a-Pierre Road from the Southern Main Road to a point 30 metres North of Mount Moriah Road	Eastern	Sunday, Tuesday, Thursday, Saturday
	Western	Monday, Wednesday, Friday
20. Pointe-a-Pierre Road from a point 30 metres North of Chacon Street to Short Street		
21. Quenca Street from San Fernando Street to its junction with Vistabella Road	Eastern	Sunday, Tuesday, Thursday, Saturday
	Western	Monday, Wednesday, Friday
22. Vistabella Road		
23. St. James Street between Penitence Street and Pointe-a-Pierre Road	Northern	Sunday, Tuesday, Thursday, Saturday
	Southern	Monday, Wednesday, Friday

336 **Chap. 48:50** *Motor Vehicles and Road Traffic*  
[Subsidiary]

---

## PRIVATE MOTOR CARS (PARKING PLACES) ORDER

### ARRANGEMENT OF CLAUSES

#### CLAUSE

1. Citation.
2. Interpretation.
3. Parking for private motor car.
4. Parking in manner prescribed.
5. Parking in scheduled area.
6. Obstruction and traffic signs.
7. Offences.

#### SCHEDULE.

---

**PRIVATE MOTOR CARS (PARKING PLACES) ORDER**

[\*214/1979.  
220/1980  
151/1981].

*made under section 65*

1. This Order may be cited as the Private Motor Cars (Parking Places) Order.

Citation.

2. In this Order “scheduled area” means any area set out in the Schedule to this Order.

Interpretation.

3. No person shall cause or permit any vehicle other than a private motor car to be or to remain parked in any scheduled area.

Parking for private motor car.

4. No person shall cause or permit a private motor car to be parked in any scheduled area otherwise than in the manner prescribed in clause 5 of this Order.

Parking in manner prescribed.

5. Any person who parks a private motor car in a scheduled area shall park such car in the space between any two white lines drawn on the surface of the scheduled areas and not otherwise.

Parking in scheduled area.

6. (1) No person shall cause or permit a private motor car to be parked in any scheduled area in such a manner as to cause an obstruction to the free ingress to or egress from the said scheduled area.

Obstruction and traffic signs.

(2) No person shall cause or permit a private motor car to enter or leave a scheduled area save in accordance with the directions indicated by the traffic signs placed at the entrance and exit of any such scheduled area.

7. Any person who contravenes any of the provisions of this Order is liable on summary conviction to a fine of five hundred dollars or to imprisonment for three months.

Offences.

---

\*See Act No. 9 of 2017 for further amendments to this Order.

## SCHEDULE

### PART I

#### PORT-OF-SPAIN

1. The area bounded as follows:  
NORTH—by Independence Square North.  
SOUTH—by Independence Square South.  
EAST—by George Street.  
WEST—by Charlotte Street.
2. The area bounded as follows:  
NORTH—by Independence Square North.  
SOUTH—by Independence Square South.  
EAST—by Charlotte Street.  
WEST—by Henry Street.
3. *(Deleted by LN 151/1981).*
4. The area bounded as follows:  
NORTH—by Independence Square North.  
SOUTH—by Independence Square South.  
EAST—by Abercromby Street.  
WEST—by St. Vincent Street.
5. The area bounded as follows:  
NORTH—by Independence Square North.  
SOUTH—by Independence Square South.  
EAST—by St. Vincent Street.  
WEST—by Edward Street.
6. The area bounded as follows:  
NORTH—by the building occupied by Government Wireless Station.  
SOUTH—by Wrightson Road.  
EAST—by St. Vincent Street.  
WEST—by the building occupied by the Planning and Housing Commission and by Edward Street.
7. Hart Street bounded as follows:  
EAST—by Frederick Street.  
WEST—by Abercromby Street.
8. The southern half of the parking lot situated at the corner of Naparima-Mayaro Road and Guayaguayare Road (opposite the Mayaro Market).

**PART II**

**TOBAGO**

1. Scarborough Wharf—on the western side of Entry Street to Customs Area facing South, alongside the northern and southern Customs Warehouses—three cars respectively.
2. Exit Street from Customs Area—Western side, from a point two metres away from the junction with Carrington Street and extending in a southerly direction for a distance of fifteen metres—three private cars facing North.
3. Exit Street from Customs Area—Western side, from a point one metre South of the Wharf Gate and extending in a southerly direction for a distance of twenty metres—eight private cars facing north-east.
4. Exit Street from Customs Area—Eastern side, in front of the Customs Building—six private cars facing North.
5. Exit Street from Customs Area—in front of the Post Office Building—five private cars facing North.
6. Jerningham Street—in front of the Administration Building—ten private cars facing north-west.
7. Bacolet Street—Western side at the rear of the Administration Building—ten private cars facing south-east.

340 **Chap. 48:50** *Motor Vehicles and Road Traffic*  
[Subsidiary]

---

**PUBLIC STANDS (TAXIS) PARKING ORDER**

ARRANGEMENT OF CLAUSES

**CLAUSE**

1. Citation.
2. Parking places for taxis.
3. Parking in prescribed manner.
4. Taxis shall stand in line.
5. Taxis standing for hire.
6. Public stands.
7. Offence.

**SCHEDULE.**

\_\_\_\_\_

**PUBLIC STANDS (TAXIS) PARKING ORDER**

\*212/1979.

*made under section 65*

1. This Order may be cited as the Public Stands (Taxis) Parking Order. Citation.
2. The Public Stands described in the Schedule are hereby appointed as parking places for taxis. Parking places for taxis.
3. Any taxi while waiting at the parking places described in the Schedule shall be parked in the prescribed manner only, and at night when so parked shall not be required to carry any lighted lamps. Parking in prescribed manner.
4. The taxis shall stand in line commencing five metres from the near kerb of any intersecting road unless otherwise provided and not less than one metre nor more than one metre apart from each other: Provided that where taxis are required or permitted to stand alongside each other they shall so stand not less than three hundred millimetres apart, and not less than one metre between the lines. Taxis shall stand in line.
5. (1) Taxis standing for hire in stands shall leave such stands for the purpose of answering calls according to their priority of position in such stands and not otherwise. Taxis standing for hire.  
(2) On the departure of any taxi standing for hire in any such stands the taxi next in rear thereto shall move forward and occupy the vacant place, and in like manner other taxis in rear shall move forward in the line and occupy the vacant spaces immediately in front of them.
6. No vehicles other than taxis may park in Public Stands appointed for taxis. Public stands.
7. Any person who contravenes any of the provisions of this Order is liable on summary conviction to a fine of five hundred dollars or to imprisonment for three months. Offence.

\*This Order has been amended by the following: LN 220/1980; LN 149/1983; LN 164/1984; LN 75/1985; LN 97/1985; LN 183/1986; Act No. 9 of 2017 and LN 208/2023.

**SCHEDULE**

**PART A**

**COUNTY OF CARONI**

*Taxi Stands—Chaguanas*

1. Chaguanas Main Road—Northern side from a point seventy metres East of Endeavour Road and extending in an easterly direction for a distance of fifty-two metres—nine taxis facing East.
2. Chaguanas Main Road—Southern side from a point ten metres of the Old Southern Main Road and extending in an easterly direction for a distance of one hundred and twenty metres—seventeen taxis facing West.
3. Old Southern Main Road—Eastern side from a point ten metres South of Chaguanas Main Road and extending in a southerly direction for a distance of one hundred and ten metres—ten taxis facing South.
4. Old Southern Main Road—Eastern side from a point ten metres South of Eleanor Street and extending in a southerly direction for a distance of fifty metres—eight taxis facing South.
5. St. Yves Street—Western side from a point twenty metres North of the Chaguanas Main Road and extending in a northerly direction for a distance of forty metres—six taxis facing North.
6. Noel Street—on the western side, North of Gran Couva Road, from a point nine metres extending northwards—twelve taxis facing South.

*Taxi Stand—Carapichaima*

Waterloo Road, St. Mary's Junction—Northern side from a point ten metres West of the entrance to the Gas Station and extending in a westerly direction for a distance of forty metres (Church entrance shall be free of obstruction) — six taxis facing West.

**PART B**

**COUNTY OF MAYARO**

*Taxi Stand—Mayaro*

The northern half of the parking lot situated at the corner of Naparima Mayaro Road and Guayaguayare Road (opposite the Mayaro Market)—eleven taxis parked within lines painted or marked on the surface of the said parking lot.

**PART C**

**COUNTY OF NARIVA**

*Taxi Stands—Rio Claro*

1. Naparima-Mayaro Road—Southern side from a point fifty metres East of the junction of Guayaguayare Road and extending in an easterly direction for a distance of forty-five metres—eighteen taxis facing North.
2. Naparima-Mayaro Road—From a point forty metres East of Cunapo South Road, along the northern side of Railway Road—ten taxis facing East.

**PART D**

**COUNTY OF ST. ANDREW**

*Taxi Stands—Sangre Grande*

1. Railway Station Road Exit—Eastern side—eight taxis facing south-west.
2. Old Railway Station Road—Northern side near wall of Public Transport Service Corporation Administration Building—ten taxis facing South.
3. Cunapo Southern Main Road—Eastern side from a point ten metres North of Andre Street and extending in a northerly direction for a distance of fifty metres—eight taxis facing South.
4. Foster Local Road—Eastern side from a point ten metres North of Toco Main Road and extending in a northerly direction for a distance of seventy-three metres—sixteen taxis facing South.
5. Ojoe Road— from a point ten metres North of Eastern Main Road and extending in a northerly direction for a distance of twenty-five metres—four taxis parked as follows:
  - between 6.00 a.m. and 6.00 p.m. daily, on eastern side facing South.
  - between 6.00 p.m. and 6.00 a.m. daily, on western side facing North.

**PART E**

**COUNTY OF ST. DAVID**

Nil

**PART F**

**COUNTY OF ST. GEORGE EAST**

*Taxi Stand—Curepe*

Evans Street—From a point thirty metres from the corner of Old Southern Main Road and Evans Street.

*Taxi Stand—Arouca*

Golden Grove Road—Eastern side from a point twenty-three metres South of the Eastern Main Road extending in a southerly direction—ten taxis facing South.

*Taxi Stands—Arima*

1. Broadway—Northern side between Queen Street (Dial) and Prince Street—fourteen taxis facing East.
2. North side of Broadway from a point ten metres East of Woodford Street to a point indicated by studs fifteen metres West of Queen Street—fifteen taxis facing East.
3. Pro Queen Street—Western side between Hollis Avenue and de Verteuil Street—fifteen taxis facing North.
4. West side of Pro Queen Street from a point thirty metres South of Hollis Street and extending in a southerly direction for sixty metres—ten taxis facing North.
5. Queen Street—Western side, from a point nine metres South of the corner of Farfan Street—twelve taxis facing South.

**PART G**

**COUNTY OF ST. GEORGE WEST**

*Taxi Stands—Port-of-Spain*

1. Queen's Park West—On North side, opposite to the front of Queen's Park Hotel—twenty taxis facing East.
2. Queen's Park West—On South side in front of the Princes Building between the East entrance and West entrance of drive excluding entrance to central path—twenty-two taxis facing West.

3. Green Corner—Southern side of Tragarete Road from a point three metres West of St. Vincent Street and extending in a westerly direction for a distance of eighty-five metres—fifteen taxis facing East.

4. Park Street—Northern side from a point ten metres East of Edward Street and extending in an easterly direction to a point ten metres West of St. Vincent Street—eight taxis facing West.

5. Duke Street—Southern side from a point ten metres West of George Street to a point ten metres East of Charlotte Street—ten taxis facing West.

6. At the corner of Piccadilly Street and Laventille Road.

7. Independence Square (North)—Southern side from George Street to Charlotte Street—nine taxis facing East.

8. Independence Square (North)—Southern side between Henry Street and Charlotte Street—twelve taxis facing East.

9. Independence Square (North)—Southern side from St. Vincent Street to Broadway—thirty-one taxis facing East.

10. Independence Square (North)—Southern side from Edward Street to St. Vincent Street—eight taxis facing East.

11. Independence Square (South)—Northern side from Duncan Street to Nelson Street—twelve taxis facing West.

12. Independence Square (South)—Northern side from George Street to Charlotte Street—seven taxis facing West.

13. Independence Square (South)—Northern side from Broadway to Chacon Street—ten taxis facing West.

14. Independence Square (South)—Northern side from Henry Street to Broadway—twenty-eight taxis facing South.

15. Broadway—On East side close to kerb from Independence Square North to Independence Square South—ten taxis facing West.

16. Broadway—On West side close to kerb from Independence Square North to Independence Square South—twelve taxis facing East.

17. Dock Road—On North side and close to kerb from a point twenty-five metres West of No. 2 Gate, King's Wharf and extending in a westerly direction—seven taxis facing South.

18. Queen Street—On the southern side, from a point nine metres East of Nelson Street—ten taxis facing West.

*Taxi Stand—Morvant*

Lady Young Road—Western side shoulder from a point thirty metres North of Morvant Junction and extending northerly for a distance of thirty-four metres. The width of the said Taxi Stand is to commence six metres West of the Lady Young Road and to extend for a distance of a further six metres West thereof—ten taxis facing north-east.

*Taxi Stands—San Juan*

1. Eastern Main Road—The south-east corner of the El Socorro Road junction—nine taxis facing south-west, the head of the rank being the taxi nearest the Post Office.

2. Second Street—Northern side from a point ten metres West of Saddle Road and extending in a westerly direction for twenty metres—three taxis facing East.

3. Second Street—Northern side from a point forty-five metres West of Saddle Road and extending in a westerly direction for sixty metres—nine taxis facing East.

4. Prizgar Road—Northern side from a point nine metres West of Saddle Road extending westward to a point nine metres East of Newalloville Extension Road—forty taxis facing East.

5. First Street—Northern side, from a point nine metres East of Saddle Road to a point one hundred metres further East of the said road—twenty taxis facing West.

**PART H**

**COUNTY OF ST. PATRICK**

*Taxi Stands—Penal*

1. Siparia-Erin Road—Western side along the frontage of the Police Station—five taxis facing North.

2. Siparia-Erin Road—Western side from a point twelve metres South of Clarke Street and extending in a southerly direction for a distance of forty metres—six taxis facing North.

3. Penal Rock Road—Southern side from a point twelve metres East of Siparia-Erin Road and extending in an easterly direction for a distance of twenty metres—eight taxis facing north-east.

*Taxi Stands—Siparia*

1. Eastern side of the parking ground adjoining the Post Office on the Siparia-Erin Road—four taxis facing South.
2. Coora Extension Road—Eastern side of Siparia-Erin Road—six taxis facing South in herring-bone fashion.

*Taxi Stand—Fyzabad*

South side of Fyzabad-Guapo Road from a point twenty metres West of the junction of Fyzabad Road and extending in a westerly direction for a distance of thirty metres—four taxis facing West.

*Taxi Stands—Point Fortin*

1. Mainfield Road—Northern side—eight taxis facing West.
2. Frisco Junction—On the eastern side of the triangular piece of land known as the Savannah and bounded by the Point Fortin Main Road on the North, Mainfield Road on the South and the connecting road on the East—ten taxis facing East.
3. Cap-de-Ville Junction—On the piece of prepared ground at North side of the junction and bounded by the Guapo-Cap-de-Ville Road on the north-eastern side and the Point Fortin Main Road on the south-western side—twelve taxis parked as indicated on the site.

**PART I**

**TOBAGO**

*Taxi Stands—Tobago*

1. Piggott Street—On the South side close to kerb from Jerningham Street to Burnett Street—six taxis facing West.
2. Ross Street—On the North side close to kerb from Jerningham Street to Burnett Street—six taxis facing East.
3. Jerningham Street—On the West side close to kerb from a point three metres North of Main Street to a point twenty-five metres North of Main Street—four taxis facing North.

4. Carrington Street—Southern side from a point three metres West of Exit Street from Customs Area and extending in a westerly direction for a distance of seventy metres—twenty-five taxis facing north-east.

**PART J**

**COUNTY OF VICTORIA**

*Taxi Stands—San Fernando*

1. Harris Promenade—Southern side of Harris Promenade (Road) from a point twenty metres West of Library Street and extending in a westerly direction for a distance of forty-five metres—nine taxis facing West.

2. Harris Promenade—Eastern end of Harris Promenade (Grounds) northern side from a point five metres West of Library Street and extending in a westerly direction for a distance of thirty metres—six taxis facing West.

3. High Street—Southern side from a point ten metres West of Harris Promenade and extending in a westerly direction for a distance of one hundred and twenty metres—twenty taxis facing East.

4. Library Street—Northern side from a point ten metres West of Mucurapo Street and extending in a westerly direction for a distance of forty metres—seven taxis facing West.

5. Lord Street—Northern side from a point ten metres West of Mucurapo Street and extending in a westerly direction for a distance of sixty metres—ten taxis facing East.

6. Keate Street—Northern side from a point twenty metres West of Prince Alfred Street, and extending in a westerly direction for a distance of ninety metres—fifteen taxis facing East.

7. Queen Street—Southern side from a point five metres East of Lady Hailes Avenue and extending in an easterly direction for a distance of sixty metres—twenty-five taxis facing North in herring-bone fashion.

8. Mucurapo Street—Western side from a point ten metres South of Lord Street, and extending in a southerly direction for a distance of forty-two metres—seven taxis facing South.

*Taxi Stands—Princes Town*

1. Naparima-Mayaro Road—Southern side from a point ten metres West of Bonanza Street and extending in a westerly direction for a distance of forty-five metres—seven taxis facing West.

2. Naparima-Mayaro Road—Southern side from a point seventy metres West of Bonanza Street and extending in a westerly direction for a distance of forty-five metres—seven taxis facing West.

3. North side of the Naparima-Mayaro Road from a point fifteen metres East of Bonanza Street and extending in an easterly direction for a distance of twenty metres—three taxis facing East.

4. The area at the intersection of Naparima-Mayaro Road and Buen Intento Road known as the Roundabout—On the southern side, thirteen taxis facing North and on the northern side, nine taxis facing South.

5. Buen Intento Road—Eastern side from a point twenty metres North of Naparima-Mayaro Road and extending in a northerly direction for a distance of forty metres—six taxis facing South.

350 **Chap. 48:50** *Motor Vehicles and Road Traffic*

[Subsidiary]

\*[213/1979].

**PUBLIC STANDS (MOTOR OMNIBUSES)  
PARKING ORDER**

*made under section 65*

- Citation. **1.** This Order may be cited as the Public Stands (Motor Omnibuses) Parking Order.
- Parking places for motor omnibuses. **2.** The Public Stands described in the Schedule are hereby appointed as parking places for motor omnibuses.
- Parking in prescribed manner. **3.** Any motor omnibus while waiting at the parking places described in the Schedule shall be parked in the prescribed manner only, and at night when so parked shall not be required to carry any lighted lamps.
- Public Stands. **4.** No vehicles other than motor omnibuses may park in Public Stands appointed for motor omnibuses.
- Offence. **5.** Any person who contravenes any of the provisions of this Order is liable on summary conviction to a fine of five hundred dollars or to imprisonment for three months.

**SCHEDULE**

**PART A**

**COUNTY OF CARONI**

Nil

**PART B**

**COUNTY OF MAYARO**

Nil

**PART C**

**COUNTY OF NARIVA**

*Motor Omnibus Stand—Rio Claro*

On the South side of the Naparima-Mayaro Road, East of the Taxi Stand—  
three omnibuses facing West.

\*See Act No. 9 of 2017 for further amendments to this Order.

**PART D**

**COUNTY OF ST. ANDREW**

*Motor Omnibus Stands—Sangre Grande*

1. South side of Railway Station Road from a point ten metres East of the former Railway Station “In” Road—seven motor omnibuses facing East.
2. North side of Andre Street five metres from the Cunapo Southern Road—two omnibuses facing West.

**PART E**

**COUNTY OF ST. DAVID**

Nil

**PART F**

**COUNTY OF ST. GEORGE EAST**

*Motor Omnibus Stands—Arima*

1. North side of Broadway from a point twenty metres East of Queen Street and extending in an easterly direction for a distance of twenty metres—two omnibuses facing East.
2. North side of Broadway from a point seventy metres East of Queen Street and extending in an easterly direction for a distance of thirty metres—three omnibuses facing East.
3. South side of Broadway from a point twenty metres East of Queen Street and extending in an easterly direction for a distance of forty-five metres—five omnibuses facing West.

**PART G**

**COUNTY OF ST. GEORGE WEST**

Nil

**PART H**

**COUNTY OF ST. PATRICK**

*Motor Omnibus Stand—Penal*

West side of Siparia-Erin Road from the twelve-kilometre post and extending in a northerly direction for a distance of forty-five metres—five omnibuses facing North.

**PART I**

**TOBAGO**

*Motor Omnibus Stand—Tobago*

Carrington Street from a point one metre West of Exit Street from Customs Area, Scarborough, to the sea wall—eight omnibuses facing North.

**PART J**

**COUNTY OF VICTORIA**

1. The Eastern side of the triangle in Buen Intento Road—two omnibuses facing North.

2. Omnibuses entering Princes Town from the East shall park along the North side of the Naparima-Mayaro Road from a point one hundred metres East of the corner of the Naparima-Mayaro Road and Buen Intento Road to a point three metres East of the said corner—two omnibuses facing East.

---

**GOODS VEHICLES STANDS PARKING ORDER**

\*[215/1979].

*made under section 65*

1. This Order may be cited as the Goods Vehicles Stands Parking Order. Citation.

2. The goods vehicles stands described in the Schedule are hereby appointed as places where goods vehicles may be parked. Goods vehicles stands.

3. No person shall cause or permit any vehicle other than a goods vehicle to be or to remain parked in the Goods Vehicle Stands appearing in the Schedule. Parking for goods vehicle.

4. Any person who contravenes any of the provisions of this Order is liable on summary conviction to a fine of five hundred dollars or to imprisonment for three months. Offence.

---

**SCHEDULE**

*Goods Vehicles Stand—Port-of-Spain*

The northern side of that portion of South Quay between Charlotte Street and George Street.

*Goods Vehicles Stand—Scarborough, Tobago*

Milford Road, on the southern side, from a point ten metres West of Wilson Road and extending in a westerly direction for ninety metres. All goods vehicles facing north-east.

---

\*See Act No. 9 of 2017 for further amendments to this Order.

[Subsidiary]

\*[216/1979].

**PARKING ON DUAL CARRIAGE-WAYS ORDER**

*made under section 65*

Citation.

**1.** This Order may be cited as the Parking on Dual Carriage-ways Order.

Parking on dual carriage-way.

**2.** Subject to any law in force relating to the parking of vehicles, no person shall cause or permit any vehicle to be or to remain parked on any dual carriage-way except on the extreme left-hand side of the portion of such carriage-way along which any such vehicle is lawfully proceeding.

Offence.

**3.** Any person who contravenes any of the provisions of this Order is liable on summary conviction to a fine of five hundred dollars or to imprisonment for three months.

---

\*See Act No. 9 of 2017 for further amendments to this Order.

**QUEEN'S PARK SAVANNAH PARKING ORDER**

\*[73/1966].

*made under section 65*

**1.** This Order may be cited as the Queen's Park Savannah Parking Order. Citation.

**2.** (1) Subject to subclause (2) no person shall park or cause or permit any vehicle to be or to remain parked on that side of any of the roads abutting the Queen's Park Savannah which is further away from the said Savannah. Parking.

(2) Subclause (1) does not apply to that portion of the road designated as Queen's Park West which lies between the eastern entrance and the western entrance of the Princes Building and which is commonly known as the Princes Building Taxi Stand.

**3.** Any person who contravenes any of the provisions of clause 2(1) is liable on summary conviction to a fine of five hundred dollars or to imprisonment for three months. Offence.

---

\*See Act No. 9 of 2017 for further amendments to this Order.

[Subsidiary]

\*[220/1979].

**INDEPENDENCE SQUARE  
(PARKING OF VEHICLES) ORDER**

*made under section 65*

Citation. **1.** This Order may be cited as the Independence Square (Parking of Vehicles) Order.

Parking. **2.** (1) No person shall cause or permit any vehicle to be or to remain parked on that portion of Independence Square South between George Street and a point twenty-five metres East of Broadway.

(2) Subject to subclause (3) no person shall cause or permit a vehicle to stand on that portion of Independence Square South mentioned in subclause (1) in order that the vehicle may be loaded or unloaded or that passengers may enter or leave the vehicle.

(3) A person may cause or permit a goods vehicle to stand on that portion of Independence Square South mentioned in subclause (1) in order that the vehicle may be loaded or unloaded.

Offence. **3.** Any person who contravenes any of the provisions of this Order is liable on summary conviction to a fine of five hundred dollars or to imprisonment for three months.

---

\*See Act No. 9 of 2017 for further amendments to this Order.

**SOUTH QUAY (PARKING OF VEHICLES) ORDER**

\*[219/1979].

*made under section 65*

**1.** This Order may be cited as the South Quay (Parking of Vehicles) Order. Citation.

**2.** No person shall cause or permit any vehicle of a class or description specified in the first column of the First Schedule to be or to remain parked on the portions of South Quay in the City of Port-of-Spain between St. Vincent Street and Broadway and between Henry Street and Charlotte Street, save as in the manner prescribed therefor in the second column of the said Schedule. Parking in the First Schedule.

**3.** No person shall cause or permit any vehicle to be or to remain parked on the portions of South Quay in Port-of-Spain, as specified in the Second Schedule. Parking in the Second Schedule.

**4.** No person shall cause or permit any vehicle in excess of 2 495 kilogrammes tare or a taxi to be or to remain parked on the southern side of South Quay between Henry Street and Charlotte Street. Parking of heavy vehicles.

**5.** Any person who contravenes any of the provisions of this Order is liable on summary conviction to a fine of five hundred dollars or to imprisonment for three months. Offence.

---

\*See Act No. 9 of 2017 for further amendments to this Order.

358      **Chap. 48:50**      *Motor Vehicles and Road Traffic*  
[Subsidiary]      *South Quay (Parking of Vehicles) Order*

---

### FIRST SCHEDULE

<i>Description of Type of Vehicle</i>	<i>Manner of Parking</i>
(a) Private motor cars not in excess of 2 495 kilogrammes tare	Within any two parallel white lines drawn in the centre of the road
(b) Any vehicle other than a vehicle specified in paragraph (a)	On the northern side of the road against the kerb.

---

### SECOND SCHEDULE

1. That portion of South Quay in the City of Port-of-Spain which lies between Henry Street and Broadway.
  2. The northern side of South Quay between George Street and Nelson Street.
  3. The southern side of South Quay between George Street and Charlotte Street.
-

**BROADWAY (PARKING OF VEHICLES) ORDER**

\*[218/1979].

*made under section 65*

1. This Order may be cited as the Broadway (Parking of Vehicles) Order. Citation.

2. No person shall cause or permit any vehicle other than a vehicle mentioned in the first column of the Schedule to park or remain parked on the road known as Broadway in the City of Port-of-Spain between the hours of 6.00 a.m. and 6.00 p.m. on Mondays to Fridays inclusive save in the manner prescribed in the second column of the said Schedule. Parking on Broadway.

3. Any person who contravenes any of the provisions of clause 2 is liable on summary conviction to a fine of five hundred dollars or to imprisonment for three months. Offence.

4. This Order does not apply on Sundays, Saturdays and public holidays. Application.

---

**SCHEDULE**

<i>Description or type of Vehicle</i>	<i>Manner of Parking</i>
Private motor cars ... ..	Within the white lines drawn diagonally across the surface of the centre of the road.

---

\*See Act No. 9 of 2017 for further amendments to this Order.

360 **Chap. 48:50** *Motor Vehicles and Road Traffic*

[Subsidiary]

\*[211/1979,  
220/1980  
75/1985].

### ONE-WAY TRAFFIC ORDER

*made under section 65*

- Citation. **1.** This Order may be cited as the One-Way Traffic Order.
- Prohibition. **2.** No person shall drive any vehicle on any road specified in the Schedule to this Order otherwise than in the direction indicated in the said Schedule in respect of such road.
- Offence. **3.** Any person who contravenes any of the provisions of this Order is liable on summary conviction to a fine of five hundred dollars or to imprisonment for three months.

---

### SCHEDULE

#### PART A

#### COUNTY OF CARONI

*A. In a westerly direction only*

Edgar Street, Couva.

#### PART B

#### COUNTY OF MAYARO

*A. In a westerly direction only*

Pierreville Village Street in the Ward of Guayaguayare.

*B. In an easterly direction only*

Naparima-Mayaro Road in the Ward of Guayaguayare, from its intersection with Pierreville Village Street at its eastern end to the intersection with that Street at its western end.

---

\*See also Legal Notices LN 176/2013, LN 268/2013; LN 147/2015; LN 56/2016; LN 48/2017, Act No. 9 of 2017 and LN 143/2017 for further amendments to this Order.

**PART C**

**COUNTY OF NARIVA**

Nil

**PART D**

**COUNTY OF ST. ANDREW**

*A. In a northerly direction only*

1. Andre Street from Cunapo Southern Road to Eastern Main Road, Sangre Grande, between 6.00 a.m. and 6.00 p.m. daily.
2. George Street from Mary Street to Eastern Main Road, Sangre Grande, between 6.00 a.m. and 6.00 p.m. daily.

*B. In a southerly direction only*

1. Ojoe Road from Brierley Street to Eastern Main Road, Sangre Grande, between 6.00 a.m. and 6.00 p.m. daily.
2. Cunapo Southern Road from Eastern Main Road to Mary Street, Sangre Grande, between 6.00 a.m. and 6.00 p.m. daily.

*C. In an easterly direction only*

Brierley Street from Riverside Extension Road to Foster Local Road, Sangre Grande, between 6.00 a.m. and 6.00 p.m. daily.

*D. In a westerly direction only*

1. Eastern Main Road, Sangre Grande, from its junction with Ojoe Road and Toco Road at the Roundabout on the East to the junction of Old Railway Road West, between 6.00 a.m. and 6.00 p.m. daily.
2. Mary Street from Cunapo Southern Road to George Street, Sangre Grande, between 6.00 a.m. and 6.00 p.m. daily.

*E. In a northerly then easterly direction*

Old Railway Road West—i.e., in a northerly direction from the Eastern Main Road, to the first bend, then in an easterly direction to Riverside Extension Road, between 6.00 a.m. and 6.00 p.m. daily.

**PART E**

**COUNTY OF ST. DAVID**

*A. In a northerly direction only*

Paria Road in the Ward of Toco between the Toco Depot and Church Street.

*B. In a westerly direction only*

Church Street in the Ward of Toco bounded on the East and West by the Paria Road.

**PART F**

**COUNTY OF ST. GEORGE EAST**

*A. In a northerly direction only*

1. St. Joseph Street between Hollis Avenue and Broadway, Arima.
2. Woodford Street between Hollis Avenue and Broadway, Arima.
3. Calcutta Street between Guanapo Street and Columbus Street, Arima.

*B. In a southerly direction only*

Queen Street between Broadway and Hollis Avenue, Arima.

*C. In an easterly direction only*

Broadway between St. Joseph Street and Queen Street, Arima.

*D. In a westerly direction only*

Hollis Avenue between Queen Street and Woodford Street, Arima.

**PART G**

**COUNTY OF ST. GEORGE WEST**

*A. In a northerly direction only*

1. Hubert Lane between Gloster Lodge Road and Hermitage Road, Belmont.
2. Norfolk Street between Erthig Road and Belmont Circular Road, Belmont.
3. Duncan Street between Independence Square South and Prince Street in the City of Port-of-Spain.

4. George Street between South Quay and Duke Street in the City of Port-of-Spain.
5. Henry Street from South Quay to Gordon Street in the City of Port-of-Spain.
6. Frederick Street between Keate Street and Queen's Park West in the City of Port-of-Spain.
7. Pembroke Street between Knox Street and Keate Street in the City of Port-of-Spain.
8. Abercromby Street between South Quay and Keate Street in the City of Port-of-Spain.
9. Edward Street between Tragarete Road and Gordon Street in the City of Port-of-Spain.
10. Edward Street between Independence Square North and Tragarete Road in the City of Port-of-Spain.
11. Francis Street between Sackville Street and Charles Street in the City of Port-of-Spain.
12. Borde Street between Tragarete Road and New Street in the City of Port-of-Spain.
13. Belle Smythe Street between Ariapita Avenue and Warren Street, Woodbrook.
14. Hamilton Holder Street and O'Connor Street between Wrightson Road and Ariapita Avenue, Woodbrook.
15. Gatacre Street, Woodbrook.
16. Alfredo Street, Woodbrook.
17. Rosalino Street, Woodbrook.
18. Gallus Street, Woodbrook.
19. Petra Street between Warren Street and Ariapita Avenue, Woodbrook.
20. Damian Street between Warren Street and Kelly Kenny Street, Woodbrook.
21. Henry Pierre Street, Mucurapo.
22. Benares Street, St. James.
23. Coronation Street from Mucurapo Road to Western Main Road, St. James.

**COUNTY OF ST. GEORGE WEST—Continued**

24. El Socorro Road, San Juan between the priority bus route and the Eastern Main Road.
25. Colda Tinda Avenue between Eastern Main Road and Second Street, San Juan.
26. First Street between Eastern Main Road and Saddle Road, San Juan.
27. Fitzblackman Drive in the City of Port-of-Spain.

*B. In a southerly direction only*

1. Augustine Lane between Hermitage Road and Gloster Lodge Road, Belmont.
2. Belmont Circular Road between Belmont Valley Road and Erthig Road, Belmont.
3. Observatory Street between Belmont Circular Road and Charlotte Street.
4. Bath Street between Piccadilly Street and Siparia Hill in the City of Port-of-Spain.
5. Piccadilly Street between South Quay and Queen Street in the City of Port-of-Spain.
6. Nelson Street between South Quay and Duke Street in the City of Port-of-Spain.
7. Charlotte Street between Keate Street and Queen's Park West in the City of Port-of-Spain.
8. Charlotte Street between Park Street and South Quay in the City of Port-of-Spain.
9. Frederick Street between Keate Street and Independence Square North in the City of Port-of-Spain.
10. Chacon Street between Queen Street and Beetham Highway in the City of Port-of-Spain.
11. St. Vincent Street between Gordon Street and Independence Square North in the City of Port-of-Spain.
12. Dundonald Street between Queen's Park West and Tragarete Road in the City of Port-of-Spain.

13. Richmond Street between Fraser Street and Independence Square South in the City of Port-of-Spain.
  14. Scott-Bushe Street South Extension between Charles Street and the intersection of Wrightson Road and Sackville Street.
  15. Luis Street, Woodbrook.
  16. White Street, Woodbrook.
  17. Alberto Street, Woodbrook.
  18. Ana Street between Warren Street and Wrightson Road, Woodbrook.
  19. O'Connor Street between Warren Street and Ariapita Avenue, Woodbrook.
  20. De Verteuil Street and Dennis Mahabir Street between Ariapita Avenue and Wrightson Road.
  21. Gaston Johnson Street, Mucurapo.
  22. Lucknow Street, St. James.
  23. Luckput Street from Western Main Road, St. James to Mucurapo Road.
  24. Ethel Street, St. James between Pujadas Street and Mucurapo Road.
  25. Bridge Road, San Juan between Eastern Main Road and Maloney Street, between 3.00 p.m. and 6.00 p.m. daily.
  26. Broome Street, San Juan between Eastern Main Road and Maloney Street, between 3.00 p.m. and 6.00 p.m. daily.
  27. Savannah Street between Neverson Street and Bridge Road.
- C. In an easterly direction only*
1. Meyler Street, Belmont.
  2. Belmont Circular Road from Charlotte Street to Observatory Street, Belmont.
  3. Queen's Park West between Frederick Street and Charlotte Street in the City of Port-of-Spain.
  4. New Street in the City of Port-of-Spain between Dundonald Street and Charlotte Street.
  5. Park Street between St. Vincent Street and Charlotte Street in the City of Port-of-Spain.
  6. Tragarete Road between Edward Street and St. Vincent Street in the City of Port-of-Spain.

**COUNTY OF ST. GEORGE WEST—Continued**

7. Knox Street between Abercromby Street and Frederick Street in the City of Port-of-Spain.
8. Prince Street in the City of Port-of-Spain.
9. Sackville Street between Wrightson Road and Richmond Street in the City of Port-of-Spain.
10. Faure Street between George Street and Nelson Street in the City of Port-of-Spain.
11. Independence Square North between Wrightson Road and St. Joseph Road Bridge in the City of Port-of-Spain.
12. Warner Street from Maraval Road to Cipriani Boulevard in the City of Port-of-Spain.
13. McDonald Street, Woodbrook.
14. Warren Street between Belle Smythe Street and Hamilton Street, Woodbrook.
15. Pujadas Street, St. James from Bay Road to Ethel Street.
16. Old St. Joseph Road, Laventille.
17. Second Street between First Avenue and First Street, San Juan.
18. Neverson Street, between Bridge Road and Savannah Street.

*D. In a westerly direction only*

1. Clifford Street, Belmont.
2. Erthig Road between Belmont Circular Road and Norfolk Street, Belmont.
3. Keate Street between Charlotte Street and Frederick Street in the City of Port-of-Spain.
4. Oxford Street between Observatory Street and Dundonald Street in the City of Port-of-Spain.
5. Fraser Street in the City of Port-of-Spain.
6. Kew Place between Longden Street and Park Street in the City of Port-of-Spain.
7. Park Street between St. Vincent Street and Edward Street in the City of Port-of-Spain.

8. Duke Street between Charlotte Street and Richmond Street in the City of Port-of-Spain.
9. Hart Street between Frederick Street and Abercromby Street in the City of Port-of-Spain.
10. Charles Street between Wrightson Road and Richmond Street in the City of Port-of-Spain.
11. London Street between Richmond Street and Wrightson Road in the City of Port-of-Spain.
12. Cockerton Street between George Street and Nelson Street in the City of Port-of-Spain.
13. Queen Street between Piccadilly Street and Richmond Street in the City of Port-of-Spain.
14. Treasury Street between St. Vincent Street and Edward Street in the City of Port-of-Spain.
15. Independence Square South between St. Joseph Road Bridge and Wrightson Road in the City of Port-of-Spain.
16. Marli Street, St. Clair from Queen's Park West to Maraval Road in the City of Port-of-Spain.
17. Methuen Street, Woodbrook.
18. Kelly Kenny Street, Woodbrook.
19. Hamilton Street, Woodbrook.
20. Avenue First, St. James from Ethel Street to Bay Road.
21. First Street between Second Street and First Avenue, San Juan.
22. First Street between Eastern Main Road and Saddle Road, San Juan.
23. Eastern Main Road from the intersection with the Old St. Joseph Road at its eastern end to the intersection with that road at its western end between the hours of 6.00 a.m. and 9.00 a.m. daily excluding Sundays and public holidays.
24. Ariapita Avenue, Woodbrook, between Belle Smythe Street and Taylor Street.
25. Warren Street, Woodbrook, between Taylor Street and Belle Smythe Street, between 6.00 a.m. and 9.00 a.m. and between 3.00 p.m. and 6.00 p.m. daily.

26. Bridge Road between Savannah Street and Neverson Street.
27. Maloney Street between Eastern Main Road and Bushe Street.

**PART H**

**COUNTY OF ST. PATRICK**

*A. In a southerly direction only*

Clark Street, Penal between Siparia-Erin Road and Penal Rock Road.

*B. In an easterly direction only*

1. School Road, Point Fortin between Mainsfield Road and Guapo-Cap-de-Ville Road.
2. Mainsfield Road North between School Road and Point Fortin Main Road.

*C. In a westerly direction only*

Mainsfield Road South between School Road and Point Fortin Main Road.

**PART I**

**TOBAGO**

*A. In a northerly direction only*

1. Jerningham Street between Main Street and Piggott Street, Scarborough.
2. Exit Street from Customs Area, Scarborough.

*B. In a southerly direction only*

1. Burnett Street between Carrington and Main Streets, Scarborough.
2. Bacolet Street between Piggott and Main Streets, Scarborough.
3. Entry Street to Customs Area, Scarborough.

*C. In a westerly direction only*

1. Piggott Street between Bacolet and Robinson Streets, Scarborough.
2. Piggott Street between Jerningham and Burnett Streets, Scarborough.
3. Ross Street, Scarborough.

**PART J**

**COUNTY OF VICTORIA**

*A. In a northerly direction only*

1. Penitence Street, between Harris Promenade and St. James Street, San Fernando.
2. Independence Avenue, between Keate Street and Rushworth Street (Western Carriage-way), San Fernando.

*B. In a southerly direction only*

1. Mon Chagrin Street, between St. James Street and High Street, San Fernando.
2. Quenca Street, between St. James Street and High Street, San Fernando.
3. Prince Alfred Street, between Cemetery Street and Keate Street, San Fernando.
4. Mucurapo Street, between Lord Street and Cemetery Street, San Fernando.
5. Mucurapo Street, between Keate Street and Sutton Street, San Fernando.
6. Court Street, between Harris Promenade South and Knox Street, San Fernando.
7. Independence Avenue, between Keate Street and Rushworth Street (Eastern Carriage-way), San Fernando.

*C. In a south-easterly direction only*

1. Hollis Street, San Fernando.
2. Coffee Street, between Mucurapo Street and Lord Street, San Fernando.

*D. In an easterly direction only*

1. San Fernando Street, San Fernando.
2. St. James Street, between High Street and Quenca Street, San Fernando.
3. High Street, between Chancery Lane and the Library Corner, San Fernando.

**COUNTY OF VICTORIA—Continued**

4. Harris Promenade South, San Fernando.
5. Lord Street, between Paradise Street and Mucurapo Street, San Fernando.
6. Carib Street, San Fernando.

*E. In a westerly direction only*

1. St. James Street, between Pointe-a-Pierre Road and Quenca Street, San Fernando.
  2. High Street, between Chancery Lane and Queen Street, San Fernando.
  3. Harris Promenade North, San Fernando.
  4. Library Street, San Fernando.
  5. Lord Street, between Coffee Street and Mucurapo Street, San Fernando.
  6. Johnstone Street, San Fernando.
-

**EASTERN MAIN ROAD TRAFFIC ORDER**

ARRANGEMENT OF CLAUSES

CLAUSE

1. Citation.
2. Application.
3. Division of Eastern Main Road.
4. Effect of Order.
5. Hours and direction.
6. Hours and direction.
7. Use of middle lane.
8. Parking on lanes.
9. Offence.

[Subsidiary]

\*[58/1976].

**EASTERN MAIN ROAD TRAFFIC ORDER**

*made under section 65*

Citation. **1.** This Order may be cited as the Eastern Main Road Traffic Order.

Application. **2.** This Order applies to that portion of the Eastern Main Road between Junction Box Crossing, St. Augustine and the Aranguez Road.

Division of Eastern Main Road. **3.** For the purposes of this Order that portion of the Eastern Main Road referred to in clause 2 has been divided into three distinct lanes which are referred to in this Order as—

- (a) the northern lane;
- (b) the middle lane; and
- (c) the southern lane.

Effect of Order. **4.** This Order shall have effect from Mondays to Fridays inclusive, but only during the hours specified herein.

Hours and direction. **5.** Between the hours of 6.00 a.m. and 9.00 a.m. no person shall drive or cause any vehicle to be driven—

- (a) on the northern lane otherwise than in an easterly direction; and
- (b) on the southern and middle lanes otherwise than in a westerly direction.

Hours and direction. **6.** Between the hours of 3.00 p.m. and 6.00 p.m. no person shall drive or cause any vehicle to be driven—

- (a) on the northern and middle lanes otherwise than in an easterly direction; and
- (b) on the southern lane otherwise than in a westerly direction.

Use of middle lane. **7.** Between the hours specified herein only the middle lane may be used at intersections for right-turning traffic.

---

\*See Act No. 9 of 2017 for further amendments to this Order.

8. Notwithstanding any other written law to the contrary, between the hours specified herein no person shall park or cause or permit any vehicle to be parked or to remain on any of the lanes. Parking on lanes.

9. A person who contravenes any of the provisions of this Order is liable on summary conviction to a fine of five hundred dollars or to imprisonment for three months. Offence.

---

**BEETHAM HIGHWAY ORDER**

\*[60/1976].

*made under section 65*

1. This Order may be cited as the Beetham Highway Order. Citation.
2. No person shall drive or cause any vehicle to be driven in an easterly direction on that portion of the northern carriageway of the Beetham Highway between Abattoir Road and Sea Lots Roundabout between the hours of 6.00 a.m. and 9.00 a.m. from Mondays to Fridays, inclusive. Direction in which vehicle to be driven.
3. A person who contravenes any of the provisions of this Order is liable on summary conviction to a fine of five hundred dollars or to imprisonment for three months. Offence.

---

\*See Act No. 9 of 2017 for further amendments to this Order.

374 **Chap. 48:50** *Motor Vehicles and Road Traffic*

[Subsidiary]

56/1963.  
[156/1985].

**RESTRICTION OF PARKING  
(PUBLIC BUILDINGS) ORDER**

*made under section 107(2)*

Citation. **1.** This Order may be cited as the Restriction of Parking (Public Buildings) Order.

Control of public buildings. Schedule. **2.** For the purposes of this Order, the public buildings described in the first column of the Schedule shall be under the control of the respective public officers mentioned in the second column of the Schedule.

Public officers to grant permission to park. Schedule. **3.** The public officers referred to in the second column of the Schedule are hereby authorised to grant permission to any person to park a vehicle in or on any grounds or open space adjoining or attached to the respective public buildings referred to in the first column of the Schedule.

**SCHEDULE**

56/1963.	All buildings occupied as offices by officers of the respective Ministries (except the Red House, the Old Fire Brigade Building and Knowsley)	The Permanent Secretaries of the appropriate Ministries
	The Red House and the Old Fire Brigade Building	The Permanent Secretary, Ministry of Legal Affairs
	Knowsley	The Permanent Secretary, Ministry of External Affairs
	The Magistrates' Courts, Port-of-Spain	The Chief Magistrate
	Magistrates' Courts (other than Port-of-Spain)	The Senior Magistrate of the District in which the Court is situated
	The Supreme Court, San Fernando	The Sub-Registrar and Deputy Marshal, San Fernando
178/1970.	All buildings occupied for use as offices by the Comptroller of Customs and Excise and located at Port-of-Spain, San Fernando and Scarborough	The Comptroller of Customs and Excise
156/1985.	All buildings occupied for use by the Ministry of Agriculture, Lands and Food Production	The Permanent Secretary, Ministry of Agriculture, Lands and Food Production

[Subsidiary]

**PUBLIC STAND (MAXI-TAXI) PARKING ORDER**

\*[141/1981].

*made under section 65*

1. This Order may be cited as the Public Stand (Maxi-Taxi) Parking Order. Citation.

2. That area of Independence Square in Port-of-Spain which is surrounded on the North by Independence Square North, on the East by Chacon Street, on the South by Independence Square South, and on the West by Abercromby Street is hereby appointed as a parking place for maxi-taxis. Parking area.

3. Any maxi-taxi while waiting in the area described in paragraph 2 shall be parked, and shall leave and enter such area in the manner prescribed. Parking.

4. No vehicles other than maxi-taxis may park in the area herein appointed as a parking place. Prohibited parking.

5. Any person who contravenes this Order is liable on summary conviction to a fine of one hundred dollars or to imprisonment for three months. Offence.

---

\*See Act No. 9 of 2017 for further amendments to this Order.

**TRAFFIC RESTRICTION (QUEEN'S PARK  
SAVANNAH RETICULATION) ORDER**

ARRANGEMENT OF CLAUSES

CLAUSE

1. Citation.
2. Commencement.
3. One-way traffic.
4. No right turn.
5. Parking prohibited.
6. Parking prohibited.
7. No parking on Saddle Road.
8. Parking restricted.
9. Removal and impounding of vehicles unlawfully parked.

---

**TRAFFIC RESTRICTION (QUEEN'S PARK  
SAVANNAH RETICULATION) ORDER**

147/1981.

*made under section 65*

1. This Order may be cited as the Traffic Restriction (Queen's Park Savannah Reticulation) Order. Citation.
2. This Order shall come into operation at 6.00 a.m. on Wednesday 21st October 1981. Commencement.
3. All vehicular traffic shall proceed as indicated below — One-way traffic.
  - (a) Queen's Park East—in a southerly direction only;
  - (b) Queen's Park West—in a westerly direction only except in that area between Frederick Street and Charlotte Street where vehicles will be allowed to travel East along the southern side of Queen's Park West;
  - (c) Woodford Street, between Queen's Park West and Tragarete Road—in a southerly direction only;
  - (d) Picton Street, between Tragarete Road and Queen's Park West—in a northerly direction only;
  - (e) Maraval Road, between Queen's Royal College Roundabout and St. Clair Roundabout—in a northerly direction only;
  - (f) Circular Road—in an easterly direction only;
  - (g) Keate Street, between Frederick Street and Chancery Lane—in an easterly direction only;
  - (h) Lamy Street, between Saddle Road and Prada Street—in a southerly direction only;
  - (i) Newbold Street, between Scott Street and Saddle Road—in a southerly direction only;
  - (j) Prada Street, between Queen's Park Savannah and Newbold Street—in a westerly direction only;
  - (k) Fitzgerald Lane—in a westerly direction only;
  - (l) Dere Street—in a northerly direction only;

- (m) Melville Lane—in an easterly direction only;
- (n) Cummins Lane—in an easterly direction only.

No right turn.

**4.** No vehicular traffic on the undermentioned roads shall turn right on reaching the Queen's Park Savannah—

- (a) Lady Young Road;
- (b) Belmont Circular Road;
- (c) Cadiz Road;
- (d) Park Avenue;
- (e) Jerningham Avenue;
- (f) Chancery Lane;
- (g) Victoria Avenue;
- (h) Cipriani Boulevard;
- (i) Woodford Street;
- (j) Picton Street;
- (k) St. Clair Avenue;
- (l) Hayes Street;
- (m) Flood Street;
- (n) exit from Whitehall;
- (o) Serpentine Road;
- (p) Lady Chancellor Road;
- (q) entrance to Emperor Valley Zoo;
- (r) Visitors Entrance to President House;
- (s) exit from Princes Building Grounds.

Parking  
prohibited.

**5.** No person may park, or cause or permit any vehicle to be parked or to remain on any of the roads mentioned below—

- (a) Dere Street, between Cummins Lane and Queen's Park West, except for taxis plying for hire from the taxi stand on the western side;
- (b) eastern side of Queen's Park East;
- (c) Gordon Street, between Abercromby Street and St. Vincent Street;

- (d) Queen's Park East, between Jerningham Avenue and Queen's Park West;
- (e) Queen's Park East, between Belmont Circular Road and St. Ann's Roundabout.
- (f) Charlotte Street, between Queen's Park West and Keate Street;
- (g) Albion Street, between Stanmore Avenue and Dundonald Street;
- (h) Queen's Park West, between Victoria Avenue and Marli Street;
- (i) Queen's Park West, 90 metres West and 90 metres South of Casuals Club;
- (j) Queen's Park West, between Picton Street and Queen's Royal College Roundabout;
- (k) Maraval Road, between Queen's Royal College Roundabout and Hayes Street;
- (l) Maraval Road, between Serpentine Road and Prada Street;
- (m) southern side of Circular Road, between St. Clair Roundabout and the Visitor's Entrance to President House;
- (n) southern side of Circular Road, between the main Entrance to President House and St. Ann's Roundabout;
- (o) Victoria Avenue, between Cummins Lane and Queen's Park West, except for taxis plying for hire from the taxi stand on the eastern side only;
- (p) Victoria Avenue, between Queen's Park West and a distance of 60 metres South, except for taxis plying for hire from the Taxi Stand on the western side only.

6. While this Order is in force no person may park or cause or permit any vehicle to be parked or to remain— Parking prohibited.

- (a) on the western side of Queen's Park East, between Belmont Circular Road and Jerningham Avenue,

- between the hours of 7.00 a.m. and 9.00 a.m. and 3.00 p.m. and 5.00 p.m. from Mondays to Fridays;
- (b) on Maraval Road, between Hayes Street and Serpentine Road, between the hours of 7.00 a.m. and 9.00 a.m. and 3.00 p.m. and 5.00 p.m. from Mondays to Fridays.

No parking on Saddle Road.

7. While this Order is in force no person may park or cause or permit any vehicle to be parked on Saddle Road, between St. Clair Roundabout and Maraval River Bridge between the hours of 6.00 a.m. and 9.00 a.m. and 3.00 p.m. and 6.00 p.m. from Mondays to Fridays.

Parking restricted.

8. Parking is permitted on the undermentioned roads—

- (a) Albion Street, between Dundonald Street and Chancery Lane—on the northern side only;
- (b) Chancery Lane, between Keate Street and Gordon Street—on the western side only;
- (c) Frederick Street, between Keate Street and Queen's Park West—on the eastern side only;
- (d) Queen's Park West, between Queen's Park East and Cipriani Boulevard—on the northern side only;
- (e) Queen's Park West, between Cipriani Boulevard and Casuals Club—on the eastern side only;
- (f) Queen's Park West, between Casuals Club and Maraval Road—on the northern side only;
- (g) Maraval Road, between Queen's Park West and Circular Road—on the eastern side only;
- (h) Cummins Lane—on the northern side only.

Removal and impounding of vehicles unlawfully parked.

9. Without prejudice to any other liability incurred by the commission of a summary offence, vehicles found parked in contravention of this Order may be removed by the Police and impounded and otherwise dealt with in accordance with sections 108 and 109 of the Motor Vehicles and Road Traffic Act.

**TRAFFIC RESTRICTION (SAN FERNANDO) ORDER**

ARRANGEMENT OF CLAUSES

CLAUSE

1. Citation.
2. One-way traffic.
3. Parking prohibited.
4. Parking restricted.
5. Two-way traffic.
6. No right turn.
7. Vehicular route.
8. Removal and impounding of vehicles unlawfully parked.

[Subsidiary]

152/1981. **TRAFFIC RESTRICTION (SAN FERNANDO) ORDER**  
*made under section 65*

Citation. **1.** This Order may be cited as the Traffic Restriction (San Fernando) Order.

One-way traffic. **2.** All vehicular traffic shall proceed as indicated below—

- (a) Coffee Street, from Royal Road and Navet Junction to Carib Street—in a westerly direction only;
- (b) Marryat Street, between Carib Street and Coffee Street—in a southerly direction only;
- (c) Upper Hillside Street between Carib Street and Coffee Street—in a northerly direction only;
- (d) Howard Lane between Carib Street and Coffee Street—in a southerly direction only;
- (e) Hobson Street—in an easterly direction only;
- (f) Kelshall Street—in an easterly direction only.

Parking prohibited. **3.** No person may park or cause or permit any vehicle to be parked or to remain on any of the undermentioned roads—

- (a) High Street, between Hollis Street and Pointe-a-Pierre Road, except for taxis plying for hire in a Taxi Stand;
- (b) Prince of Wales Street, between Keate Street and Coffee Street;
- (c) Hollis Street, between High Street and Quenca Street;
- (d) Chancery Lane;
- (e) Pointe-a-Pierre Road, between High Street and the Naparima Girls High School Private Road, on the North near to the Texaco Gas Station;
- (f) Mon Chagrin Street, between High Street and St. James Street;

- (g) Penitence Street, between Harris Promenade and St. James Street;
- (h) St. Joseph Road, between London Street and the Bye-Pass.

4. Parking is permitted on the undermentioned roads—

Parking  
restricted.

- (a) Ciperó Street, between Coffee Street and Rushworth Street—on the eastern side only;
- (b) Mucurapo Street, between Keate Street and Sutton Street—on the eastern side only;
- (c) Keate Street, between Mucurapo Street and Independence Avenue—
  - (i) on Mondays, Wednesdays and Fridays—on the northern side only;
  - (ii) on Tuesdays, Thursdays and Saturdays—on the southern side only;
- (d) Court Street, between Independence Avenue and Harris Street—
  - (i) on Mondays, Wednesdays and Fridays—on the northern side only;
  - (ii) on Tuesdays, Thursdays and Saturdays—on the southern side only;
- (e) Chacon Street, between King Street and Pointe-a-Pierre Road—
  - (i) on Mondays, Wednesdays and Fridays—on the northern side only;
  - (ii) on Tuesdays, Thursdays and Saturdays—on the southern side only;
- (f) Ruth Avenue between Harris Street and Mucurapo Street—on the southern side only;
- (g) Pointe-a-Pierre Road, between Cane Street and Mt. Moriah Road—
  - (i) on Tuesdays, Thursdays and Saturdays—on the western side only;
  - (ii) on Mondays, Wednesdays and Fridays—on the eastern side only;

384      **Chap. 48:50**      *Motor Vehicles and Road Traffic*  
[Subsidiary]      *Traffic Restriction (San Fernando) Order*

---

Two-way traffic.      **5.** While this Order is in force, vehicular traffic may proceed on St. Joseph Road in both an easterly and westerly direction.

No right turn.      **6.** No vehicular traffic travelling along the undermentioned roads shall turn right on reaching the Bye-Pass—  
    (a) East along St. Joseph Road; and  
    (b) West along Forres Avenue.

Vehicular route.      **7.** While this Order is in operation, vehicular traffic proceeding South along the Bye-Pass may turn West into St. Joseph Road.

Removal and impounding of vehicles unlawfully parked.      **8.** Without prejudice to any other liability incurred by the commission of a summary offence, vehicles found parked in contravention of the foregoing provisions of this Order may be removed by the police and impounded and otherwise dealt with in accordance with sections 108 and 109 of the Motor Vehicles and Road Traffic Act.

---

**NOTICE**

242/1986.  
[10/2003].

**NOTICE OF EXEMPTION FROM REQUIREMENT  
TO HOLD A DRIVER'S PERMIT ISSUED IN A  
FOREIGN COUNTRY**

*made under section 56A(2)*

NOTICE is hereby given in accordance with section 56A(2) of the Motor Vehicles and Road Traffic Act that the holders of a valid driving permit issued in any of the countries listed in the Schedule shall, whilst such permit remains valid, be exempted for a period of three months commencing on the date of his arrival in Trinidad and Tobago, from the requirement to hold a driving permit issued under the Act.

**SCHEDULE**

Albania	Ecuador
Algeria	Egypt
Anguilla	Federal Republic of Germany
Antigua/Barbuda	Fiji
Argentina	Finland
Australia	France
Austria	Ghana
Bangladesh	Greece
Barbados	Grenada
Belgium	Guatemala
Belize	Guyana
Benin	Haiti
Botswana	Holy See
Brazil	Hungary
Bulgaria	Iceland
Canada	India
Central African Republic	Ireland
Chile	Israel
Congo	Italy
Cuba	Ivory Coast
Cyprus	Jamaica
*Czechoslovakia	Japan
Democratic Kampuchea	Jordan
Denmark	Lao People's Democratic Republic
Dominica	Lebanon
Dominican Republic	Lesotho

\*Czechoslovakia is now divided between the Czech Republic and Slovakia.

Luxembourg	San Marino
Madagascar	Senegal
Malawi	Sierra Leone
Malaysia	Singapore
Mali	Spain
Malta	Sri Lanka
Monaco	St. Kitts/Nevis
Morocco	St. Lucia
Netherlands	St. Vincent and the Grenadines
New Zealand	Sweden
Niger	Switzerland
Nigeria	Syrian Arab Republic
Norway	Thailand
Papua New Guinea	Togo
Paraguay	Tunisia
People's Republic of China	Turkey
Peru	Uganda
Philippines	*Union of Soviet Socialist Republics
Poland	United Kingdom
Portugal	United States of America
Republic of Korea	Venezuela
Romania	†Yugoslavia
Rwanda	Zaire

\*The Union of Soviet Socialist Republics is now divided between Armenia, Azerbaijan, Belarus, Estonia, Georgia, Kazakhstan, Kyrgyzstan, Latvia, Lithuania, Moldova, Russia, Tajikistan, Turkmenistan, Ukraine and Uzbekistan.

†Yugoslavia is now divided between Bosnia-Herzegovina, Croatia, Macedonia, Slovenia and FR Yugoslavia.

**TRAFFIC CONTROL REGULATIONS**

ARRANGEMENT OF REGULATIONS

REGULATION

1. Citation.

**PART I  
PORT-OF-SPAIN**

2. Maxi-taxi stand.
3. No entry to maxi-taxis.
4. No entry to taxis.
5. Parking prohibited.
6. Parking.
7. Entry and exit from Richmond Street.
8. One-way traffic.

**PART II  
TUNAPUNA**

9. One-way traffic.
10. Parking.
11. Parking prohibited.

**PART III  
CUREPE**

12. No stopping or parking.

**PART IV  
ARIMA**

13. One-way traffic.
14. No parking, stopping or waiting.
15. Parking prohibited.
16. Parking permitted.
17. No entry to maxi-taxis.

**PART V  
SANGRE GRANDE**

18. One-way traffic.

REGULATION

**PART VI  
MARABELLA**

19. One-way traffic.

**PART VII  
ST. MARGARET'S**

20. Major road.

**PART VIII  
TOBAGO**

21. Parking prohibited.  
22. Two-way traffic.  
23. Left turn.  
24. Right turn.  
25. Carrington Street.  
26. No right turn.  
27. Goods vehicles.  
28. Road closure.

**PART IX  
PRINCES TOWN**

29. Two-way traffic.  
30. No right turn.  
31. No left turn.  
32. Maxi-taxi stand.

**PART X  
CHAGUARAMAS**

33. Speed limit.

**PART XI  
SAN JUAN**

34. One-way streets.

**PART XII  
GENERAL**

35. Weight limits on main roads.  
36. Removal and impounding of vehicles unlawfully parked.
-

**TRAFFIC CONTROL REGULATIONS**

90/1993.

*made under section 100*

1. These Regulations may be cited as the Traffic Control Regulations. Citation.

**PART I**

**PORT-OF-SPAIN**

2. Maxi-taxi drivers plying route one (Cocorite) may park in the area bounded by Abercromby Street, Chacon Street, Independence Square North and Independence Square South. Maxi-taxi stand.

3. Maxi-taxis are prohibited on—

No entry to maxi-taxis.

- (a) Frederick Street, between Park Street and Independence Square North;
- (b) Charlotte Street, between Duke Street and Queen Street;
- (c) Queen Street, between Charlotte Street and Chacon Street;
- (d) Duke Street, between Henry Street and Pembroke Street;
- (e) Independence Square North, between Chacon Street and Nelson Street; and
- (f) Park Street, between St. Vincent Street and Charlotte Street.

4. Taxis shall not enter—

No entry to taxis.

- (a) Henry Street, between Independence Square North and Queen Street;
- (b) Frederick Street, between Hart Street and Independence Square North; and
- (c) Queen Street, between Henry Street and Chacon Street.

5. Parking is prohibited on the following roads:

Parking prohibited.

- (a) the northern side of Kew Place, between Philipps Street and Richmond Street;

- (b) the northern side of Marli Street, between Woodford Street and Maraval Road;
- (c) Richmond Street, between Independence Square North and Independence Square South;
- (d) Rapsey Street, between Wainwright Street and Saddle Road;
- (e) the eastern side of Cipriani Boulevard, for a distance of forty metres North of Tragarete Road;
- (f) the southern side of Keate Street, between Chancery Lane and Abercromby Street;
- (g) the western side of Abercromby Street, between Gordon Street and Keate Street;
- (h) the eastern side of Victoria Avenue, between New Street and Tragarete Road; and
- (i) Colville Street, between Tragarete Road and Ariapita Avenue, between the hours of 7.00 a.m. and 5.00 p.m. on Mondays to Fridays.

Parking.

**6. Motorists may park their vehicles on—**

- (a) the southern side of Marli Street, between Woodford Street and Maraval Road except in the immediate vicinity of the Embassy of the Federal Republic of Germany as marked; and
- (b) the eastern side of Abercromby Street, between Keate Street and Gordon Street.

Entry and exit from Richmond Street.

**7. Motorists may enter and exit Richmond Street, between Independence Square North and Independence Square South through the Independence Square North intersection.**

One-way traffic.

**8. Motorists shall proceed—**

- (a) in an easterly direction on Roberts Street, between French Street and Colville Street;
- (b) in a westerly direction on Kitchener Street, between Colville Street and French Street;

- (c) in an easterly direction on Baden-Powell Street, between French Street and Colville Street;
- (d) in a westerly direction on Buller Street, between Colville Street and French Street; and
- (e) in a northerly direction on Stephens Road, Maraval.

**PART II**

**TUNAPUNA**

**9. Motorists shall proceed—**

- (a) in a westerly direction on Sapodilla Street, between St. Vincent Street and Bowen Street;
- (b) in a northerly direction on Bowen Street, between Sapodilla Street and Cornell Street; and
- (c) in a southerly direction on St. Vincent Street, between Francis Street and the Eastern Main Road.

One-way traffic.

**10. Motorists may park on Pasea Main Road, between Bharrat Trace and Churchill-Roosevelt Highway on the eastern side on Mondays, Wednesdays and Fridays and on the western side on Tuesdays, Thursdays and Saturdays.**

Parking.

**11. Parking is prohibited on—**

- (a) Macoya Road, between Back Street and the Priority Bus Route; and
- (b) Bharrat Trace, between Pasea Main Road and Centenary Street.

Parking prohibited.

**PART III**

**CUREPE**

**12. Motorists shall not stop or park on the Southern Main Road, between Churchill-Roosevelt Highway and a point one hundred and twenty-five metres South of the Churchill-Roosevelt Highway.**

No stopping or parking.

**PART IV**

**ARIMA**

One-way traffic.

**13. Motorists shall proceed—**

- (a) in a clockwise direction around the Princess Royal Park;
- (b) in a southerly direction on Pro Queen Street, from Robinson Circular to Railway Road;
- (c) in a northerly direction on Railway Road, from the Priority Bus Route to Robinson Circular;
- (d) in a southerly direction on Industry Street, from Anglican Street to Hollis Avenue;
- (e) in a southerly direction on St. Joseph Street, from Sorzano Street to Hollis Avenue;
- (f) in a northerly direction on Woodford Street, from Hollis Avenue to Sorzano Street;
- (g) in a southerly direction on Queen Street, from Sorzano Street to Hollis Avenue;
- (h) in a westerly direction on Farfan Street, from Cocorite Street to St. Joseph Street;
- (i) in a westerly direction on Rose Street, between St. Joseph Street and King Street;
- (j) in an easterly direction on Green Street, between King Street and Cocorite Street;
- (k) in an easterly direction on Sorzano Street, between King Street and Prince Street;
- (l) in a southerly direction on Raglan Street;
- (m) in a northerly direction on Prince Street, from Broadway to Sorzano Street;
- (n) in an easterly direction on Devenish Street, from Queen Street to Cocorite Street;
- (o) in a westerly direction on De Verteuil Street, from Llanos Street to Pro Queen Street; and
- (p) in a westerly direction on Quesnel Street, from Nelson Street to Pro Queen Street.

**14.** Motorists shall not park, stop or wait on the following roads from 6.00 a.m. to 8.00 p.m. on Mondays to Fridays and from 6.00 a.m. to 1.00 p.m. on Saturdays: No parking, stopping or waiting.

- (a) the western side of Queen Street, between Broadway and Devenish Street; and
- (b) the northern side of Hollis Avenue, between Pro Queen Street and St. Joseph Street.

**15.** Except for taxi drivers operating from taxi stands, motorists shall not park on the following roads from 6.00 a.m. to 8.00 p.m. on Mondays to Fridays and from 6.00 a.m. to 1.00 p.m. on Saturdays: Parking prohibited.

- (a) on Green Street, between Cocorite Street and Woodford Street;
- (b) on Cocorite Street, between Broadway and Quesnel Street;
- (c) on Sorzano Street, between St. Joseph Street and Queen Street;
- (d) on Farfan Street, between Woodford Street and Cocorite Street;
- (e) on Pro Queen Street, between Devenish Street and Quesnel Street;
- (f) on Broadway, between St. Joseph Street and Woodford Street;
- (g) on Prince Street, between Sorzano Street and Broadway;
- (h) on Lopez Street, between Industry Street and King Street on the northern side; and
- (i) on the eastern side of Queen Street, between Broadway and Devenish Street.

**16.** Motorists may park on—

- (a) the northern side of Sorzano Street, between Queen Street and Prince Street and on the southern side, between King Street and Woodford Street;

Parking permitted.

- (b) the western side of King Street, between Lopez Street and Sorzano Street;
- (c) the western side of St. Joseph Street, between Broadway and Sorzano Street;
- (d) the western side of Woodford Street, between Hollis Avenue and Sorzano Street;
- (e) the southern side of Farfan Street and Rose Street, between Woodford Street and King Street;
- (f) the southern side of Green Street, between King Street and Woodford Street;
- (g) De Verteuil Street, between Llanos Street and Pro Queen Street;
- (h) the eastern side of Industry Street, between Anglican Street and Hollis Avenue; and
- (i) the southern side of Robinson Circular Road, between Pro Queen Street and Railway Street.

No entry to maxi-taxis.

**17. Maxi-taxis are prohibited on—**

- (a) Broadway, between Prince Street and Queen Street;
- (b) Queen Street, between Broadway and Hollis Avenue; and
- (c) Railway Road Extension, between Railway Road and the Eastern Main Road.

**PART V**

**SANGRE GRANDE**

One-way traffic.

**18. Motorists shall proceed—**

- (a) in a westerly direction on River Street, between Foster Road and Ojoe Road; and
- (b) in a southerly direction on Railway Extension Road, between River Street and Brierley Street.

**PART VI**

**MARABELLA**

19. Motorists shall proceed in an easterly direction on Market Street, between the Southern Main Road and Industry Lane. One-way traffic.

**PART VII**

**ST. MARGARET'S**

20. Old Southern Main Road at its intersection with Ramdhany's Road is deemed a major road. Major road.

**PART VIII**

**TOBAGO**

21. Parking is prohibited on—

- (a) Gardenside Street, between Darrell Spring Road and Carrington Street from 7.00 a.m. to 5.00 p.m. from Mondays to Fridays;
- (b) Picton Street, between 7.00 a.m. to 5.00 p.m. from Mondays to Fridays.

Parking prohibited.

22. Motorists may proceed in both directions on Hamilton Street. Two-way traffic.

23. Motor vehicles weighing over three thousand kilogrammes proceeding North along Jerningham Street may turn left onto Piggott Street. Left turn.

24. Motorists—

- (a) driving motor vehicles weighing over three thousand kilogrammes proceeding West on Hamilton Street may turn right onto Carrington Street;
- (b) proceeding South on Wilson Road from the Claude Noel Highway may turn right onto Dutch Fort Street;
- (c) proceeding North along Castries Street may turn right onto Carrington Street.

Right turn.

25. Motorists proceeding West on Carrington Street may continue to do so beyond its intersection with Castries Street. Carrington Street.

396 **Chap. 48:50** *Motor Vehicles and Road Traffic*

**[Subsidiary]** *Traffic Control Regulations*

No right turn. **26.** Motorists proceeding out of the Scotia Bank Car Park shall not turn right into Gardenside Street.

Goods vehicles. **27.** No more than six goods vehicles may be parked at Scarborough Market Square, adjacent to Wilson Road from Mondays to Fridays.

Road closure. **28.** The following roads shall be closed to vehicular traffic:  
(a) Silk Cotton Trace, from Crompstain Trace southwards;  
(b) Gaskin Bay Road, from a point two hundred and thirty metres South of Store Bay Local Road southwards;  
(c) Killigwyn Bay Road, from a point two hundred and thirty metres South of Store Bay Local Road southwards.

#### PART IX

#### PRINCES TOWN

Two-way traffic. **29.** Motorists may proceed in both directions on Railway Road.

No right turn. **30.** Motorists proceeding in a westerly direction on the Naparima-Mayaro Road shall not turn right onto Railway Road.

No left turn. **31.** Motorists proceeding in an easterly direction on the Naparima-Mayaro Road shall not turn left onto Railway Road.

Maxi-taxi stand. **32.** Maxi-taxis plying for hire shall park on Tramline Street, from a point fifty-five metres West of the intersection of the Naparima-Mayaro Road and Railway Road.

#### PART X

#### CHAGUARAMAS

Speed limit. **33.** Motorists may not exceed a speed limit of fifty kilometres per hour on the following roads:

- (a) Airways Road;
- (b) Tucker Valley Road;

- (c) Bellerand Road;
- (d) Edith Falls Road; and
- (e) Elder Road.

**PART XI**

**SAN JUAN**

**34. Motorists shall proceed—**

One-way streets.

- (a) in a northerly direction only on Saddle Road from Eastern Main Road to Real Street from 3.00 p.m. to 8.00 p.m. on Mondays to Fridays except on Public Holidays;
- (b) in a northerly direction only on Saddle Road between Real Street and Mission Road from 7.00 a.m. to 9.00 a.m. and from 3.00 p.m. to 8.00 p.m. on Mondays to Fridays and from 7.00 a.m. to 2.00 p.m. on Saturdays except on Public Holidays.

**PART XII**

**GENERAL**

**35. The maximum M.G.W. allowed on the following main roads are:**

Weight limits on main roads.

Arima-Blanchisseuse Road	...	...	...	8 tonnes
Brasso-Tamana Road	...	...	...	8 tonnes
Brasso-Chickland Road	...	...	...	5 tonnes
Brighton Road	...	...	...	8 tonnes
Caparo Valley-Brasso Road	...	...	...	8 tonnes
Caroni Savannah Road	...	...	...	5 tonnes
Cunapo Southern Road	...	...	...	5 tonnes
Caura Royal Road	...	...	...	5 tonnes
Cedar Hill Road	...	...	...	8 tonnes
Guaracara-Tabaquite Road	...	...	...	8 tonnes
La Pastora Road	...	...	...	5 tonnes
Long Circular Road	...	...	...	8 tonnes
Manzanilla-Mayaro Road	...	...	...	5 tonnes
Mayaro-Guayaguayare Road	...	...	...	5 tonnes
Morne Coco Road	...	...	...	5 tonnes
Maracas Royal Road	...	...	...	5 tonnes
Valencia Road	...	...	...	5 tonnes

398      **Chap. 48:50**      *Motor Vehicles and Road Traffic*  
[Subsidiary]      *Traffic Control Regulations*

---

Removal and  
impounding of  
vehicles  
unlawfully  
parked.

**36.** Without prejudice to any other liability incurred by the commission of a summary offence, vehicles found parked in contravention of these Regulations may be removed by the Police and impounded and dealt with in accordance with section 108(1)(b) of the Motor Vehicles and Road Traffic Act.

UNOFFICIAL

**MOTOR VEHICLES (SEAT BELT ASSEMBLIES)  
REGULATIONS**

ARRANGEMENT OF REGULATIONS

**REGULATION**

1. Citation.
2. Interpretation.
3. Acceptable seat belt assembly.
4. Required standard of seat belt assemblies.
5. Anchorage points.
6. All motor vehicles to be fitted with seat belt assemblies.
7. Additional requirements in respect of seat belt assemblies.
8. Proper installation and configuration of seat belts.
9. Exemption certificate.

210/1994.      **\*MOTOR VEHICLES (SEAT BELT ASSEMBLIES)  
REGULATIONS**

*made under section 43A*

Citation.      **1.** These Regulations may be cited as the Motor Vehicles  
(Seat Belt Assemblies) Regulations.

Interpretation.      **2.** In these Regulations—

“Act” means the Motor Vehicles and Road Traffic Act;

“anchorage points” means that part of the motor vehicle which is  
designed to hold securely in position on the vehicle seat  
belts for the driver’s seat and the specified passengers’ seats;

“motor vehicles” means a vehicle required, under section 43A  
and B of the Act, to be fitted with a seat belt;

“seat belt assembly” means an assembly of straps with quick release  
coupling devices, adjusting devices and an attachment and  
deployment system which deploys automatically, requires no  
action by the occupant, is anchored to a power-driven vehicle  
and is intended to be worn by an occupant of a motor vehicle.

Acceptable seat  
belt assembly.

**3.** Every seat belt assembly shall be of a type the  
designation of which shall be any of the following:

(a) a lap belt which is a seat belt assembly that is  
anchored at two points and passes across the  
front of the wearer’s pelvic region from one side  
of the hip to the other side;

(b) a diagonal belt which is a seat belt assembly,  
that is anchored at two points and passes  
diagonally across the front of the chest from the  
hip to the opposite shoulder;

(c) a three-point belt which is a seat belt assembly,  
that is anchored at three points and passes across  
the front of the wearer’s pelvic region and across  
the front of the chest from the hip to the  
opposite shoulder;

(d) any other seat belt assembly that is duly certified  
by the Trinidad and Tobago Bureau of Standards.

\*These Regulations took effect on 1st January 1995.

4. (1) Every—

- (a) rigid part of a seat belt assembly namely the release devices, retractors and belt adjusting devices; and
- (b) strap of a seat belt assembly namely the restraining and deployment straps and their material, weave, dimensions and strength,

Required standard of seat belt assemblies.

shall conform to either the Trinidad and Tobago Standard, (TTS) 31 60 505—Seat Belt Assemblies for Automobiles or the Trinidad and Tobago Standard, (TTS) 31 60 519—Seat Belt Assemblies for Motor Vehicles or any other standard approved by the Trinidad and Tobago Bureau of Standards.

(2) Every seat belt assembly shall have legibly and permanently affixed to it a label showing a mark of certification approved by the Trinidad and Tobago Bureau of Standards (TTBS) which shall include one or more of the following:

- (a) the Trinidad and Tobago Bureau of Standards (TTBS) standard mark;
- (b) the Japanese Industrial Standard Mark (JIS);
- (c) an indication of conformity to the Federal Motor Vehicle Safety Standard (FMVSS 290);
- (d) an approved European Economic Community Mark (EEC);
- (e) an approved Economic Commission for Europe Mark (ECE);
- (f) the British Standards Institute Kitemark (BSI);
- (g) the Australian Standard Mark;
- (h) any other mark approved by the Trinidad and Tobago Bureau of Standards (TTBS).

(3) The label referred to in subregulation (2) shall also have legibly and permanently marked on it the name of the manufacturer of the seat belt or his trade mark and country of origin.

5. Every motor vehicle shall be equipped with anchorage points which shall conform to any standard approved by the Trinidad and Tobago Bureau of Standards.

Anchorage points.

All motor vehicles to be fitted with seat belt assemblies.

**6.** (1) Every motor vehicle shall have fitted to the front seat three-point seat belt assemblies.

(2) Every motor vehicle with seating that accommodates three people at the front shall be equipped with three-point seat belt assemblies fitted to the seating positions of the driver and the passenger at the extreme left or right, as the case may be, and a lap belt in the seating position between that of the driver and the passenger.

(3) The diagonal seat belt assembly may be fitted to a seating position in the front of the vehicle only if there is a compensatory knee panel fitted to the dashboard panel of the vehicle at the seating position in which the diagonal belt is fitted.

Additional requirements in respect of seat belt assemblies.

**7.** Every seat belt assembly shall be securely affixed to the anchorage points and shall be designed, constructed, installed, maintained, and worn in such a manner that when deployed it will operate satisfactorily and thereby reduce the risk of injury to the person wearing it in the event of a collision or abrupt vehicle deceleration by limiting the mobility of the wearer's body.

Proper installation and configuration of seat belts.

**8.** (1) Every seat belt shall be installed in such a manner that—

- (a) the straps are not liable to assume a dangerous configuration; and
- (b) when deployed, the risk of the strap slipping from the shoulder and the risk of the straps deteriorating through contact with rigid parts of the vehicle or seat structure is reduced to a minimum.

(2) The installation and configuration of all seat belts and any compensatory knee panels shall conform to either—

- (a) the Trinidad and Tobago Standard (TTS) 31 60 505;
- (b) the Trinidad and Tobago Standard (TTS) 31 60 519; or

(c) any other standard approved by the Trinidad and Tobago Bureau of Standards.

9. (1) A person who desires to be exempt from wearing a seat belt on grounds other than medical grounds shall apply for an exemption certificate from the Transport Commissioner.

(2) The Transport Commissioner in providing an applicant with an exemption certificate shall indicate on the certificate whether the exemption is to be permanent or temporary and, if temporary, the duration of the exemption.

(3) A person who holds a valid exemption certificate signed by the Transport Commissioner and has the certificate in his possession shall be exempt from wearing a seat belt.

(4) A holder of a valid exemption certificate or a medical certificate occupying the front seat of a motor vehicle in motion who is not wearing a seat belt shall have either on his person or in the motor vehicle his certificate for production as required under subregulation (5).

(5) A person referred to in subregulation (4) shall, on being so required by any member of the Police Service, give his name and address and produce his certificate.

(6) A person who fails to comply with either subregulation (4) or (5) is liable to a fine of five hundred dollars.

Exemption  
certificate.

**TRAFFIC SIGNS AND PEDESTRIAN  
CROSSINGS ORDER**

ARRANGEMENT OF CLAUSES

CLAUSE

**PART I  
PRELIMINARY**

1. Citation.
2. Definitions.

**PART II  
“PELICAN” CROSSINGS**

3. “Pelican” crossing.
4. Vehicular traffic light signals.
5. Pedestrian light signals.
6. Manner of indicating vehicular approach to “Pelican” crossings.
7. Manner of placing traffic signals.
8. Significance of vehicular traffic light signals.
9. Significance of traffic signs for pedestrians.
10. Prohibitions against the waiting of vehicles and pedestrians at “Pelican” crossings.
11. Imperfect traffic signals at “Pelican” crossings.

**PART III  
“ZEBRA” PEDESTRIAN CROSSING**

12. “Zebra” crossings.
13. “Zebra” controlled area.
14. Variation of number of marks.
15. *(Repealed by LN 241/2001).*
16. Traffic signs (Globes).
- 16A. Traffic signs (Wig Wags).
17. Prohibitions against the waiting of vehicles and pedestrians.
18. Prohibition against waiting and overtaking.
19. Precedence of pedestrian over vehicles.
20. Imperfections of “Zebra” crossing and “Zebra” controlled area.

**SCHEDULE.**

---

**TRAFFIC SIGNS AND PEDESTRIAN  
CROSSINGS ORDER**

1/1993.  
[241/2001].

*made under section 64(2)*

**PART I**

**PRELIMINARY**

1. This Order may be cited as the Traffic Signs and Pedestrian Crossings Order. Citation.

2. (1) In this Order—

Definitions.

“the Act” means the Motor Vehicles and Road Traffic Act;

“appropriate authority” means the Minister or any person acting under his directions exercising the powers under this Order;

“carriageway” does not include that part of any road which consists of a street refuge or central reservation, whether within the limits of a crossing or not;

“central reservation” means any provision, not consisting of a street refuge, made in a road for separating one part of the carriageway of that road from another part of that carriageway for the safety or guidance of vehicular traffic using that road;

“crossing” or “Pedestrian crossing” means a crossing for pedestrian crossing established under clause 3 or clause 12;

“Diagram” means a diagram set out in the Schedule;

Schedule.

“one-way road” means a road on which the driving of any vehicle is prohibited otherwise than in a specific direction;

“Pelican crossing” means a crossing, the presence and limits of which are indicated in accordance with clause 3;

“stop line”, in relation to the driver of a motor vehicle approaching a “Pelican” crossing, means the white line indicating the approach to that crossing which is parallel to the limits of the crossing and on the same side of the crossing as the driver;

“uncontrolled ‘Zebra’ crossing” means a “Zebra” crossing at which traffic is not for the time being controlled by a constable in uniform or other person authorised by the Act;

“‘Zebra’ controlled area” means, in relation to a “zebra” crossing the area of the carriageway in the vicinity of the crossing and lying on both sides of the crossing or on one side of the crossing, being an area the presence and limits of which are indicated in accordance with clause 13;

“‘Zebra’ crossing” means a crossing the presence and limits of which are indicated in accordance with clause 12.

(2) The terms and expressions used in this Order, but not defined, shall have the same meanings assigned to them in the Act.

## PART II

### “PELICAN” CROSSINGS

“Pelican”  
crossing.

3. The traffic signs which are to be placed at or near a crossing for the purpose of constituting it a “Pelican” crossing shall consist of a combination of—

- (a) vehicular traffic light signals;
- (b) pedestrian light signals; and
- (c) indicators for pedestrians,

of the size, colour and type as hereinafter provided.

Vehicular traffic  
light signals.  
[241/2001].

4. The vehicular traffic light signals shall be as follows:

- (a) three lights shall be used, one red, one amber and one green;
- (b) the lamps showing the aforesaid lights shall be arranged either vertically or horizontally;
- (c) in the vertical arrangement the lamp showing the red light shall be the uppermost and that showing the green light the lowermost;
- (d) in the horizontal arrangement the lamp showing the red light shall be to the left side and the one showing the green light to the right side;
- (e) each lamp shall be separately illuminated;
- (f) the effective diameter of the amber and green lenses shall not be less than 200 millimetres;

- (g) the effective diameter of the red lens shall not be less than 300 millimetres;
- (h) the height of the centre of the lens in the lamp showing the green light from the surface of the carriageway shall not be less than 1.2 metres;
- (i) the distance from the edge of a lens to the edge of the next closest lens shall not be more than 15 millimetres;
- (j) **(Deleted by LN 241/2001);**
- (k) the design of the signals shall meet the specifications given in Diagram 1 in the Schedule. Schedule.

5. (1) The pedestrian light signals shall be of the size, colour and type indicated in Diagram 1 in the Schedule. Pedestrian light signals. [241/2001]. Schedule.

(2) The height of the lower edge of the container enclosing the light signals from the surface of the carriageway shall not be less than 2.1 metres and not more than 2.6 metres.

(3) The said signals shall be so designed that—

- (a) the red icon can be internally illuminated by a steady light or by a flashing light;
- (b) the green icon can be internally illuminated by a steady light; and
- (c) where one signal is illuminated the other is not.

6. (1) Subject to the following provisions of this Order, the approach for vehicular traffic to a “Pelican” crossing shall be indicated by a number of lines marked on the carriageway as is shown in Diagrams 2, 3 and 4 in the Schedule. Manner of indicating vehicular approach to “Pelican” crossings. [241/2001]. Schedule.

(2) On either side of a “Pelican” crossing and parallel to it and 1 800 millimetres away there shall be a transverse stop line 200 millimetres wide painted in white from the edge of the carriageway to its centre on that side of the carriageway on which vehicles approach the crossing in the case of a road that is not a one-way road, and across the entire width of the carriageway in the case of a road that is a one-way road.

- (3) In the case of a road not being a one-way road—
- (a) there shall be a longitudinal continuous white line 150 millimetres wide and 15 metres long along the centre of the carriageway extending from the end of the transverse stop line away from the crossing followed by longitudinal broken line 150 millimetres wide extending from the end of the aforesaid continuous white line and consisting of three strips 5.0 metres long and three gaps 2.0 metres long arranged alternately in such a manner that the first gap adjoins the continuous white line;
  - (b) there shall also be marked a continuous yellow line 100 millimetres wide extending from the extremity of the transverse stop line that is nearer the edge of the carriageway, away from the crossing along and parallel with the edge of the carriageway for a distance of 5 metres.

(4) In the case of a road that is a one-way road, there shall be marked a continuous yellow line 100 millimetres wide extending from either extremity of the transverse stop line away from the crossing along and parallel with the edge of the carriageway for a distance of 5 metres.

(5) Where there is a road refuge or central reservation on a road the transverse stop line referred to in this clause shall extend from the edge of the carriageway, to the road refuge or central reservation.

(6) No vehicle shall be parked on a “Pelican” crossing, or on any portion of the carriageway within the limits defined by the yellow line referred to in subclauses (3) and (4).

7. The light signals at or near any “Pelican” crossing shall be so arranged that—

- (a) each vehicular traffic light signal shall face the stream of traffic it is intended to control;
- (b) each pedestrian light signal at either end of the crossing shall be so placed as to be clearly visible to any person who is about to use the crossing at the other end of the crossing.

8. (1) The vehicular traffic light signals at a “Pelican” crossing shall convey the following meanings: Significance of vehicular traffic light signals.

- (a) the full green signal that vehicular traffic may proceed beyond the stop line and across the crossing;
- (b) the full amber signal shown alone means that vehicular traffic shall not proceed beyond the stop line, or if the stop line is not for the time being visible, beyond the traffic light signal facing traffic on the side of the carriageway on which vehicles approach the crossing, except in the case of a vehicle which when the amber signal shown, is so close to the said line or signal that it cannot safely be stopped before passing the line or signal;
- (c) the combination of the red signal and the full amber signal shall be taken to denote an impending change in the indications given by the signal from red to green but shall not be taken to alter the prohibitory significance of the red signal;
- (d) the red light means that vehicular traffic shall not proceed beyond the stop line, or if the stop line is not for the time being visible, or there is no stop line beyond the traffic light signal facing traffic on the side of the carriageway on which vehicles approach the crossing;
- (e) the green arrow signal shown alone shall be taken to indicate that vehicular traffic may proceed beyond the stop line, but only in the direction indicated by the arrow;
- (f) the combination of the red signal and the green arrow signal shall be taken as prohibiting vehicular traffic to proceed beyond the stop line on the carriageway provided in conjunction with the signals except when proceeding in the direction indicated by the arrow;
- (g) the combination of the red signal and the amber arrow signal shall be taken to indicate that vehicular traffic is prohibited from proceeding

beyond the stop line on the carriageway provided in conjunction with the signals except when proceeding in the direction indicated by the arrow and that vehicles so proceeding shall give way to vehicles proceeding across their path;

- (h) the flashing red signal shall be taken to indicate that vehicular traffic shall stop at the stop line on the carriageway provided in conjunction with the signals and proceed when it is safe to so do;
- (i) the flashing amber signal shall be taken to indicate that vehicular traffic shall reduce speed and not proceed beyond the stop line until it is safe to proceed.

(2) Vehicular traffic shall pass the traffic light signal in accordance with subclause (1) and in so doing shall proceed with due regard to the safety of other users of the road, and subject to the direction of any constable or traffic warden in uniform who may be engaged in the regulation of traffic.

Significance of traffic signs for pedestrians.

**9.** The traffic signs for pedestrians at a “Pelican” crossing shall convey the following warnings and information:

- (a) the red light shown by the pedestrian light signals means that the pedestrian shall not use the crossing;
- (b) the green light shown by the pedestrian light signal means that the pedestrian may use the crossing, and drivers of vehicles shall not cause their vehicles to enter the limits of the crossing while the pedestrian is in the act of crossing;
- (c) where a flashing red light is shown by the pedestrian light signal—
  - (i) a pedestrian who is already on the crossing when the flashing red light is first shown, may continue to use the crossing;
  - (ii) vehicular traffic may proceed across the crossing, but if the pedestrian is on the carriageway within the limits of the

crossing before any part of the vehicle has entered those limits, the pedestrian has the right of precedence within those limits over that vehicle;

- (iii) a pedestrian who is not already on the crossing when the flashing red light is first shown shall not start to cross the carriageway.

**10.** (1) The driver of a vehicle shall not cause the vehicle or any part thereof to stop within the limits of a “Pelican” crossing unless either he is prevented from proceeding by circumstances beyond his control or it is necessary for him so to stop in order to avoid an accident.

Prohibitions against the waiting of vehicles and pedestrians at “Pelican” crossings.

(2) A pedestrian shall not remain on the carriageway within the limits of a “Pelican” crossing longer than is necessary for the purpose of passing over the crossing with reasonable despatch.

**11.** A “Pelican” crossing shall not be deemed to have ceased to be indicated in accordance with this Order by reason only of the imperfection, discolouration or disfigurement of any light or markings, or the failure of any light.

Imperfect traffic signals at “Pelican” crossing. [241/2001].

### PART III

#### “ZEBRA” PEDESTRIAN CROSSINGS

**12.** (1) “Zebra” crossings shall be denoted on a road by alternate black and white stripes painted parallel to the kerb of the said road as shown in Diagram 5 in the Schedule.

“Zebra” crossings.

Schedule.

(2) Each stripe shall be not less than 2.5 metres and not more than 10 metres in length, and not less than 0.04 metre and not more than 0.60 metre in width.

**13.** (1) The traffic signs which are to be placed on a road for the purpose of constituting a “Zebra” controlled area lying either on both sides of the limits of the crossing or only on one side of

“Zebra” controlled area. [241/2001].

Schedule.      such limits and indicating the presence and limits of such an area shall consist of a pattern of lines and type shown in Diagram 6 in the Schedule with the measurements as hereinafter provided.

(2) The pattern of lines shall, subject as hereinafter provided, consist of—

Schedule.      (a) a transverse broken line (hereinafter referred to as the “give-way line”), as indicated in Diagram 6 in the Schedule placed across the carriageway 1 metre from and parallel to the imaginary line caused by the nearest extremities of the black and white strips indicating the limits of the crossing;

(b) two or more longitudinal white broken lines (hereinafter referred to as “zig-zag lines”) placed on the carriageway, or where the road is a dual carriageway road on each part of the carriageway, zig-zag lines containing not less than 4 and not more than 18 white marks and extending away from the crossing at a point 150 millimetres from the nearer edge of the give-way line on the same side of the crossing for such a distance as the appropriate authority may think fit having regard to the angle of the crossing in relation to the edge of the carriageway at the place where the crossing is situated and any other features of the carriageway at that point.

(3) Each mark referred to in subclause (b) shall be 2 000 millimetres in length and not less than 100 millimetres and not more than 150 millimetres in width, and there shall be a space of 150 millimetres separating each mark from the one nearest to it.

(4) Each mark contained in a give-way line or in a zig-zag line may be illuminated by use of a reflecting material.

Variation of number of marks.

**14.** Where the appropriate authority is satisfied, in relation to a particular area in the vicinity of a “Zebra” crossing, that by reason of the layout of or character of the roads in the vicinity of

the crossing it would be impractical to lay the lines as indicated in Diagram 6 in the Schedule and in accordance with clause 13(2), Schedule. the following variations are permitted:

- (a) the number of marks in each zig-zag line may be reduced from 4 to not less than 2;
- (b) a mark contained in a zig-zag line may be varied in length so as to extend for a distance less than 2 metres but not less than 1 metre, and where such variation is made as respects a mark each other mark in each zig-zag line shall be of the same or substantially the same length as that mark, so, however, that the number of marks in each zig-zag line shall not be more than 4 and less than 2.

**15. (Repealed by LN 241/2001).**

**16.** (1) The traffic signs which may be placed at or near a crossing for the purpose of indicating it as a “Zebra” crossing shall consist of globes as indicated in Diagram 7 in the Schedule or danger warning traffic signs. Traffic signs (Globes).  
Schedule.

(2) Such globes shall be—

- (a) yellow in colour;
- (b) not less than 275 millimetres and not more than 335 millimetres in diameter; and
- (c) so mounted on posts that the height of the lowest part of the globe is not less than 2.1 metres and not more than 3.1 metres above the surface of the ground in the immediate vicinity.

(3) Such globes shall be illuminated by a flashing light or by a constant light.

(4) Each post upon which a globe is mounted shall be coloured black and white in alternate horizontal bands, and shall be placed in such a position as to be clearly visible to approaching traffic.

(5) Each such band shall not be less than 275 millimetres nor more than 335 millimetres in width and shall not be marked on any container fixed on any such post which enclosed the apparatus for providing the illumination of a globe.

Traffic signs  
(Wig Wags).  
[241/2001].  
Schedule.

**16A.** (1) The traffic signs which may be placed at or near a crossing for the purpose set out in clause 16 may also consist of Wig Wags as indicated in Diagram 8 of the Schedule.

(2) Wig Wags shall be—

- (a) 300 mm in diameter; and
- (b) so mounted on posts at an average height of 2.5 m above the surface of the ground in the immediate vicinity of the crossing.

(3) The container which houses the apparatus for illumination of a Wig Wag shall be yellow or black in colour.

(4) Wig Wags shall be illuminated by a flashing amber signal.

(5) Each post upon which a Wig Wag is mounted shall be coloured black and white in alternative horizontal bands, and shall be placed in such a position as to be clearly visible to approaching traffic.

(6) Each band shall be 300 mm in width and shall not be marked on any container which encloses the apparatus for providing the illumination of a Wig Wag.

Prohibitions  
against the  
waiting of  
vehicles and  
pedestrians.

**17.** (1) The driver of a vehicle shall not cause the vehicle or any part thereof to stop within the limits of a “Zebra” crossing unless either he is prevented from proceeding by circumstances beyond his control or it is necessary for him to do so in order to avoid an accident.

(2) No pedestrian shall remain on the carriageway within the limits of “Zebra” crossing longer than is necessary for the purpose of passing over the crossing with reasonable despatch.

Prohibition  
against waiting  
and overtaking.

**18.** The driver of a vehicle shall not park, stop his vehicle, or overtake another vehicle within a “Zebra” controlled area.

**19.** (1) A pedestrian shall not cross the carriageway within the vicinity of a “Zebra” crossing except within the limit of the give-way line.

Precedence of pedestrian over vehicles. [241/2001].

(2) Every pedestrian on a “Zebra” crossing has precedence over any vehicle and the driver of the vehicle shall accord such precedence to the pedestrian where the pedestrian came onto the “Zebra” crossing prior to the vehicle.

**20.** (1) A “Zebra” crossing shall not be deemed to have ceased to be indicated in accordance with this Order by reason only of the imperfection, discolouration or disfiguration of any globe, danger warning traffic sign or post, or the failure of the illumination of any globe or danger warning traffic sign.

Imperfections of “Zebra” crossing and “Zebra” controlled area.

(2) A “Zebra” controlled area or its limits shall not be deemed to have ceased to be indicated in accordance with this Order by reason only of the imperfection, discolouration or partial displacement of either a terminal line or one or more of the marks comprised in a give-way line or a zig-zag line, so long as the general indication of any such line is not thereby materially impaired.

416 **Chap. 48:50** *Motor Vehicles and Road Traffic*  
[Subsidiary] *Traffic Signs and Pedestrian Crossings Order*

Clause 4.  
Diagram 1.  
[241/2001].

**SCHEDULE**  
**PELICAN CROSSING—STREET FURNITURE**


red icon

green icon

UNOFFICIAL


**CONTROLLED CROSSING—ROAD MARKINGS  
(ONE-WAY STREET WITH MORE THAN ONE LANE)**

Clause 5.  
Diagram 2.



Clause 5.  
Diagram 3.

**CONTROLLED CROSSING—ROAD MARKINGS  
(SINGLE CARRIAGEWAY—2-DIRECTIONAL TRAFFIC)**



**CONTROLLED CROSSING—ROAD MARKINGS  
(ONE-WAY ONE-LANE STREET)**

Clause 5.  
Diagram 4.

UNOFFICIAL


Clause 12.  
Diagram 5.

**PEDESTRIAN CROSSING**  
**POSSIBLE LAYOUTS**

UNOFFICIAL

**ZEBRA CROSSINGS—ROAD MARKINGS  
(SINGLE CARRIAGEWAY) 2-DIRECTIONAL TRAFFIC**

Clause 13.  
Diagram 6.  
[241/2001].



422      **Chap. 48:50**      *Motor Vehicles and Road Traffic*  
[Subsidiary]      *Traffic Signs and Pedestrian Crossings Order*

---


Clause 16.  
Diagram 7.

## ZEBRA CROSSING—STREET FURNITURE

UNOFFICIAL

ZEBRA CROSSING—STREET FURNITURE  
WIG WAG

Clause 16A.  
Diagram 8.  
[241/2001].



**TRAFFIC CONTROL TAXI STAND LOCATION ORDER**

ARRANGEMENT OF CLAUSES

CLAUSE

1. Citation.

**PART I**

**PORT-OF-SPAIN**

2. Conventional taxi stand location.
3. One-way traffic.
4. Maxi-taxi stand.
5. No entry—taxis and maxi-taxis.
6. No entry—maxi-taxis only.
7. Parking prohibited.
8. No plying for hire.
9. No right turn.

**PART II**

**GENERAL**

10. Offence.
-

**TRAFFIC CONTROL TAXI STAND LOCATION ORDER**

\*[113/1988.  
266/2013].

*made under section 65*

1. This Order may be cited as the Traffic Control Taxi Stand Location Order. Citation.

**PART I**

**PORT-OF-SPAIN**

2. Taxi drivers plying—

Conventional  
taxi stand  
location.

- (a) the San Juan route may park on the southern side of Independence Square South, between George Street and Charlotte Street and facing North on the western side of George Street, between Independence Square South and South Quay;
- (b) the Chaguanas/San Fernando route may park on the southern side of Independence Square North, between Henry Street and Charlotte Street;
- (c) the Cunupia/Enterprise “Round-the-Road” route may park on the southern side of Independence Square North, between George Street and Charlotte Street;
- (d) the St. James route may park on the northern side of Hart Street, between Abercromby Street and Frederick Street;
- (e) the St. Ann’s route may park on the southern side of Hart Street, between Abercromby Street and Frederick Street;
- (f) the Belmont/Gonzales route may park on the western side of Charlotte Street, between Queen Street and Prince Street;
- (g) the Carenage route may park on the southern side of Tragarete Road, between Green Corner and Edward Street;

\*See Act No. 9 of 2017 for further amendments to this Order.

- (h) the Maraval route may park on the southern side of Duke Street, between George Street and Charlotte Street and on the western side of George Street, between Duke Street and Prince Street;
- (i) the Pashley Street/Prizgar Lands route may park on the southern side of Queen Street, between Nelson Street and Duncan Street;
- (j) the Trou Macaque route may park on the southern side of Independence Square North, between Nelson Street and Duncan Street;
- (k) the Cascade route may park on the northern portion of the western side of Charlotte Street, between Queen Street and Prince Street;
- (l) the Morvant route may park on the northern side of Independence Square North, between George Street and Nelson Street;
- (m) the Long Circular route may park on the southern side of Independence Square North, between Cipriani Circle and Chacon Street;
- (n) the Diego Martin/Petit Valley route may park on the southern side of Independence Square North, between Chacon Street and Abercromby Street, on the eastern side of Abercromby Street, between Independence Square North and South and on the northern side of Independence Square South, between Chacon Street and Abercromby Street;
- (o) the Tunapuna/Curepe route may park on the southern side of Independence Square North from five metres East of Broadway to five metres West of Henry Street;
- (p) the Arima/Sangre Grande route may park facing a south-westerly direction on the northern side of Independence Square South from a point five metres West of Henry Street to a point five metres West of Broadway;
- (q) from the Marine Square taxi stand may park facing East on the south-western section of

Cipriani Circle and on the northern side of Independence Square South, between Cipriani Circle and Chacon Street; and

- (r) the Laventille Road/Port-of-Spain route shall park on the eastern side of Nelson Street from Prince Street, extending northwards with ten taxis facing South as marked.

**3. Motorists shall proceed—**

One-way traffic.

- (a) in a northerly direction only on Charlotte Street, between Independence Square South and South Quay;
- (b) in a southerly direction only on Henry Street, between Independence Square South and South Quay.

**4. Maxi-taxi drivers plying—**

Maxi-taxi stand.

- (a) the West Bound route may park on the Independence Square parking lots, between Chacon Street and Abercromby Street;
- (b) the Maraval route may park on the southern side of Duke Street, between Charlotte Street and Henry Street;
- (c) the Carenage route may park facing East on the northern side of Park Street, between Edward Street and Green Corner;
- (d) the Sangre Grande/La Horquetta route may park facing North on the western side of the parking allotment on Broadway;
- (e) the Maloney/Arima via the Churchill-Roosevelt Highway route may park facing South on the eastern side of the parking allotment on Broadway;
- (f) the Eastern Main Road route may park facing North on the western side of Charlotte Street, between Independence Square South and South Quay;

- (g) the Round-the-Road route may park on the eastern side of Charlotte Street within a distance of five metres South of Independence Square North, between Independence Square South and Independence Square North;
- (h) the Long Circular route may park not more than two (2) small maxi-taxis or one (1) large maxi-taxi facing East in the designated spaces just South of Independence Square North on the western side of Cipriani Circle;
- (i) the San Fernando route may park on the southern side of Independence Square South, between Henry Street and Charlotte Street;
- (j) the Morvant route may park on the southern side of Queen Street, between George Street and Nelson Street.

No entry—taxis  
and maxi-taxis.

**5. Taxis and maxi-taxis may not enter the following streets:**

- (a) Queen Street, between Henry Street and Abercromby Street;
- (b) Henry Street, between Independence Square North and Queen Street;
- (c) Frederick Street, between Hart Street and Independence Square North.

No entry—  
maxi-taxis only.

**6. Maxi-taxis may not enter—**

- (a) Independence Square North, between Chacon Street and a point 12 metres West of the intersection of Independence Square North with Broadway and between a point two metres East of Broadway on Independence Square North to Nelson Street;
- (b) Independence Square South, between Nelson Street and Charlotte Street; and
- (c) George Street, between South Quay and Independence Square South.

7. Motorists with the exception of taxi drivers operating in taxi stands may not park on— Parking prohibited.

- (a) Independence Square North, between St. Vincent Street and Duncan Street;
- (b) Independence Square South, between Duncan Street and Abercromby Street;
- (c) Prince Street, between Frederick Street and Charlotte Street;
- (d) the eastern side of George Street, between Independence Square South and South Quay;
- (e) the eastern side of Charlotte Street, between South Quay and Independence Square South;
- (f) Henry Street, between Independence Square South and South Quay.

8. Taxi drivers with the exception of taxi drivers operating in taxi stands may not ply for hire their taxis or maxi-taxis on Independence Square North and Independence Square South, between St. Vincent Street and Duncan Street. No plying for hire.

9. Vehicular traffic may not turn North from Independence Square South into the following roads: No right turn.

- (a) George Street;
- (b) St. Vincent Street;
- (c) Henry Street.

**PART II**  
**GENERAL**

10. Any person who contravenes any of the provisions of this Order is guilty of an offence and is liable on summary conviction to a fine of five hundred dollars or to imprisonment for three months. Offence.

**PORT-OF-SPAIN TRANSIT CENTRE  
(TAXI STAND) ORDER**

ARRANGEMENT OF CLAUSES

CLAUSE

1. Citation.
  2. Taxi stand.
  3. Access—Red and Green Band maxi-taxis.
  4. Access to taxi stand—6.00 a.m. to 9.00 a.m.
  5. Parking, stopping restricted.
  6. Parking prohibited.
  7. Offence.
-

**PORT-OF-SPAIN TRANSIT CENTRE  
(TAXI STAND) ORDER**

\*[226/1997].

*made under section 65*

1. This Order may be cited as the Port-of-Spain Transit Centre (Taxi Stand) Order. Citation.

2. That area of the compound of the Public Transport Service Corporation, hereinafter called “the taxi stand”, which is bounded by the Beetham Highway, Broadway, South Quay and St. Ann’s River is hereby designated as a taxi stand for the parking of maxi-taxis. Taxi stand.

3. Maxi-taxis plying routes two and three (Red and Green Bands) shall access the taxi stand via the St. Ann’s River bridge. Access—  
Red and  
Green Band  
maxi-taxis.

4. (1) Between the hours of 6.00 a.m. and 9.00 a.m. from Monday to Friday, maxi-taxis shall proceed as follows: Access to taxi  
stand—6.00 a.m.  
to 9.00 a.m.

(a) maxi-taxis may enter the taxi stand at the western end of the Priority Bus Route and proceed in a westerly direction to the designated off-loading areas on Platforms 1, 2, 3, and 4 and after off-loading proceed in the direction so indicated by way of the Holding Bay to the Ready Bay;

(b) maxi-taxis plying for hire along—

(i) the Port-of-Spain to San Fernando route utilising the Priority Bus Route, the Churchill-Roosevelt Highway and the Solomon Hochoy Highway, may proceed in a westerly direction from the Ready Bay onto Platform 6 to their loading position at Bay A on the western side of the taxi stand and park facing North;

(ii) the Port-of-Spain to Chaguanas route utilising the Priority Bus Route and Solomon Hochoy Highway, may proceed

\*See Act No. 9 of 2017 for further amendments to this Order.

- in a westerly direction from the Ready Bay onto Platform 6 to their loading position at Bay B on the western side of the taxi stand and park facing North;
- (iii) the Port-of-Spain to Arima route utilising the Eastern Main Road, may proceed in a westerly direction from the Ready Bay onto Platform 6 to their loading position at Bay C on the western side of the taxi stand and park facing North;
  - (iv) the Port-of-Spain to Sangre Grande route utilising the Eastern Main Road, the Priority Bus Route and the Churchill-Roosevelt Highway, may proceed in a westerly direction from the Ready Bay onto Platform 6 to their loading position at Bay D on the western side of the taxi stand and park facing North;
  - (v) the Port-of-Spain to Arima route utilising the Priority Bus Route, may proceed in a westerly direction from the Ready Bay behind Platform 6, then North onto Platform 5 to their loading position at Bay A on the western side of the taxi stand and park facing North;
  - (vi) the Port-of-Spain to Maloney route utilising the Priority Bus Route and the Churchill-Roosevelt Highway, may proceed in a westerly direction from the Ready Bay, then North onto Platform 5 to their loading position at Bay B on the western side of the taxi stand and park facing North;
  - (vii) the Port-of-Spain to La Horquetta route utilising the Priority Bus Route and the Churchill-Roosevelt Highway, may

- proceed in a westerly direction from the Ready Bay behind Platform 6, then North onto Platform 5 to their loading position at Bay C on the western side of the taxi stand and park facing North;
- (viii) the Port-of-Spain to Morvant route utilising the Eastern Main Road, may proceed in a westerly direction from the Ready Bay behind Platform 6 then North onto Platform 5 to their loading position at Bay D on the western side of the taxi stand and park facing North.
- (2) At all other times, maxi-taxis shall proceed as follows:
- (a) maxi-taxis may enter at the western end of the Priority Bus Route and proceed in a westerly direction to the designated off-loading area on Platform 1, and after off-loading proceed in the direction so indicated to the Ready Bay;
- (b) maxi-taxis plying for hire along—
- (i) the Port-of-Spain to Morvant route utilising the Eastern Main Road; may proceed in a westerly direction from the Ready Bay onto Platform 6 to their loading position at Bay A on the western side of the taxi stand and park facing North;
- (ii) the Port-of-Spain to Arima route utilising the Eastern Main Road, may proceed in a westerly direction from the Ready Bay onto Platform 6 to their loading positions at Bays B, C and D on the western side of the taxi stand and park facing North;
- (iii) the Port-of-Spain to Sangre Grande route utilising the Eastern Main Road, the Priority Bus Route or the Churchill-Roosevelt Highway, may proceed in a westerly direction from the Ready Bay

behind Platform 6, turning North onto Platform 5 to their loading positions at Bays A and B on the western side of the taxi stand and park facing North;

- (iv) the Port-of-Spain to Chaguanas route utilising the Priority Bus Route and the Solomon Hochoy Highway, may proceed in a westerly direction from the Ready Bay behind Platform 6, then North onto Platform 5 to their loading positions at Bay C on the western side of the taxi stand and park facing North;
- (v) the Port-of-Spain to San Juan route utilising the Eastern Main Road, may proceed in a westerly direction from the Ready Bay behind Platform 6, then North onto Platform 5 to their loading position at Bay D on the western side of the taxi stand and park facing North;
- (vi) the Port-of-Spain to Maloney route utilising the Priority Bus Route and the Churchill-Roosevelt Highway, may proceed in a westerly direction from the Ready Bay behind Platforms 6 and 5, then onto Platform 4 to their loading positions at Bays A and B on the western side of the taxi stand and park facing North;
- (vii) the Port-of-Spain to La Horquetta route utilising the Priority Bus Route and the Churchill-Roosevelt Highway, may proceed in a westerly direction from the Ready Bay behind Platforms 6 and 5, then North onto Platform 4 to their loading positions at Bays C and D on the western side of the taxi stand and park facing North;

- (viii) the Port-of-Spain to San Fernando route utilising the Priority Bus Route, the Churchill-Roosevelt Highway and the Solomon Hochoy Highway, may proceed in a westerly direction from the Ready Bay behind Platforms 6, 5 and 4, then North onto Platform 3 to their loading positions at Bays A and B on the western side of the taxi stand and park facing North;
- (ix) the Port-of-Spain to Chaguanas route utilising the Churchill-Roosevelt Highway and the Southern Main Road, may proceed in a westerly direction from the Ready Bay behind Platforms 6, 5 and 4, then North onto Platform 3 to their loading position at Bay C on the western side of the taxi stand and park facing North;
- (x) the Port-of-Spain to Arima route utilising the Priority Bus Route, may proceed in a westerly direction from the Ready Bay behind Platforms 6, 5, 4 and 3, then North onto Platform 2 to their loading positions at Bays A, B, C and D on the western side of the taxi stand and park facing North.

5. Maxi-taxis shall not park, stop or wait in the designated areas immediately East or West of the building which houses the Maxi-Taxi (Route 2) Association. Parking, stopping restricted.

6. No vehicles other than maxi-taxis may park in the taxi stand. Parking prohibited.

7. Any person who contravenes the provisions of this Order is liable on summary conviction to a fine of five hundred dollars or imprisonment for a period not exceeding three months. Offence.

**PORT-OF-SPAIN TRANSIT CENTRE (PUBLIC SERVICE  
VEHICLE STATION) REGULATIONS**

ARRANGEMENT OF REGULATIONS

**REGULATION**

1. Citation.
2. Interpretation.
3. Appointment as Public Service Vehicle Station.
4. Issue of permits to owners and operators.
5. Regulation of conduct of owners and operators.
6. Conductor's permit.
7. Holding Bay.
8. Ready Bay.
9. Loading Bay.
10. Refusal of passenger.
11. Cancellation or suspension of permits.
12. Appeals.
13. General.
14. Offence.

**SCHEDULE.**

---

**PORT-OF-SPAIN TRANSIT CENTRE (PUBLIC  
SERVICE VEHICLE STATION) REGULATIONS**

\*[227/1997].

*made under section 100*

1. These Regulations may be cited as the Port-of-Spain  
Transit Centre (Public Service Vehicle Station) Regulations. Citation.

2. In these Regulations— Interpretation.

“Authorised officer” means any member of the management and staff of the Corporation duly authorised by the Corporation; and includes Customer Service Representatives duly appointed by the Corporation, Automotive Licensing Officers, Traffic Wardens, Police Officers and duly precepted Security Officers;

“Corporation” means the Public Transport Service Corporation;

“Holding Bay” means that area of the Corporation’s compound immediately preceding the Ready Bay and designated for use by public service vehicles;

“Loading Bay” means that area of the Corporation’s compound designated for use by public service vehicles for the loading or taking up of passengers;

“Manager” means the person appointed as Manager of the Port-of-Spain Transit Centre;

“Off-loading platform” means that area of the Corporation’s compound designated for the dropping off or discharge of passengers from public service vehicles;

“operator” means the holder of a valid permit under section 6A of the Maxi-Taxi (Amendment) Act, 1994 and includes the driver of a public service vehicle; Sub. Leg.  
3 of 1994.

“owner” means a registered maxi-taxi owner under section 6 of the Maxi-Taxi (Amendment) Act, 1994;

“passenger” means any person who hires a public service vehicle and includes any person who enters the vehicle with the permission of its owner or operator;

“persistent offender” means any person found guilty of a breach of any of these Regulations on more than three occasions;

---

\*See Act No. 9 of 2017 for further amendments to this Order.

438      **Chap. 48:50**      *Motor Vehicles and Road Traffic*  
[Subsidiary]      *Port-of-Spain Transit Centre (Public Service Vehicle Station) Regulations*

Ch. 48:53.      “public service vehicle” means a maxi-taxi as defined under section 2 of the Maxi-Taxi Act;

“Ready Bay” means that area of the Corporation’s compound immediately preceding the Loading Bay and designated for use by public service vehicles;

“touting” means speaking or making noises or sounds in order to attract the attention of the public or possible passengers, and includes noisome and frequent demands or the persistent following of the public or possible passenger for the purpose of holding out a public service vehicle for hire to the public or possible passenger;

Legal Notice No. 226/1997.      “Transit Centre” means the taxi stand as defined by the Port-of-Spain Transit Centre (Taxi Stand) Order, made under the Motor Vehicles and Road Traffic Act;

“Users” include owners, operators, conductors and passengers who use the Transit Centre.

Appointment as Public Service Vehicle Station.      **3.** (1) That area of the Corporation’s compound which is bounded by the Beetham Highway, Broadway, South Quay and St. Ann’s River is hereby appointed a station for public service vehicles.

(2) The Corporation is authorised to make reasonable charges for the use of any accommodation on its property so provided.

Issue of permits to owners and operators. Schedule. Form 1.      **4.** (1) The owner or operator of a public service vehicle who desires to use the Transit Centre shall apply to the Corporation in the manner set out in Form 1 of the Schedule.

(2) Upon receipt of an application form under subregulation (1) and the payment of a fee of one hundred dollars from an owner or twenty-five dollars from an operator, the Corporation upon being satisfied that such owner or operator is a fit and proper person to use the Transit Centre shall issue to such owner or operator a permit in the manner set out in Form 2 of the Schedule.

Schedule. Form 2.      (3) The Corporation shall not issue a permit to an owner or operator of any public service vehicle where the vehicle is not registered or does not carry valid insurance.

(4) A permit issued under subregulation (2) shall have a duration of one year from the date of issue and shall be renewable upon application in the manner set out in Form 3 of the Schedule.

Schedule.  
Form 3.

5. Any owner or operator of any public service vehicle operating within the Transit Centre who—

Regulation of  
conduct of  
owners and  
operators.

- (a) takes up passengers on the designated off-loading platform or in any other area other than that specifically appointed for such purpose;
- (b) engages in touting;
- (c) employs any person as a conductor who is not the holder of a valid permit issued under these Regulations;
- (d) loiters within the Transit Centre for the purpose of taking up passengers; or
- (e) leaves or permits to be left on any roadway within the Transit Centre any vehicle which has broken down, without taking immediate steps to have it removed to an area so designated by the Corporation without reasonable excuse,

shall be guilty of an offence under these Regulations.

6. (1) A person who is the holder of a Conductor's Permit under the Motor Vehicles and Road Traffic Act shall be required to hold a Conductor's Permit to operate within the Transit Centre.

Conductor's  
permit.

(2) Application for such a permit shall be made in the manner set out in Form 4 of the Schedule.

Schedule.  
Form 4.

(3) The Corporation on being satisfied that the applicant is a fit and proper person to operate as a conductor on a public service vehicle within the Transit Centre, shall upon the payment of a fee of twenty-five dollars grant to the successful applicant a permit in the manner set out in Form 2 of the Schedule.

Schedule.  
Form 2.

(4) A permit shall have a duration of one year from the date of issue, and shall be renewable upon application in the manner set out in Form 3 of the Schedule.

Schedule.  
Form 3.

440      **Chap. 48:50**      *Motor Vehicles and Road Traffic*  
[Subsidiary]      *Port-of-Spain Transit Centre (Public Service Vehicle Station) Regulations*

Holding Bay.      **7.** (1) Public service vehicles whilst in the Holding Bay shall be parked in the manner prescribed by an authorised officer of the Corporation.

(2) An owner or operator of a public service vehicle shall only cause his vehicle to leave the Holding Bay for the purpose of answering calls according to its priority of position.

(3) On the departure of any public service vehicle from the Holding Bay, the vehicle immediately behind it shall move forward and occupy the vacant space and in the like manner other vehicles in the rear shall move forward in the line and occupy the vacant spaces immediately in the front of them.

Ready Bay.      **8.** (1) An owner or operator of a public service vehicle shall only cause his vehicle to enter the Ready Bay for the purpose of answering calls according to its priority of position.

(2) An owner or operator of a public service vehicle shall not cause his vehicle to leave the Ready Bay until instructed to do so by an authorised officer of the Corporation.

Loading Bay.      **9.** Upon leaving the Ready Bay, an owner or operator shall, prior to loading, hand in his position number to an authorised officer located in the area so designated, and then take his vehicle to the Loading Bay as indicated by its position number.

Refusal of passenger.      **10.** An owner or operator shall not refuse to take up any passenger bound for any destination stated on a Loading Bay without reasonable excuse.

Cancellation or suspension of permits.      **11.** The Manager may suspend or cancel the permit of any owner, operator or conductor upon being satisfied that such owner, operator or conductor is—

- (a) a persistent offender; or
- (b) otherwise deemed unfit by the Manager to hold a permit.

**12.** The Corporation shall hear and determine any appeal Appeals. submitted by an aggrieved person against any decision to cancel or suspend his permit and the decision of the Corporation thereon shall be final and conclusive.

**13.** All users of the Transit Centre shall be required to General. observe such operating conditions as shall be prescribed by the Corporation from time to time.

**14.** An owner, operator or conductor who contravenes any of Offence. these Regulations shall be guilty of an offence and liable on summary conviction to a fine of five hundred dollars for a first offence and one thousand dollars for each subsequent offence.

442 **Chap. 48:50** *Motor Vehicles and Road Traffic*  
[Subsidiary] *Port-of-Spain Transit Centre (Public Service Vehicle Station) Regulations*

Regulation  
4(1).

**SCHEDULE**

**FORM 1**

**PUBLIC TRANSPORT SERVICE CORPORATION  
PORT-OF-SPAIN TRANSIT CENTRE FACILITY**

Form of particulars to be given by Applicant for Registration for a Public Service Vehicle Permit to use Transit Centre

1	Full name of owner	
2	Postal address or residence of owner	
3	Full name of driver/operator (1)	
4	Postal address of driver/operator (1)	
5	Full name of driver/operator (2)	
6	Postal address of driver/operator (2)	
7	Description or type of vehicle	
8	Type and colour of body and seating accommodation	
9	Make of vehicle and year of manufacture	
10	Chassis number	
11	Registration number	
12	Name of Company with which insured	
13	Number of policy	
14	Date policy expires	
15	Weight for registration purposes	
16	Are you the registered owner of a Maxi-Taxi?	
17	State are you the holder of a permit to operate a Maxi-Taxi	
18	If yes, state registration certificate/permit number and date of issue	

.....  
*Date*

.....  
*Signature*

N.B: It is an offence under the Motor Vehicles and Road Traffic Act, Chap. 48:50 to give any particulars which are not correct and you will be liable to prosecution if you do so.

**FORM 2**

Regulation 4(2).

**PUBLIC TRANSPORT SERVICE CORPORATION**

(FRONT)

PHOTOGRAPH	REPUBLIC OF TRINIDAD AND TOBAGO		
	TRANSIT CENTRE PASS CONDUCTOR/ OWNER/OPERATOR/DRIVER		
	Issue Date	Expiry Date	
	Birth Date	Sex	Class
	Permit Number	Date of Payment	
SIGNATURE OF HOLDER	Classification:		
	<input type="checkbox"/> Owner		
	<input type="checkbox"/> Operator/Driver		
<input type="checkbox"/> Conductor			
AUTHORISED SIGNATURE			

444

**Chap. 48:50** *Motor Vehicles and Road Traffic*

[Subsidiary]

*Port-of-Spain Transit Centre (Public Service Vehicle Station) Regulations*

(BACK)

Reminder Notice

This Permit is valid for one (1) year from the date of First Issue or Anniversary

Date of Renewal.

NOTES

---

Transaction Code:

- A FIRST ISSUE
  - B RENEWAL
  - C DUPLICATE
  - D ENDORSEMENT
-

**FORM 3**

Regulation 4(4).

**PUBLIC TRANSPORT SERVICE CORPORATION PORT-OF-SPAIN  
TRANSIT CENTRE FACILITY**

**RENEWAL OF TRANSIT CENTRE PASS**

1	Type of Pass applied for	[ ] Motor vehicle [ ] Conductor
2	Full name of applicant	
3	Sex	
4	Place of Birth	
5	Date of Birth	
6	Nationality	
7	Residential Address	
8	Postal address if different from above	
9	Are you the holder of a Transit Centre Pass?	[ ] Yes [ ] No
	Have you previously been the holder of a Transit Centre Pass?	[ ] Yes [ ] No
	If yes, state number and date of issue	
	Maxi-Taxi Registration No.	
10	Give particulars of any pass which you held or now hold	
11	Have you at any time been disqualified from obtaining a Transit Centre Pass?	[ ] Yes [ ] No
12	If yes, give particulars	

.....  
*Date*

.....  
*Signature of Applicant*

N.B.: It is an offence under the Motor Vehicles and Road Traffic Act, Chap. 48:50 to give any particulars which are false or in any material respect misleading and you will be liable to prosecution if you do so.

(BACK)

**DECLARATION IN RESPECT OF APPLICATION FOR  
DUPLICATE TRANSIT CENTRE PASS FOR  
OWNER/OPERATOR/DRIVER/CONDUCTOR**

I, .....  
of .....

in the Republic of Trinidad and Tobago do solemnly and sincerely declare as follows:

1. I am the holder of ..... No. ....  
which was issued/renewed for the year 20.....
2. The said ..... No. .... was lost or stolen, on or about  
the ..... day of .....  
and although I have made a diligent search for the said .....  
..... I have been unable to find same.
3. The said ..... No. .... was destroyed on or about  
the ..... day of ..... 20.....

And I make this declaration conscientiously believing the same to be true and according to the Statutory Declarations Act, Chap. 7:04 and I am aware that if there is any statement in this declaration which is false in fact, which I know or believe to be false or do not believe to be true I am liable to fine and imprisonment.

Declared at .....  
this ..... day of ..... 20 .....

Before Me,

.....  
*Commissioner of Affidavits*

\_\_\_\_\_

FORM 4

Regulation 6(2).

**PUBLIC TRANSPORT SERVICE CORPORATION  
PORT-OF-SPAIN TRANSIT CENTRE FACILITY**

Form of Particulars to be given by Applicant for Conductor's Permit

1	Full name of applicant	
2	Postal address or residence of applicant	
3	State date of birth of applicant	
4	Are you the holder of a conductor's permit, or have you at any time previously been the holder of a conductor's permit, if so state number and date of issue	
5	State particulars of any endorsement on any conductor's or driver's permit which you hold or have	
6	Have you at any time been disqualified from obtaining a conductor's or driver's permit? If so, give particulars as to the Court by whom, the date on which and the period for which the disqualification was imposed	

.....  
*Date*

.....  
*Signature*

N.B.: It is an offence under the Motor Vehicles and Road Traffic Act, Chap. 48:50 to give any particulars which are not correct and you will be liable to prosecution if you do so.

**PRIORITY BUS ROUTE  
(TRAFFIC CONTROL) ORDER**

ARRANGEMENT OF CLAUSES

CLAUSE

1. Citation.
2. Conditional use of route.
3. No left turn—eastbound traffic.
4. No left turn—westbound traffic.
5. No right turn—eastbound traffic.
6. No right turn—westbound traffic.
7. Stopping prohibited.
8. Offence.

\_\_\_\_\_

**PRIORITY BUS ROUTE  
(TRAFFIC CONTROL) ORDER**

\*[99/1988].

*made under section 65*

1. This Order may be cited as the Priority Bus Route (Traffic Control) Order. Citation.

2. Drivers of maxi-taxis and other vehicles authorised by the Minister may use the Priority Bus Route (hereinafter called “the Route”) subject to the following conditions: Conditional use of route.

(a) drivers proceeding westwards may enter the Route at—

(i) Five Rivers, Arouca and exit at Orange Grove Road, Tunapuna; and

(ii) Sargeant Street East, Tunapuna and exit into Port-of-Spain via Abattoir Road, West of the flyover bridge;

(b) drivers proceeding eastwards may enter the Route at—

(i) Abattoir Road, West of the flyover bridge, Port-of-Spain and exit in Tunapuna via Sargeant Street West; and

(ii) Orange Grove Road, Tunapuna and exit at Five Rivers, Arouca;

(c) no driver shall park along the Route; and

(d) drivers of maxi-taxis shall ply for hire at designated maxi-taxi stops only.

3. (1) Drivers proceeding eastwards along the Route shall not turn left at the following intersections: No left turn—eastbound traffic.

(a) Croisee, San Juan;

(b) Curepe, except for drivers of PTSC buses; and

(c) Scott Street.

(2) Drivers of maxi-taxis proceeding eastwards along the Route shall not turn left at Centenary Street, Tunapuna.

\*See Act No. 9 of 2017 for further amendments to this Order.

450      **Chap. 48:50**      *Motor Vehicles and Road Traffic*  
[Subsidiary]      *Priority Bus Route (Traffic Control) Order*

---

No left turn—  
westbound  
traffic.

**4.** Drivers proceeding westwards along the Route shall not turn left at the following intersections:

- (a) Aranguez Road;
- (b) Sixth Avenue.

No right turn—  
eastbound  
traffic.

**5.** Drivers proceeding eastwards along the Route shall not turn right at the following intersections:

- (a) Sixth Avenue;
- (b) Aranguez Road.

No right turn—  
westbound  
traffic.

**6.** (1) Drivers proceeding westwards along the Route shall not turn right at the following intersections:

- (a) Scott Street;
- (b) Curepe;
- (c) Croisee, San Juan; and
- (d) Abattoir Road, West of the flyover.

(2) Drivers of maxi-taxis proceeding westwards along the Route shall not turn right at Centenary Street, Tunapuna.

Stopping  
prohibited.

**7.** Drivers shall not stop along the Route within a distance of—

- (a) one hundred metres in either direction from any intersection; or
- (b) one hundred metres in either direction from any bus terminus,

except that drivers of maxi-taxis may stop at the designated maxi-taxi stops.

Offence.

**8.** A driver who contravenes this Order is guilty of an offence and is liable on summary conviction to a fine of five hundred dollars or imprisonment for three months.

**PRIORITY BUS ROUTE  
(SPECIAL ROADS TOLL) REGULATIONS**

ARRANGEMENT OF REGULATIONS

**REGULATION**

1. Citation.
  2. Definitions.
  3. Prohibition.
  4. Application to the Minister.
  5. Tolls.
  6. Duration of permit.
  7. Permit subject to conditions.
  8. Penalty.
-

[Subsidiary]

\*[75/1988].

**PRIORITY BUS ROUTE  
(SPECIAL ROADS TOLL) REGULATIONS**

*made under section 100 (n)*

Citation.      **1.** These Regulations may be cited as the Priority Bus Route (Special Roads Toll) Regulations.

Definitions.      **2.** In these Regulations—  
“applicant” means an owner who applied to the Minister under regulation 4 for permission to operate a maxi-taxi on the Priority Bus Route;  
“Licensing Authority” has the meaning assigned to it by the Motor Vehicles and Road Traffic Act;  
“owner” means the owner of a maxi-taxi;  
“quarter” means a period of three months or less expiring on 31st March; 30th June; 30th September or 31st December;  
“Route” means the Priority Bus Route classified under section 3 of the Highways Act;  
Ch. 48:01.      “toll” means the fee payable for a permit issued under regulation 5(1).

Prohibition.      **3.** No owner shall operate or cause to be operated, his maxi-taxi along the Route unless he is in possession of a permit issued by the Minister authorising him to do so.

Application to the Minister.      **4.** An owner who is desirous of operating his maxi-taxi along the Route shall apply in writing to the Minister for a permit to do so.

Tolls.      **5.** (1) The successful applicant shall receive a permit issued by the Minister upon payment of a toll in the amount of three hundred dollars.

(2) The toll referred to in subregulation (1) is payable in advance by the owner to the Licensing Authority and is non-refundable.

---

\*See Act No. 9 of 2017 for further amendments to this Order.

**6.** The grant of a permit is for the duration of one quarter and is renewable upon application by the owner in accordance with regulation 4. Duration of permit.

**7.** The Minister may attach to the grant of the permit such conditions as he thinks fit. Permit subject to conditions.

**8.** An owner who contravenes these Regulations is guilty of an offence and liable on summary conviction to a fine of two hundred and fifty dollars. Penalty.

[Subsidiary]

266/2009.

**MOTOR VEHICLES AND ROAD TRAFFIC  
(APPROVAL OF DEVICE FOR QUANTITATIVE  
MEASURING OF THE PROPORTION OF ALCOHOL IN  
A PERSON'S BREATH) ORDER**

*made under section 70C(13)*

Citation.

**1.** This Order may be cited as the Motor Vehicles and Road Traffic (Approval of Device for Quantitative Measuring of the Proportion of Alcohol in a Person's Breath) Order.

Approved  
devices for  
evidential  
breath testing.

**2.** The Minister approves the following devices to be used for the purpose of the quantitative measuring of the proportion of alcohol in a person's breath:

- (a) RBT IV manufactured by Intoximeters Inc., of St. Louis, Missouri;
- (b) FC 20 manufactured by Lifeloc Technologies, Inc. (formerly Lifeloc, Inc.) of Wheat Ridge, Colorado; and
- (c) Intoxilyser 400 PA manufactured by CMI Inc., Owensboro, Kentucky.

---

**MOTOR VEHICLES AND ROAD TRAFFIC  
(APPROVAL OF DEVICE FOR OBTAINING AN  
INDICATION OF ALCOHOL IN A PERSON'S  
BREATH) ORDER**

267/2009.

*made under section 70B(9)*

1. This Order may be cited as the Motor Vehicles and Road Traffic (Approval of Device for Obtaining an Indication of Alcohol in a Person's Breath) Order. Citation.

2. The Minister approves the following devices to be used for the purpose of obtaining an indication of alcohol in a person's breath: Approved devices for preliminary breath sampling.

- (a) Lion Alcolmeter® AlcoBlow® manufactured by Lion Laboratories Ltd;
- (b) Alco Sensor FST manufactured by Intoximeters Inc.;
- (c) Breathalyser Dräger Alcotest 6510 manufactured by Dräger Safety A.G. and Company; and
- (d) AlcoBlow® manufactured by CMI Inc., Owensboro, Kentucky.

**MOTOR VEHICLES AND ROAD TRAFFIC  
(MOBILE DEVICES) REGULATIONS**

ARRANGEMENT OF REGULATIONS

**REGULATION**

1. Citation.
  2. Commencement.
  3. Interpretation.
  4. Prohibition on driving while holding or using a hand-held mobile device.
  5. Restrictions on supervising the holder of a provisional permit.
  6. Use of hands-free devices permitted.
  7. Prohibition on electronic messaging while driving.
  8. Limitation on application of regulations 4, 5 and 7 to certain persons.
  9. Limitation on application of regulations 4, 5 and 7 in certain circumstances.
-

**MOTOR VEHICLES AND ROAD TRAFFIC (MOBILE  
DEVICES) REGULATIONS**

[281/2010  
9 of 2017].

*made under section 100*

1. These Regulations may be cited as the Motor Vehicles and Road Traffic (Mobile Devices) Regulations.

Citation.

2. These Regulations came into effect on 2nd February 2011.

Commencement.

3. (1) In these Regulations—

Interpretation.

“interactive communications function” includes—

- (a) sending or receiving oral or written message;
- (b) sending or receiving facsimile;
- (c) sending or receiving still or moving images; and
- (d) providing access to the internet;

“mobile device” means a mobile telephone or any other device, other than a two-way radio, which performs an interactive communication function by transmitting and receiving data;

“provisional permit” means a provisional permit to drive issued under section 42 of the Act;

“two-way radio” means any wireless telecommunications apparatus which is designed or adapted—

- (a) for the purpose of transmitting and receiving spoken messages; and
- (b) to operate on any frequency other than 880 MHz to 915 MHz, 925 MHz to 960 MHz, 1710 MHz to 1785 MHz, 1805 MHz to 1880 MHz, 1900 MHz to 1980 MHz or 2110 MHz to 2170 MHz; and

“wireless communication device” means a device used to transfer information over a distance without the use of electrical conductors or wires.

(2) For the purpose of these Regulations—

- (a) a mobile telephone or other device is to be treated as hand-held if it is held or is required to

be held at some point during the course of making or receiving a call or performing any other interactive communication function; and

- (b) a person supervises the holder of a provisional permit if he does so pursuant to a condition imposed on the provisional permit holder under section 42(4) of the Act.

Prohibition on driving while holding or using a hand-held mobile device.  
[9 of 2017].

**4.** (1) No person shall drive or have charge of a motor vehicle, on any road while holding or using a hand-held mobile device.

(2) A person who contravenes subregulation (1) is liable to a fine of one thousand, five hundred dollars.

Restrictions on supervising the holder of a provisional permit.  
[9 of 2017].

**5.** (1) No person shall supervise the holder of a provisional permit if the person supervising is using a hand-held mobile device.

(2) A person who contravenes subregulation (1) is liable to a fine of one thousand, five hundred dollars.

Use of hands-free devices permitted.

**6.** Notwithstanding regulations 4 and 5, a person may drive a motor vehicle on a road while using a mobile device in hands-free mode.

Prohibition on electronic messaging while driving.  
[9 of 2017].

**7.** (1) No person shall use a wireless communication device to view, send or compose an electronic message while driving or having charge of a motor vehicle.

(2) A person who contravenes subregulation (1) is liable to a fine of one thousand, five hundred dollars.

Limitation on application of regulations 4, 5 and 7 to certain persons.

**8.** Regulations 4, 5 and 7 shall not apply to—

- (a) the driver of an ambulance, fire service vehicle or police service vehicle;
- (b) any other person or class of persons prescribed by the Minister under the Act;

- (c) a person holding or using a device prescribed by the Minister under the Act;
- (d) a person engaged in an activity prescribed by the Minister under the Act; and
- (e) under any other condition or circumstances prescribed by the Minister under the Act.

9. Regulations 4, 5 and 7 shall not apply where the motor vehicle is—

- (a) off the roadway or is lawfully parked on the roadway;
- (b) not in motion; and
- (c) not impeding traffic.

Limitation on application of regulations 4, 5 and 7 in certain circumstances.

460 **Chap. 48:50** *Motor Vehicles and Road Traffic*

---

[Subsidiary]

[60/2016.  
73/2016].

**MOTOR VEHICLES AND ROAD TRAFFIC (SPEED  
MEASURING DEVICE) ORDER**

*made under section 62(6A)*

Citation.

**1.** This Order may be cited as the Motor Vehicles and Road Traffic (Speed Measuring Device) Order.

Approved  
device for  
measuring  
speed of  
vehicles.

**2.** The Minister approves the LTI 20/20 Tru CAM Lidar, manufactured by Laser Technology Inc., as a device to be used for measuring the speed at which a person is driving a motor vehicle.

---

142/2017.

**MOTOR VEHICLES AND ROAD TRAFFIC (SPEED  
MEASURING DEVICE) ORDER**

*made under section 62(6A)*

Citation.

**1.** This Order may be cited as the Motor Vehicles and Road Traffic (Speed Measuring Device) Order.

Approved  
device for  
measuring  
speed of motor  
vehicles.

**2.** The Minister approves the DragonEye Speed LIDAR, manufactured by DragonEye Technology, LLC as a speed measuring device to be used for measuring the speed at which a person is driving a motor vehicle.

---

**MOTOR VEHICLES AND ROAD TRAFFIC  
(FIXED PENALTY PAYMENT METHODS AND PAYEE)  
ORDER**

\*[101/2020].

*made under section 88D*

1. This Order may be cited as the Motor Vehicles and Road Traffic (Fixed Penalty Payment Methods and Payee) Order.

Citation.

2. In this Order—

“Act” means the Motor Vehicles and Road Traffic Act; and

Interpretation.

“fixed penalty” means the penalty prescribed under section 84 of the Act.

Ch. 48:50.

3. Payment of a fixed penalty shall be made in cash, electronic form or by electronic means.

Payment of Fixed Penalty.

4. (1) The Minister, acting in accordance with section 88D(1)(e) of the Act, approves the Trinidad and Tobago Postal Corporation as a payee for the purpose of receiving payment of fixed penalty.

Trinidad and Tobago Postal Corporation approved as payee.

(2) Payment of a fixed penalty under subclause (1) shall be made at any corporate shop of the Trinidad and Tobago Postal Corporation as specified in the Schedule.

**SCHEDULE**

<i>Corporate Shop</i>	<i>Location</i>
(a) Arima Corporate Shop	No. 17 Prince Street, Arima
(b) Bon Accord Corporate Shop	Milford Court, Bon Accord, Tobago
(c) Chaguanas Corporate Shop	Eleanore and Southern Main Road, Chaguanas
(d) La Romaine Corporate Shop	No. 2 Lucky Street, La Romaine

\*LN 101/2020 took effect on 27th May 2010.

L.R.O.

462 **Chap. 48:50** *Motor Vehicles and Road Traffic*

**[Subsidiary]** *Motor Vehicles and Road Traffic (Fixed Penalty Payment Methods and Payee) Order*

<i>Corporate Shop</i>	<i>Location</i>
(e) National Mail Centre Corporate Shop	Nos. 240–250 Golden Grove Road, Piarco
(f) San Juan Corporate Shop	No. 5 Eastern Main Road, San Juan
(g) Scarborough Corporate Shop	No. 19 Dutch Fort, Scarborough, Tobago
(h) St. Ann's Corporate Shop	No. 29 St. Ann's Main Road, St. Ann's
(i) St. James Corporate Shop	Nos. 61–63 Western Main Road, St. James
(j) St. Vincent Street Corporate Shop	Nos. 22–24 St. Vincent Street, Port-of-Spain
(k) Tragarete Road Corporate Shop	No. 177 Tragarete Road, Port-of-Spain
(l) Tunapuna Corporate Shop	Eastern Main Road, Tunapuna

**MOTOR VEHICLES AND ROAD TRAFFIC  
(WINDSCREEN AND WINDOW TINT)  
REGULATIONS**

ARRANGEMENT OF REGULATIONS

**REGULATION**

1. Citation.
2. Interpretation.
3. Prohibition on the use of material on windscreen and window.
4. Prohibition on the use of reflective material.
5. Restriction on the use of curtains or screens.
6. Exemption: Generally.
7. Application for exemption on medical grounds.
8. Void exemption certificate.
9. Requirement to have exemption certificate in vehicle at all times.
10. Register of exemption certificates.
11. Use and approval of light transmittance measuring device.
12. Certificate issued to the driver by constable.
13. Evidence in proceedings.

**SCHEDULE.**

---

\*[281/2020.  
385/2020  
78/2024].

**MOTOR VEHICLES AND ROAD TRAFFIC  
(WINDSCREEN AND WINDOW TINT) REGULATIONS**

*made under section 100*

Citation. **1.** These Regulations may be cited as the Motor Vehicles and Road Traffic (Windscreen and Window Tint) Regulations.

Interpretation. **2.** In these Regulations—

Ch. 48:50. “Act” means the Motor Vehicles and Road Traffic Act;

“anti-glare band overlay” means a tinted overlay that is transparent and that is applied along the top edge of the windscreen for the purpose of reducing glare from the sun;

“body transfer vehicle” means a motor vehicle that is used primarily for the transportation of deceased persons;

“constable” has the meaning assigned to it in section 80 of the Act;

“exemption certificate” means a certificate issued under Regulation 6(2);

“light transmittance measuring device” means a device approved by the Transport Commissioner under regulation 11 for the purpose of measuring visible light transmittance;

“material” means any overlay, film, coating, spray, sticker or other adhesive product, vinyl or paint applied, affixed or fitted to the safety glass on the windscreen or windows of a vehicle, but excludes any glazing or coating added during the manufacture of the vehicle;

“overlay” means a transparent, translucent, opaque, tinted or perforated self-adhesive or clinging film, sticker, wrap or material, including anti-glare band overlays and stoneguard overlays, which are used for—

(a) the purposes of—

(i) reduction of ultraviolet light;

(ii) infrared or visible light transmission;

(iii) advertising;

(iv) identification;

\*These Regulations came into effect on the 3rd August 2020.

- (v) information;
- (vi) protection;
- (vii) aesthetics; or

(b) any other purpose;

“sticker” means a self-adhesive or clinging film, with or without print on it, that is applied for—

(a) the purposes of—

- (i) advertising;
- (ii) identification;
- (iii) information;
- (iv) aesthetics; or
- (v) compliance with any written law; or

(b) any other purpose;

“stone-guard overlay” means a transparent overlay and that is applied along the bottom edge of the windscreen for the purpose of preventing damage to the windscreen from stones and other debris thrown up by other vehicles;

“visible light transmittance” means the proportion of visible light which—

- (a) passes through the glass of a windscreen or window of a vehicle, including any materials affixed to the glass; and
- (b) is expressed as a percentage of the total amount of light falling on the glass, including any materials affixed to the glass, when measured by a light transmittance measuring device in accordance with regulation 11.

“window”, in relation to a vehicle, means—

- (a) a front window;
- (b) a rear window; or
- (c) any other window that enables a person in the vehicle to view outside the vehicle,

but does not include a windscreen;

“windscreen”, in relation to a vehicle, means the front or rear windshield or other exterior viewing device of the vehicle which—

- (a) extends across the front or rear of the vehicle; and
- (b) is not parallel to the vehicle’s longitudinal centre-line.

Prohibition on the use of material on windscreen and window.

**3.** (1) A person shall not cause or permit a vehicle to be used, or drive or have charge of a vehicle, upon any road where a windscreen or window of the vehicle is composed of, coated or covered by, or treated or darkened with, any material, overlay or other product, that has the effect of making the windscreen or window non-transparent or reducing the visible light transmittance of the windscreen or window unless—

- (a) the front windscreen has a visible light transmittance of at least seventy per cent;
- (b) each front window, including any side wing and side window, on either side and forward of the vertical plane immediately behind the driver’s seatback in its rearmost and upright position, has a visible light transmittance of at least thirty-five per cent; and
- (c) each rear window, including any side window behind the front window and the rear windscreen, has a visible light transmittance of at least twenty per cent.

(2) Subregulation (1) does not apply where the material on the windscreen or window was installed by the manufacturer of the vehicle and approved by the Licensing Authority.

(3) Notwithstanding subregulation (1), the front windscreen of a vehicle may have affixed to its top, along its width and in such a position as not to interfere with the vision of

either the driver, or a passenger carried in the front seat, a band of material or an anti-glare band overlay—

(a) which—

- (i) measures in width from the top of the windscreen, no more than fifteen centimetres or six inches; or
- (ii) in the case of a vehicle above Class 3, covers an area above the highest point of the windscreen that is swept by a windscreen wiper; and

(b) which has a visible light transmittance of at least thirty-five per cent.

(4) A person who contravenes subregulation (1) commits a traffic violation and is liable to a fine of five thousand dollars.

**4.** (1) A person shall not cause or permit a vehicle to be used, or drive or have charge of a vehicle, on any road, if a windscreen or window of the vehicle is composed of, coated or covered by, or treated with, any material, overlay or product, that has the effect of making the windscreen or window appear to have a metallic, reflective or mirrored effect sufficient to dazzle motorists.

Prohibition on the use of reflective material.

(2) An owner, driver or operator of the vehicle shall ensure that no windscreen or window of the vehicle has—

- (a) scratches or other defects that unreasonably impair the driver's vision through, or unreasonably compromise the strength of, the windscreen or window;
- (b) laminated glazing or glass that shows signs of discoloration that unreasonably impairs the driver's vision through the windscreen or window; or
- (c) material with any bubbling or other defects that unreasonably impair the driver's vision through the windscreen or window.

(3) A person who contravenes this regulation commits a traffic violation and is liable to a fine of one thousand dollars.

Restriction on the use of curtains or screens.

**5.** (1) An owner, driver or operator of a vehicle shall not install or cause to be installed in the vehicle any curtain, screen or other device that obstructs the view of a person into the vehicle, unless the device is installed by the manufacturer of the vehicle and approved by the Licensing Authority.

(2) A person shall not drive, or have charge of, a vehicle on any road if a curtain, screen or other device that obstructs the view of a person into the vehicle, is installed in the vehicle, unless the device is installed by the manufacturer of the vehicle and approved by the Licensing Authority.

(3) Subregulations (1) and (2) do not apply in the case of a curtain, screen or other device that is being used on a rear window to shield a child five years of age or under from the direct rays of the sun.

(4) A person who contravenes this regulation commits a traffic violation and is liable to a fine of one thousand, five hundred dollars.

Exemption: Generally. [78/2024].

**6.** (1) Regulations 3, 4 and 5 do not apply to the following:

- (a) a person who is issued an exemption certificate on medical grounds under regulation 7 in respect of a vehicle; and
- (b) any of the following vehicles which the Licensing Authority exempts, having regard to the use of the vehicle or the safety of its occupants:
  - (i) any motor vehicle which is the property of or used by the President in his official or personal capacity;
  - (ii) any motor vehicle which is the property of or used by the Prime Minister in his official or personal capacity;
  - (iii) an ambulance registered under the Emergency Ambulance Services and Emergency Medical Personnel Act;

- (iv) any vehicle which is the property of or used by—
  - (A) the Police Service; Ch. 15:01.
  - (B) the Fire Service; Ch. 35:50.
  - (C) the Prison Service; Ch. 13:02.
  - (D) the Defence Force; Ch. 14:01.
  - (E) the Customs and Excise Division; Ch. 78:01.
  - (F) the Strategic Services Agency; or Ch. 15:06.
  - (G) a protective service agency within the meaning of section 2 of the Supplemental Police Act; Ch. 15:02.
- (v) a body transfer vehicle which is the property of and registered for use by an undertaker or funeral home; or
- (vi) any other vehicle authorised, in writing, by the Licensing Authority; and
- (c) any vehicle, for national security purposes only, on the recommendation by the Minister with responsibility for national security, to the Licensing Authority.

(2) Subject to regulation 7, a person or entity who desires an exemption under subregulation (1) shall apply, in writing, to the Licensing Authority for an exemption certificate and the Licensing Authority shall consider the application and may issue or refuse to issue the exemption certificate.

(3) An exemption certificate issued by the Licensing Authority under subregulation (2)—

- (a) shall, in the case of a person, be valid for a period of two years from the date of issue or renewal; or
- (b) may, in the case of a public body or authority, be valid for such period as the Licensing Authority may determine, and shall state whether the vehicle is to be equipped or fitted with dual external rear vision side mirrors on each side of the vehicle.

(4) An exemption certificate issued by the Licensing Authority under subregulation (1) shall specify—

- (a) the minimum visible light transmittance of a windscreen or window; and
- (b) the type of material which may be affixed to a windscreen or window.

(5) An application for an exemption certificate shall be in such form as the Licensing Authority may approve.

(6) An exemption certificate issued by the Licensing Authority under subregulation (2) shall be in such form as the Licensing Authority may approve and shall remain the property of the Licensing Authority.

Application for exemption on medical grounds. [78 /2024].

**7.** (1) An application for exemption on medical grounds under regulation 6(1)(a) shall—

- (a) contain a certificate—
  - (i) completed by a medical practitioner who is registered as a medical specialist in the Medical Specialist Register under the Medical Board Act; and
  - (ii) certifying that the applicant or any other person is suffering from a medical condition listed in the Schedule which renders the person susceptible to harm or injury from exposure to sunlight; and
- (b) contain a declaration by the applicant that the vehicle will be regularly used by, or for the purposes of transporting, the applicant or other person referred to in paragraph (a)(ii).

Ch. 29:50.

(2) A certificate under subregulation (1) shall be submitted to the Licensing Authority within a period of three months from the date of examination as specified in the certificate by the medical practitioner, unless the Licensing Authority grants permission for the certificate to be submitted after the expiration of that period.

**8.** An exemption certificate issued by the Licensing Authority under regulation 6(2) shall immediately become void upon—

Void exemption certificate

- (a) the sale or transfer of the vehicle specified in the certificate;
- (b) the vehicle being destroyed or rendered permanently unserviceable; or
- (c) the death of the person specified in the certificate.

**9.** (1) A holder of an exemption certificate shall—

Requirement to have exemption certificate in vehicle at all times.

- (a) have the certificate in the vehicle at all times; and
- (b) upon request by a constable in uniform, produce the certificate for inspection.

(2) A person who contravenes subregulation (1) commits a traffic violation and is liable to a fine of two thousand dollars.

**10.** (1) The Licensing Authority shall establish and maintain a register of all exemption certificates.

Register of exemption certificates.

(2) The register under subregulation (1) shall contain the following information:

- (a) the name and address of the person specified in the exemption certificate;
- (b) the registration particulars and identification mark of the vehicle specified in the exemption certificate;
- (c) the date of issue and where applicable, the date of expiration of the exemption certificate;
- (d) the conditions upon which the exemption certificate was issued; and
- (e) such other information as the Licensing Authority may determine.

**11.** (1) The visible light transmittance of a windscreen or window of a vehicle shall be measured by a constable in uniform using a light transmittance measuring device approved by the Licensing Authority.

Use and approval of light transmittance measuring device.

(2) For the purposes of subregulation (1), a margin of error of plus or minus three percentage points shall be allowed in relation to the measurement of the visible light transmittance of a windscreen or window.

(3) Where a light transmittance measuring device is approved under subregulation (1), the Licensing Authority shall cause a notice of the approval to be published in the Gazette.

Certificate issued to the driver by constable.

**12.** (1) Where a constable uses a light transmittance measuring device to measure the visible light transmittance of a windscreen or window of a vehicle and the visible light transmittance is in contravention of these Regulations, the constable operating the device shall deliver to the driver of the vehicle a certificate, in writing, that—

- (a) specifies the reading of the measurement of the visible light transmittance of the specified windscreen or window as measured by the light transmittance measuring device;
- (b) includes particulars of the registration and identification mark of the vehicle;
- (c) bears an endorsement by the constable who operated the device, stating the date and time of the measurement of the visible light transmittance of the specified windscreen or window; and
- (d) bears the regimental number, rank, name and signature of the constable who operated the device.

(2) In proceedings for a traffic violation under regulation 3 or 4—

- (a) evidence may be given of the reading of the measurement of the visible light transmittance of the specified windscreen or window of the vehicle, as measured by the light transmittance

measuring device and operated by the constable; and

- (b) the reading of the light transmittance measuring device shall be deemed to be the visible light transmittance of the specified windscreen or window of the vehicle at the time of the alleged occurrence of the traffic violation, unless the owner, driver or operator of the vehicle proves that the visible light transmittance of the specified windscreen or window of the vehicle, exceeded the permissible percentage of the visible light transmittance at that time.

**13.** In proceedings for a traffic violation under regulation 3 or 4 in which evidence is given of the reading of the measurement of the visible light transmittance obtained by a light transmittance measuring device, a certificate purporting to be signed by a constable certifying that—

Evidence in proceedings.

- (a) the light transmittance measuring device used by him to measure the visible light transmittance of the windscreen or window of the vehicle specified therein was approved by the Licensing Authority under regulation 11;
- (b) the measurement was made on the date and completed at the time stated in the certificate;
- (c) the visible light transmittance measured by the device and expressed as a percentage was the visible light transmittance of the windscreen or window of the vehicle on the date and at the time stated in the certificate; and
- (d) the certificate, in writing, required by regulation 12 was delivered in accordance with that regulation, is admissible and is *prima facie* evidence of the particulars certified in the certificate.

Regulation 7.

**SCHEDULE**

For the purposes of regulation 7, medical condition includes—

- (a) albinism;
- (b) chronic actinic dermatitis/actinic reticuloid;
- (c) dermatomyositis;
- (d) lupus erythematosus;
- (e) porphyria;
- (f) xeroderma (pigmentosa) pigmentosum;
- (g) severe drug photosensitivity, provided that the course of treatment causing the photosensitivity is expected to be of prolonged duration;

Regulation 6(1)(a) and 7. [385/2020].

**FORM A**



**Ministry of Works and Transport  
Transport Division**

**APPLICATION FOR TINTED WINDOW EXEMPTION (MEDICAL GROUNDS)**

The Motor Vehicles and Road Traffic (Windscreen and Window Tint) Regulations, 2020 provides that the front windscreen must have at least 70% visible light transmittance (VLT), the anti-glare band (AGB) on the front windscreen (67cm or 1.5m) at least 35% VLT, the front windows at least 35% VLT and the rear windows including the rear windscreen at least 20% VLT. The Regulations provide for an exemption on medical grounds. The exemption certificate, if issued, shall be valid for a period of two (2) years from the date issue, and it shall only apply to the vehicle(s) listed. The exemption certificate must be present in the vehicle at all times. On the sale, transfer of ownership, destruction of the vehicle or death of the certificate holder, the exemption certificate will immediately become void and must be surrendered to the Licensing Authority.

Directions: Please complete form in BLOCK LETTERS. Sections 1-3 must be completed by the applicant/registered owner and Section 4 by a Registered Medical Specialist. The completed application must be returned with a certified copy of the motor vehicle(s) registration in respect of each vehicle listed for section 1 and the previous exemption certificate issued (if applicable) to the Transport Division for processing.

**Section 1: Applicant/Registered Owner Information**

Applicant Name: \_\_\_\_\_  
(Surname, First name)

Address (Street): \_\_\_\_\_

Address (Town/City): \_\_\_\_\_

Mailing Address (if different from above)(Street): \_\_\_\_\_

Address (Town/City): \_\_\_\_\_

Date of Birth: (DD/MM/YYYY) \_\_\_\_\_ I.D.  / D.P.  / PASSPORT #  \_\_\_\_\_

Sex: Male  / Female  Place of Birth: \_\_\_\_\_ Nationality: \_\_\_\_\_

Telephone Number: ( ) - \_\_\_\_\_ Email Address: \_\_\_\_\_

**Section 2 (if applicable): The medical exemption is being requested for someone other than the applicant/registered owner, who will be regularly transported in the vehicle and is suffering from a medical condition:**

Name: \_\_\_\_\_  
(Surname, First name)

Address (Street): \_\_\_\_\_

Address (Town/City): \_\_\_\_\_

Mailing Address (if different from above)(Street): \_\_\_\_\_

Address (Town/City): \_\_\_\_\_

Date of Birth: (DD/MM/YYYY) \_\_\_\_\_ I.D.  / D.P.  / PASSPORT #  \_\_\_\_\_

Sex: Male  / Female  Place of Birth: \_\_\_\_\_ Nationality: \_\_\_\_\_

Telephone Number: ( ) - \_\_\_\_\_ Email Address: \_\_\_\_\_

Relationship to applicant: \_\_\_\_\_ Driver  / Passenger  of vehicle(s) below.

**If the person is a child (under 18 years of age) who will be regularly transported in the vehicle:**

Name of Mother  / Father  / Legal Guardian : \_\_\_\_\_  
(Surname, First name)

Address (Street): \_\_\_\_\_

Address (Town/City): \_\_\_\_\_

Mailing Address (if different from above)(Street): \_\_\_\_\_

Address (Town/City): \_\_\_\_\_

Date of Birth: (DD/MM/YYYY) \_\_\_\_\_ I.D.  / D.P.  / PASSPORT #  \_\_\_\_\_

Parent's Telephone Number: ( ) - \_\_\_\_\_ Email Address: \_\_\_\_\_

I, \_\_\_\_\_ declare that I am the \_\_\_\_\_  
(Relationship)  
of the child whose name is \_\_\_\_\_

Signature of Parent/Legal Guardian

Date: (DD/MM/YYYY)

*Motor Vehicles and Road Traffic*

**Chap. 48:50**

475

*Motor Vehicles and Road Traffic (Windscreen and Window Tint) Regulations*

[Subsidiary]

**FORM A—Continued**

**Section 3: Vehicle Information**  
List vehicle(s) for which this exemption certificate has been requested. (Attach additional sheets if necessary)

Vehicle #1 Vehicle Registration Number	Chassis/VIN Number	Make	Model	Colour
Vehicle #2 Vehicle Registration Number	Chassis/VIN Number	Make	Model	Colour

Is this your first application: Yes  No  If NO, state the Vehicle Registration Number: \_\_\_\_\_

**Declaration of Applicant:**


I, \_\_\_\_\_, hereby declare that (i) the vehicle will be in regular use  
Name of Applicant/Registered Owner

by the applicant  / registered owner  for the purpose of regularly transporting a person, who is suffering from a medical condition and must be shielded from exposure to sunlight while travelling in a vehicle, and (ii) the information provided on this form is true and correct.

\_\_\_\_\_  
Signature of Applicant/Registered Owner

\_\_\_\_\_  
Date (DDMMYYYY)

**N.B:** (1) It is an offence under section 94 of the Motor Vehicles and Road Traffic Act, Chap. 48:50 to give any particulars which are not correct and you will be liable to prosecution if you do so.  
(2) Application must be supported by documents as proof of address such as a recent Utility Bill or in the case of a rental, a copy of the Lease/Rental Agreement for the rental premises identified and bearing the name of the applicant. If the utility bill or Lease/Rental Agreement is not in the applicant's name, a letter from the owner confirming the applicant's residence and copy of the owner's national identification (ID) MUST be submitted.  
(3) Section 4 (page 3) of this application form must be completed by a medical practitioner who is a Registered Medical Specialist in the Medical Specialist Register under the Medical Board Act, Chap. 29:50.  
(4) Application must be supported by a certified copy of the motor vehicle(s) registration in respect of each vehicle listed for section 4 of this application and the previous exemption certificate issued (if applicable).



[2] [OVER]

FORM A—Continued

**Section 4: Certificate of Medical Practitioner**

This section must be completed by a medical practitioner who is a Registered Medical Specialist in the Medical Specialist Register under the Medical Board Act, Chap. 29:50

Applicant Name: \_\_\_\_\_  
(Surname, First name)

Applicant I.D.  / D.P.  / PASSPORT # : \_\_\_\_\_

I certify that I have examined the patient, Mr/Mrs/Miss: \_\_\_\_\_ on \_\_\_\_\_  
(DD/MM/YYYY) and in my opinion was at the time suffering from: \_\_\_\_\_  
(DD/MM/YYYY)

**Medical Condition** (Check the medical condition that applies to the above-named patient)

- albinism;
- chronic actinic dermatitis/actinic reticuloid;
- dermatomyositis;
- lupus erythematosus;
- porphyria;
- xeroderma (pigmentosa) pigmentosum;
- severe drug photosensitivity, provided that the course of treatment causing the photosensitivity is expected to be of prolonged duration;
- photophobia associated with an ophthalmic or neurological disorder; or
- any other condition or disorder causing severe photosensitivity which renders the patient susceptible to harm or injury from exposure to sunlight and the patient is required for medical reasons to be shielded from the direct rays of the sun: \_\_\_\_\_  
Name of Medical Condition

Based on my examination and the information above, I recommend  / do not recommend  the above-named patient to be issued with a medical exemption for tint on a motor vehicle.

Medical Practitioner Name: \_\_\_\_\_  
(Surname, First name)

Registered Qualification(s) and Registration Number(s) of Medical Practitioner: \_\_\_\_\_

Office Address (Street): \_\_\_\_\_

Office Address (Town/City): \_\_\_\_\_

Telephone Number: ( ) - - Email Address: \_\_\_\_\_

I declare that to the best of my knowledge and belief the information given by me is true and correct. I am aware that if there is any statement in this declaration which is false in fact or which I know or believe to be false or do not believe to be true, I am liable on summary conviction to a fine of two thousand dollars in accordance with section 94 of the Motor Vehicles and Road Traffic Act, Chap. 48:50.

Signature of Medical Practitioner: \_\_\_\_\_ Medical Practitioner's Stamp: \_\_\_\_\_ Date: \_\_\_\_\_  
(DD/MM/YYYY)

N.B: It is an offence under section 94 of the Motor Vehicles and Road Traffic Act, Chap. 48:50 to give any particulars which are false or incorrect and you will be liable to prosecution if you do so.

**For Official Use Only:** # \_\_\_\_\_

Approved  Denied

**Term of Exemption** – Two (2) years from date of issue.

Permissible Visible Light Transmittance of Front Windscreen AGB \_\_\_\_\_ % and Windows \_\_\_\_\_ % on vehicle(s) listed above.

Requirements: Dual external rear vision side mirrors: YES  / NO  / Other: \_\_\_\_\_


Date of issue: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

Transport Commissioner \_\_\_\_\_ Date (DD/MM/YYYY) \_\_\_\_\_

11

FORM B

[385/2020].



**Ministry of Works and Transport**  
**Transport Division**

**APPLICATION FOR TINTED WINDOW EXEMPTION**  
**(GENERAL – PROTECTIVE SERVICES AND SECURITY AGENCIES/COMPANIES)**  
**Motor Vehicles and Road Traffic (Windscreen and Window Tint) Regulations, 2020**

The **Motor Vehicles and Road Traffic (Windscreen and Window Tint) Regulations, 2020** provides that the front windscreen must have at least 70% visible light transmittance (VLT), the anti-glare band (AGB) on the front windscreen (6" or 15cm) at least 35% VLT, the front windows at least 35% VLT and the rear windows including the rear windscreen at least 20% VLT. The Regulations provide for exemptions on the grounds of the use of the vehicle and the safety of its occupants. An exemption certificate, if issued, is the property of the Transport Division (Licensing) and shall be present in the vehicle at all times. On the sale, transfer of ownership, destruction of the vehicle or death of the certificate holder, the exemption certificate will immediately become void and must be surrendered to the Transport Division (Licensing).

**Directions: Please complete form in BLOCK Letters and TICK as appropriate.** The completed application must be returned with (i) a certified copy of the motor vehicle(s) registration in respect of each vehicle listed for section 3 and the previous exemption certificate issued (if applicable) to the Transport Division for processing.

**Section 1 – Applicant/registered owner information:** Agency  / Organisation  / Company

Applicant Name: \_\_\_\_\_  
(Surname, First initial)

Position/Job Title: \_\_\_\_\_

Date of Birth: (DD/MM/YYYY) \_\_\_\_\_ I.D.  / D.P.  / PASSPORT # : \_\_\_\_\_

Name of Agency/Organisation/Company: \_\_\_\_\_

Registration Number of Organisation  / Company : \_\_\_\_\_

Address (Street): \_\_\_\_\_

Address (Town/City): \_\_\_\_\_

Mailing Address (if different from above)(Street): \_\_\_\_\_

Address (Town/City): \_\_\_\_\_

Telephone Number: ( ) \_\_\_\_\_ - \_\_\_\_\_ Email Address: \_\_\_\_\_

**Section 2: Entity Classification\***  
The motor vehicle(s) referenced in this application falls into the following category:  
 a vehicle which is the property of or used by agencies and organisations specified under **Reg. 6(1)(b)(i) (ii)&(iv) of MVRT (Windscreen and Window Tint) Regulations, 2020.**  
 an Ambulance registered under the Emergency Ambulance Services and Emergency Medical Personnel Act, Chap. 29:02.  
 a body transfer vehicle which is the property of and registered for use by an undertaker  or funeral home   
 other - specify use of vehicle in relation to operations of organization or company: \_\_\_\_\_

**Section 3: Vehicle Information**  
List vehicle(s) for which this exemption certificate has been requested. (Attach additional sheets if necessary)

Vehicle #1 - Vehicle Registration Number	Chassis/VIN Number	Make	Model	Colour
Vehicle #2 - Vehicle Registration Number	Chassis/VIN Number	Make	Model	Colour
Vehicle #3 - Vehicle Registration Number	Chassis/VIN Number	Make	Model	Colour
Vehicle #4 - Vehicle Registration Number	Chassis/VIN Number	Make	Model	Colour

(i) [OVER]

**FORM B—Continued**


**Declaration of Applicant:**

I, \_\_\_\_\_ of \_\_\_\_\_  
Name of Applicant/Registered Owner Position

\_\_\_\_\_ hereby declare that the  
Agency/Company/Organisation Name  
information provided above is true and correct and hereby apply for an exemption certificate on the grounds stated herein.

\_\_\_\_\_  
Signature of Applicant/Registered Owner Date (DD/MM/YYYY)

N.B: (1) It is an offence under section 94 of the Motor Vehicles and Road Traffic Act, Chap. 48:50 to give any particulars which are not correct and you will be liable to prosecution if you do so.  
(2) All applications must be supported by (i) Company registration and validation documents such as a copy of the company/business registration certificates and/or licence of Directors and (ii) Certificates and approvals for the operation of the organization or company.  
(3) Application must be supported by a certified copy of the motor vehicles' registration in respect of each vehicle listed for section 3 of this application and the previous exemption certificate issued (if applicable).



**For Official Use Only:** # \_\_\_\_\_

Agency  / Organisation  / Company

An Ambulance registered under the Emergency Ambulance Services and Emergency Medical Personnel Act, Chap. 29:02.  
 A body transfer vehicle which is the property of and registered for use by an undertaker or funeral home.  
 A vehicle which is the property of or used by agencies and organisations specified under **Reg. 6(1)(b)(i)(ii)&(iv) of MVRT (Windscreen and Window Tint) Regulations, 2020:**

(A) the Police Service;  
 (B) the Fire Service;  
 (C) the Prison Service;  
 (D) the Defence Force;  
 (E) the Customs and Excise Division;  
 (F) the Strategic Services Agency; or  
 (G) a protective service agency within the meaning of section 2 of the Supplemental Police Act.

Other: \_\_\_\_\_

**Supporting documentation provided:**

■ \_\_\_\_\_  
 ■ \_\_\_\_\_

Total Number of Vehicles for exemption application: \_\_\_\_\_

**Application:**

Approved \_\_\_\_\_ No. of Vehicles  Denied \_\_\_\_\_ No. of Vehicles

**Term of Exemption:**

Permanent: \_\_\_\_\_  
 Temporary: \_\_\_\_\_ Days  / Weeks  / Months  / Years

Date of Issue: \_\_\_\_\_ Expiration Date: \_\_\_\_\_


**Exemption Details:**  
 Permissible Visible Light Transmittance of Front Windscreen AGB: \_\_\_\_\_ % and Windows \_\_\_\_\_ % on vehicle(s) to which the application applies.  
 Requirements: Dual external rear vision side mirrors YES  NO  Other: \_\_\_\_\_

\_\_\_\_\_  
Transport Commissioner Date (DD/MM/YYYY)

(2)

FORM C

[385/2020].

  
**Ministry of Works and Transport**  
**Transport Division**  
**APPLICATION FOR TINTED WINDOW EXEMPTION**  
**(GENERAL – INDIVIDUALS)**  
**Motor Vehicles and Road Traffic (Windscreen and Window Tint) Regulations, 2020**

The **Motor Vehicles and Road Traffic (Windscreen and Window Tint) Regulations, 2020** provides that the front windscreen must have at least 70% visible light transmittance (VLT), the anti-glare band (AGB) on the front windscreen (650 or 15cm) at least 35% VLT, the front windows at least 35% VLT and the rear windows including the rear windscreen at least 20% VLT. The Regulations provide for an exemption on the grounds of the use of the vehicle and the safety of its occupants. An exemption certificate, if issued, is the property of the Transport Division (Licensing) and shall be present in the vehicle at all times. On the sale, transfer of ownership, destruction of the vehicle or death of the certificate holder, the exemption certificate will immediately become void and must be surrendered to the Transport Division (Licensing).

**Directions:** Please complete form in BLOCK Letters and TICK as appropriate. The completed application must be returned with a certified copy of the motor vehicle(s) registration in respect of each vehicle listed for section 4 and the previous exemption certificate issued (if applicable) to the Transport Division for processing.

**Section 1: Applicant/Registered Owner Information**

Applicant Name: \_\_\_\_\_  
(Surname, First name)

Date of Birth: (DDMM/YYYY) \_\_\_\_\_ LD.  / D.P.  / PASSPORT #  \_\_\_\_\_

Address (Street): \_\_\_\_\_

Address (Town/City): \_\_\_\_\_

Mailing Address (if different from above)(Street): \_\_\_\_\_

Address (Town/City): \_\_\_\_\_

Telephone Number: ( ) \_\_\_\_\_ - \_\_\_\_\_ Email Address: \_\_\_\_\_

**Grounds of Application: (Attach written justification on additional sheets if necessary)**

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

**Section 2: Employment Information**

Job Title/Profession/Occupation: \_\_\_\_\_  
**(If self-employed please complete section 3)**

Name of Employer - Organisation/Company/Business: \_\_\_\_\_

Organisation/Company/Business Registration Number: \_\_\_\_\_

Address of Employer (Street): \_\_\_\_\_

Address of Employer (Town/City): \_\_\_\_\_

Telephone Number: ( ) \_\_\_\_\_ - \_\_\_\_\_ Email Address: \_\_\_\_\_

**Certification by Employer:**

I \_\_\_\_\_ certify  
(Surname, First name)

that the applicant is an employee or officer holding the position/job title of \_\_\_\_\_  
in our organisation/company/business and hereby recommend  / do not recommend  that the applicant be  
considered for an exemption certificate on the grounds stated above.

Name of Head of Organisation/Company/Business \_\_\_\_\_ Signature \_\_\_\_\_ Date: (DDMM/YYYY) \_\_\_\_\_

**Section 3: Business information for self-employed persons:**

Name of Company/Business: \_\_\_\_\_

Company/Business Address (Street): \_\_\_\_\_

Company/Business Address (Town/City): \_\_\_\_\_

Company/Business Registration Number: \_\_\_\_\_

Telephone Number: ( ) \_\_\_\_\_ - \_\_\_\_\_ Email Address: \_\_\_\_\_

\_\_\_\_\_

Name (Surname, First name) \_\_\_\_\_ Signature \_\_\_\_\_ Date: (DDMM/YYYY) \_\_\_\_\_

(1) JOVER

**FORM C—Continued**

**Section 4: Vehicle Information**

List vehicle(s) for which this exemption certificate has been requested. (Attach additional sheets if necessary)

Vehicle #1 - Vehicle Registration Number	Chassis/VIN Number	Make	Model	Colour
Vehicle #2 - Vehicle Registration Number	Chassis/VIN Number	Make	Model	Colour

**Declaration of Applicant:**

I, \_\_\_\_\_, hereby declare that the information provided above is true and correct and hereby apply for an exemption certificate on the grounds stated herein.

Signature of Applicant/Registered Owner

Date (DD/MM/YYYY)

NOTE: (1) It is an offence under section 94 of the Motor Vehicles and Road Traffic Act, Chap. 48:50 to give any particulars which are not correct and you will be liable to prosecution if you do so.  
(2) Application must be supported by documents as proof of address such as a recent Utility Bill or in the case of a rental, a copy of the Lease/Rental Agreement for the rental premises identified and bearing the name of the Applicant. If the utility bill or Lease/Rental Agreement is not in the Applicant's name, a letter from the owner confirming the Applicant's residence and copy of the owner's national identification (ID) MUST be submitted.  
(3) If the Applicant is a Company, the application must be supported by Company validation documents such as a copy of the company/business registration certificate and/or Notice of Directors.  
(4) Application must be supported by a certified copy of the motor vehicle(s) registration in respect of each vehicle listed for section 4 of this application and the previous exemption certificate issued (if applicable).



**For Official Use Only:**

Supporting documentation provided:

- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_

**Application:**

Approved

No. of Vehicles

Denied

No. of Vehicles

**Term of Exemption: TWO (2) YEARS**

Date of Issue: \_\_\_\_\_

Expiration Date: \_\_\_\_\_

**Exemption Details:**

Permissible Visible Light Transmittance of Front Windscreen AGB \_\_\_\_\_ % and Windows \_\_\_\_\_ % on vehicle(s) to which the application applies.

Requirements: Dual external rear vision side mirrors YES  NO  Other: \_\_\_\_\_

Transport Commissioner

Date (DD/MM/YYYY)

**MOTOR VEHICLES AND ROAD TRAFFIC  
(PERSONS WITH DISABILITY PARKING PERMIT)  
REGULATIONS**

ARRANGEMENT OF REGULATIONS

**REGULATION**

1. Citation.
2. Interpretation.
3. Application for disability permit.
4. Disability parking permit for vehicles transporting persons with a disability.
5. Appeal on refusal to grant a disability parking permit.
6. Register for disability parking permits.
7. Restrictions on the use of a disability parking permit.
8. Validity of a disability parking permit.
9. Display of a disability parking permit.
10. Lost or stolen disability parking permit.
11. Cancellation of a disability parking permit.
12. Circumstances in which a disability parking permit is to be returned to the Licensing Authority.

**SCHEDULE I.**

**SCHEDULE II.**

**SCHEDULE III.**

[Subsidiary]

[66/2024].

**MOTOR VEHICLES AND ROAD TRAFFIC  
(PERSONS WITH DISABILITY PARKING PERMIT)  
REGULATIONS**

*made under section 100 and subject to negative resolution  
of Parliament*

Citation.

**1.** These Regulations may be cited as the Motor Vehicles and Road Traffic (Persons With Disability Parking Permit) Regulations.

Interpretation.

**2.** (1) In these regulations—

“assistive devices or assistive products” mean any product, produced or generally available, that is used by or for persons with disability for participation, measurement or substitution of body functions or structures and activities support, training, prevention or impairment, activity limitations or participation restrictions;

“applicant” means a person who applies for a disability parking permit under regulation 3;

Ch. 48:50.

“constable” has the meaning assigned to it under section 80 of the Motor Vehicles and Road Traffic Act;

“disability parking permit” means a permit issued or renewed by the Licensing Authority under regulation 4;

“disability parking zone” means a parking facility with an official International Symbol of Access having specifications illustrated in Schedule I and designated for exclusive use by a person with disability;

“person with disability” means a person whose mobility is limited as a result of—

- (a) a long-term permanent disability or clinically recognisable medical condition; or
- (b) any other physical disability or debilitating impairment,

to the extent that—

- (c) the person is unable to propel himself without the aid of a wheelchair or walker, or a

combination of both or a crutch, a cane, a leg brace or a leg prosthesis or any other assistive devices or assistive products for persons with disability; or

(d) the person—

- (i) requires the daily use of a device to assist with breathing;
- (ii) has a significant cardio-pulmonary condition, which results in severe shortness of breath with minimum physical activity;
- (iii) has a severe neuro-muscular or skeletal condition, and because of any of the conditions described in paragraph (i) or (ii) is limited in mobility to fifty metres or less in outdoor weather conditions; or
- (iv) is visually impaired;

“International Symbol of Access” means the symbol with specifications as illustrated in Schedule I, used to indicate the features of buildings and road parking facilities that may be used by a person with disability.

(2) A long-term permanent disability or clinically recognisable medical condition applicable to a person with disability under these Regulations shall include a medical condition specified in Schedule II.

**3.** (1) A person who is desirous of obtaining or renewing a disability parking permit, shall submit an application to the Licensing Authority and pay the fee specified in Schedule III.

Application for  
disability  
permit.

(2) An application for a disability parking permit by a person with a permanent disability is exempt from the requirement to pay the fee specified in Schedule III.

(3) An application under subregulation (1) and certificate issued by the medical practitioner under regulation 4(1), shall be in a form approved by the Licensing Authority.

Disability  
parking permit  
for vehicles  
transporting  
persons with a  
disability.

4. (1) The Licensing Authority may issue or renew a disability parking permit to a person with disability, only where a medical practitioner certifies on the approved form, that the applicant is a person with disability and specifies the anticipated length of time that the immobility is expected to continue, if known.

(2) The Licensing Authority may issue a disability parking permit to a visitor in Trinidad and Tobago, if the visitor establishes to the satisfaction of the Licensing Authority that the visitor is the holder of a—

- (a) valid driver's licence; or
- (b) valid parking permit or number plate bearing the International Symbol of Access, issued by the home territory of the visitor.

(3) The Licensing Authority may issue or renew a disability parking permit to any entity, organisation or corporation, in respect of a number of vehicles that are owned or leased by, or operated on behalf of the entity, organisation, or corporation primarily to provide transportation services to persons with disability.

(4) A disability parking permit issued or renewed under this regulation shall—

- (a) be in the form approved by the Licensing Authority;
- (b) subject to regulation 8, be for such duration and subject to such conditions as the Licensing Authority determines; and
- (c) be displayed in a motor vehicle that is parked in a disability parking zone, only when transporting a person with disability.

(5) An approved form certified under subregulation (1), shall be submitted to the Licensing Authority within a period of three months from the date of examination as specified in the certificate by the medical practitioner.

(6) Where an application for a disability parking permit under this regulation is in respect of a child, the parent, guardian or person with responsibility for the child shall complete the application and tender all relevant documents.

5. A person whose application for the grant of a disability parking permit is denied, may within twenty-eight days from the date of being notified, appeal in writing, the decision of the Licensing Authority to the Board.

Appeal on refusal to grant a disability parking permit.

6. (1) The Licensing Authority shall establish and maintain a register to be known as “the Disability Parking Permit Register” in which shall be recorded—

Register for disability parking permits.

- (a) the name and address and other contact details of holders of a disability parking permit;
- (b) the disability with which the holder was diagnosed;
- (c) the duration and conditions of use of the disability parking permit; and
- (d) such other particulars as determined by the Licensing Authority.

(2) Where there is a change of information as recorded in the register under subregulation (1)(a), the holder of the disability parking permit shall, within twenty-one days from the date of the change, notify the Licensing Authority of the occurrence.

(3) A register under subregulation (1), may be established and maintained in an electronic format.

7. (1) A person who—

- (a) is not the holder of a disability parking permit, shall not stop, leave, stand or park a vehicle, in a disability parking zone, unless that person is transporting a person who is the holder of a disability parking permit; or

Restrictions on the use of a disability parking permit.

(b) has a disability parking permit that is cancelled or expired, shall not display, cause or allow to be displayed the cancelled or expired disability parking permit, in a vehicle that is parked in a disability parking zone.

(2) A person shall not destroy, mutilate, deface or alter in any way a disability parking permit.

(3) A person who contravenes this regulation or any condition as registered in the register for the use of a disability parking permit, commits a traffic violation and is liable to a fine of five thousand dollars.

Validity of a  
disability  
parking permit.

**8.** (1) Subject to subregulation (2), a disability parking permit issued under regulation 4 shall, unless previously suspended or cancelled, be valid for a period—

- (a) of four years, where a medical practitioner certifies the immobility as permanent;
- (b) not exceeding six months, where the immobility is temporary;
- (c) not exceeding ninety days, where the applicant is a visitor to Trinidad and Tobago; or
- (d) not exceeding four years, if issued to an entity, organisation or corporation pursuant to regulation 4(3).

(2) An application for renewal of a disability parking permit under subregulations (1)(a), (b) and (d), may be submitted to the Licensing Authority by the applicant within a two-month period prior to the expiration of the permit.

Display of a  
disability  
parking permit.

**9.** (1) A person issued with a disability parking permit shall display the disability parking permit in, or on a vehicle in such place and in such manner as directed by the Licensing Authority.

(2) A constable may, at any time, require the holder of a disability parking permit to present his permit for inspection.

(3) A person who contravenes subregulation (1), commits a traffic violation and is liable to a fine of two thousand dollars.

**10.** (1) Where a disability parking permit is—

- (a) lost or stolen; or
- (b) mutilated, defaced, altered or has become illegible,

Lost or stolen  
disability  
parking permit.

the holder of the disability parking permit shall as soon as is practicable, thereafter, notify the Licensing Authority of the occurrence.

(2) Where a disability parking permit is lost or stolen, mutilated, defaced, altered or has become illegible, the Licensing Authority may, where an application is made and the applicable fee specified in Schedule III is paid, issue a duplicate disability parking permit to the applicant.

**11.** (1) The Licensing Authority may suspend or cancel a disability parking permit if the Licensing Authority is satisfied that the holder of the permit—

Cancellation of  
a disability  
parking permit.

- (a) has contravened any condition upon which the permit is issued; or
- (b) made any false statement in his application for the permit.

(2) The Licensing Authority shall, prior to suspending or cancelling a disability parking permit under subregulation (1), give the holder of the permit written notice of its intention to suspend or cancel his permit after fourteen days from the date that the notice was served.

(3) Where the Licensing Authority suspends or cancels a disability parking permit under subregulation (1), the Licensing Authority shall inform in writing the holder of the permit of its decision.

(4) Where a holder of a disability parking permit is aggrieved by the decision to suspend or cancel his disability

parking permit, the holder of the disability parking permit may, within twenty-eight days of receiving the notice under subregulation (3), appeal in writing, the decision of the Licensing Authority to the Board.

Circumstances in which a disability parking permit is to be returned to the Licensing Authority.

**12.** (1) A disability parking permit shall become invalid in any of the following circumstances:

- (a) upon the death of the holder of the disability parking permit;
- (b) upon expiration of the disability parking permit by effluxion of time;
- (c) in the case of a permit issued to an entity, organisation, or corporation, where the entity, organisation, or corporation has ceased to exist or the entity, organisation, or corporation no longer transports persons with a disability;
- (d) where a permit becomes illegible, mutilated or damaged; or
- (e) upon the voluntary surrender of the permit by the holder.

(2) Where a disability parking permit becomes invalid under subregulation (1)(b), (c), (d) or (e), the holder of the permit shall, within fourteen days of the occurrence, return the permit to the Licensing Authority.

(3) A person who contravenes subregulation (2), commits a traffic violation and is liable to a fine of two thousand dollars.

**SCHEDULE I**

Regulation 2.

**SPECIMEN OF THE INTERNATIONAL SYMBOL OF ACCESS**



\* Stroke width:  
Minimum = 3 inches  
Special = 4 inches

Note: Blue background and  
white border are optional

Regulation 2(2).

## SCHEDULE II

Long-term permanent disability or clinically recognisable medical conditions applicable to a person with disability shall include—

- (a) Blindness;
- (b) Cerebral palsy;
- (c) Chromosomal or syndromic conditions;
- (d) Deafness or hardness of hearing;
- (e) Upper or lower limb amputations;
- (f) Motor neurone disease;
- (g) Neurodegenerative disorders;
- (h) Neuromuscular conditions;
- (i) Paraplegia, quadriplegia or other type of paralysis; or
- (j) Heart or lung disease.

Regulations 3  
and 10.

## SCHEDULE III

Fees for the issue, renewal or a duplicate disability parking permit are as follows:

- |  |        |          |
|--|--------|----------|
| (a) disability parking permit (Individual)                             | ...    | \$150.00 |
| (b) disability parking permit (Visitor)                                | ...    | \$150.00 |
| (c) disability parking permit (entity,<br>organisation or corporation) | ... .. | \$200.00 |
| (d) duplicate disability parking permit                                | ...    | \$75.00  |